



March 31, 2017

TFRRADYN

Mr. Ben Smith, AICP, Planning Director Town of Windham Planning Department 8 School Road Windham, ME 04062

<u>Preliminary Subdivision & Site Plan Application Additional Materials: Highland Views</u> <u>Manufactured Housing Park & Mixed Use Development</u>

On behalf of Chase Custom Homes & Finance, we are pleased to submit revised plans and information in support of the Preliminary Subdivision & Site Plan Applications for the Highland Views project – a 24 unit manufactured home park and 10 mixed development units. The mixed development units consist of self-storage units on the ground floor with apartments located above. As a reminder, the development parcel is located on the north side of Route 302 at 19 Roosevelt Trail, just west of the Town of Windham/Town of Falmouth & Town of Windham/City of Westbrook town lines. The property is shown as lots #63 & 66 on the Town of Windham Tax Map #7. The 38.3 acre property is located within the Commercial 3 Zone (C-3). Approximately 15 acres of the site is located within the Manufactured Housing Park Overlay Zone (MHPO). The standard net residential density for the C3 Zone is 1 lot or unit per 60,000 SF. The net residential area calculation shows that the area outside of the MHPO Zone can support 10 units. The area within the MHPO Zone is located approximately 300' from the Route 302 property line. The MHPO Zone allows homes to be constructed at a density of 1 home per every 20,000 SF when served by a shared septic system. Manufactured Home Park roads have a minimum right of way width of 23' with a minimum road surface width of 20'. They must have a 50' buffer around the perimeter when abutting residential property. Half of the buffer width must be landscaped.

The Planning Board reviewed the Preliminary Plan application at the January 9, 2017 meeting. We also held a site walk with the Board and abutters on November 12, 2016. Since that time, we have worked with Town staff to solve all of the technical issues. Attached to this cover letter, you will find two rounds of comments & responses with the town engineer. A public hearing was held on the 9th but the meeting was improperly noticed so the board decided to hold another public hearing at our next meeting date.

The plan is generally the same as the one presented at the previous meeting other than some small technical changes brought about the Town review of the project. At the suggestion of the planning board, we examined the intersection of Bailey's Way to ensure that modular home delivery vehicles could negotiate the turn. As a result, we significantly increased the radii at the entrance of Bailey's Way.

The site will be served by public water, a common subsurface septic system and underground power. A water main is located within the Route 302 right of way and it feeds a hydrant that is located right in front of the site. Portland Water District have signed off of our water design and provide us with an ability to serve letter. A new fire hydrant will be constructed at the intersection

of the internal park roads in the location requested by the Fire Chief at the Staff Review Meeting. An engineered septic system will be needed due to the estimated flow. We previously provided a hydrogeologic assessment of the septic system and have attached an updated study that included additional information requested by the town engineer.

Detailed stormwater calculations have been provided that show that the Town's water quantity and quality stormwater regulations are being met by the combination of a gravel wetland, an underdrained filter basin, forested buffers, rain gardens and roof drain filters. We prepared phosphorus export calculations as required by MDEP regulations. The project does not exceed its phosphorus budget due to the extensive use of a variety of BMPs. We have previously provided some introductory literature about gravel wetlands that was produced by the University of New Hampshire Stormwater Center, per request of the Board.

We have provided an updated Traffic Analysis that was prepared by Traffic Solutions and includes revisions requested by the town engineer. The entrance of the development will be aligned with Land of Nod Road. The sight distance exceeds the required amount.

We presented a building elevations and discussed the adherence to the Commercial District Design Standards. The board members expressed their collective belief that the building elevations, landscaping & lighting met the design standards.

We met with representatives of the Highland Lake Watershed Association in-mid January and presented the project to the president, vice president & a member who was a professional civil/environmental engineer. We talked about the stormwater system in depth. I explained the different BMPs, how they generally worked and the maintenance & inspection guidelines for each. I explained the Manufactured Park Overlay regulations and how our design was significantly below the allowable number of lots. At the end of the meeting, the members expressed a general sentiment that the stormwater and engineering of the project was completed to an appropriate level. Their main concern was the access to Highland Lake that was located on the Falmouth portion of the property. They were concerned that the project would result in an expanded beach area, lake side parking area or dredging of the lake. I explained that although no work has been proposed for the Falmouth parcel, the applicant simply wanted to preserve his rights to the access. It was my belief that dredging of the lake would not be permit-able by the MDEP in this location. Any sort of lake front development would need to go through the planning board process in Falmouth and a land owner's ability to develop within the shoreland zone is extremely limited. I further explained that any sort of development of the Falmouth parcel would be extremely difficult & unlikely due to a large significant wetland system that encumbers most of the Falmouth property. The wetland has its own non-disturbance buffer surrounding it. I left a complete set of plans & stormwater calculations with their engineer. He reviewed the material and provided us with some basic comments that I subsequently responded to.

We are requesting a waiver of the High Intensity Soil Survey. This items was discussed at the previous sketch plan & the initial preliminary plan presentation. The board generally spoke in favor of granting the waiver. The town engineer has suggested that the waiver request is reasonable. This item is a requirement of the Preliminary Subdivision Application. High Intensity Soil Surveys provide information related to the septic suitability of the soils. They can also be used to identify the runoff characteristics of the existing watershed soils, but are usually only required for large developments. The available Medium Intensity Soil Survey will be used for the



basis of the existing soil conditions for the stormwater calculations. A licensed site evaluator will provide test pits in the proposed septic disposal areas that will be used to design the systems. A High Intensity Soil Survey would not add any valuable information to the design of the project. Therefore, we ask the board to grant a waiver.

The following items previously submitted as required by the Preliminary Subdivision & Site Plan Application procedures:


- Preliminary Major Subdivision Application
- Major Site Plan Application
- Preliminary Subdivision Application Fee (\$5,500)
- Review Escrow Fee (\$4,000)
- Property Deeds
- · Certificate of Good Standing
- Hydrogeologic Assessment
- Traffic Analysis
- Stormwater Report
- Commercial District Design Standards
- Gravel Wetland Literature
- Building Elevations
- Cost Estimate & Proof of Financial Capacity to be submitted under separate cover

The following items are attached as required by the Preliminary Subdivision & Site Plan Application procedures:

- Attachment A: Waiver Request Form
- Attachment B: Comment Response to Town Engineer from February 2017 that includes
 - Ability to serve letter from PWD
 - An AutoTURN exhibit that shows a fire truck turning movement around the culde-sac.
 - Amended traffic study
 - o Amended Hydrogeological Assessment
 - Highland Views Stormwater Report
- Attachment C: Comment Response to Town Engineer from March 2017



We are hopeful that this application can be placed on the agenda for the April 24, 2017 Planning Board Meeting. Thank you for your consideration, and please call me if you have any questions as you review the enclosed plans and information.





TOWN OF WINDHAM SUBDIVISION & SITE PLAN APPLICATION

Performance and Design Standards Waiver Request Form

(Section 808 – Site Plan Review, Waivers) (Section 908 – Subdivision Review, Waivers)

For each waiver request from the <u>Performance and Design Standards</u> detailed in Section 811 or Section 911 of the Town of Windham Land Use Ordinance, as applicable, please submit a separate completed copy of this waiver request form.

Subdivision or Project Name: Highland Views

Tax Map: 7 Lot: 63 & 66

Waivers are requested from the following Performance and Design Standards (add rows as necessary):

Ordinance Section	Standard	Mark which waiver this form is for
910.C.1.c.1	High Intensity Soil Survey	

a. Describe how a waiver from the standard indicated above will improve the ability of the project to take the property's pre-development natural features into consideration. Natural features include, but are not limited to, topography, location of water bodies, location of unique or valuable natural resources, relation to abutting properties or land uses. Attach a separate sheet if necessary.

A high intensity soil survey will not provide any information that will be used for this project. Stormwater Calculations will make use of the available medium intensity soil surveys for watershed analysis. All buffer soil types will be verified with test pit information. All stormwater ponds are designed using test pit datas. The soils in the septic area will be evaluated by a licensed site evaluator.

(continued next page)

Ordinance Section:	
--------------------	--

b. Will the waiver have an impact on any of the following criteria?

	Yes	No
Water or air pollution		х
Light pollution or glare		х
Water supply		х
Soil erosion		Х
Traffic congestion or safety		Х
Pedestrian safety or access		Х
Supply of parking		х
Sewage disposal capacity		х
Solid waste disposal capacity		Х
Scenic or natural beauty, aesthetics, historic sites, or rare or irreplaceable natural areas		х
Flooding or drainage issues on abutting properties		х
The Town's ability to provide the subdivision with public safety services (if subdivision)		Х

If granting the waiver will result in an impact on any of the criteria above, please provide more detail below.



February 7, 2017

Town of Windham C/O Mr. Jonathan R. Earle, P.E. 8 School Road Windham, ME 04069

Subject: Comment Response – Highland Views

Mr. Earle:

In response to the recent review provided by Jonathan R. Earle, Town Engineer for Windham, regarding the geology and stormwater review of the Highland Views project, we would like to offer the following responses:

Jonathan R. Earle Comments & Responses:

Comment 1: Water Supply. As noted in the cover letter, and ability to serve letter is needed from the Portland Water District. Will the water main extension into the development be a public or private main? If private, the maintenance of the proposed hydrant at the intersection of the internal park roads (including snow removal) would be the responsibility of the property owner.

Response: The Portland Water District has provided an ability to serve letter (see attached letter). The internal water distribution system (including the hydrants) will be private. Maintenance of the system will be the responsibility of the property owner.

Comment 2: Hydrogeologic Assessment. The analysis provided is for the 24 manufactured house lots and does not include wastewater generated from the 10 apartments to be located above the self-storage units. The applicant should verify that inclusion of the 10 apartment units meets the requirements of site plan & subdivision ordinances.

Response: Mark Cenci has provided an updated assessment that includes the apartment complex septic systems.

Comment 3: Hydrogeologic Assessment. An site plan with contour information showing the reduction of nitrate/nitrogen in the plume from the centralized subsurface wastewater disposal field should be included as part of the hydrogeologic analysis as specified in section 910 of the Subdivision Ordinance "An analysis and evaluation of the effect of the subdivision on groundwater resources. In the case of residential developments, the evaluation shall, at a minimum, include a projection of post development nitrate/nitrogen concentrations at any wells within the subdivision, or at the subdivision boundaries; or at a distance of 1,000 feet from potential contamination sources, whichever is a shortest distance."

Response: The nitrate plumes have been added to the utility plan (C-4.0).

Comment 4: Traffic. Trip generation for the proposed 10 warehouse units was 0.14 trips/unit (AM) and 0.26 trips/unit (PM). These trip factors were based on each 1,000 SF of storage space. The square footage for each unit ranges between 582 SF and 590 SF, well below 1,000 SF/unit. The trip generation for the warehouse units should be corrected to accurately reflect the proposed condition and will still remain below the 50 trips/hour threshold for a traffic impact study.

Response: Bill Bray, P.E. has revised his study to address the above comment. See attached.

Comment 5: Traffic. The site distances (looking both right and left) are noted exceed 640' in both direction. This information should be added to the approved subdivision plan.

Response: The site distances have been added to the Subdivision Plan C-1.0

Comment 6: Traffic. Additional information need to be provided indicating the number of bedrooms in the apartments above the self-storage units to verify the site's parking requirements were met.

Response: Section 812.C.2. Table 2 shows that multifamily units with two or more bedrooms require 2 spaces per unit. The 10 units require 20 spaces. It also shows that public warehousing needs at least 0.25 spaces per k.s.f. The storage units feature 5.9 k.s.f. requiring 1.5 spaces. The driveway to each storage unit is at least $18' \times 10'$, effectively bringing the total number of available parking spaces to 30. A sign will be placed on the storage unit that indicates that the driveway is only for the use of the self-storage patrons.

Comment 7: Traffic. Per the previous comment from Deputy Fire Chief John Wescott, verify that the a fire truck with a 14' ladder can make the turn off Route 302 and maneuver the site's cul-de-sac(s).

Response: The cul-de-sacs meet town road standards. We used AUTOTURN software to analyze the turning movement. The largest ladder truck in their vehicle library (44' long ladder truck) is able to make the turn.

Comment 8: Stormwater. The site results in the disturbance of greater than 1 AC and is with the NPDES MS4 urbanized area. As such, the application needs to demonstrate compliance with the Town of Windham Post Construction Stormwater Ordinance (Chapter 144).

Response: We have provided the maintenance & inspection documents as part of the updated stormwater report and have designed MDEP approved BMPs as part of the design.

Comment 9: Stormwater. As previously noted in the staff memo dated November 9, 2016, a DEP stormwater permit will be required as part of the final plan. A construction general permit will also be required prior to any soil disturbing activities.

Response: We have submitted a MDEP Stormwater Permit that includes the erosion & sedimentation control design. I don't believe that an additional construction general permit is required.

Comment 10: Stormwater. Worksheet 1 (Project Phosphorous Export) – Calculations submitted indicate post-treatment phosphorous export will be reduced to below predevelopment levels. However, the sheet indicates that there will need to be a negative compensation fee paid as part of the project. The worksheet should be revised to indicate that no compensation fee will be required for the project.

Response: The worksheet has been corrected.

Comment 11: Stormwater. Pre-development and post-development watershed plans were not included in the submission. As such, a review of the stormwater quantity calculations was not included in this review.

Response: We have provided you with a copy of the latest stormwater quantity calculations.

Comment 12: Solid Waste. The site plan shows a dumpster enclosure located near the 10 apartment units. Will this dumpster enclosure be utilized by the 24 manufactured housing lots as well?

Response: The dumpster will only serve the apartments & self-storage facility. The manufactured housing park will contract with a private waste hauler that provides curbside pickup.

Comment 13: Plans. Sheet C-1.0 – Proposed monument locations should be shown in addition to the general note provided on C-1.1.

Response: Granite monuments & iron pins have been added to the subdivision plans.

Comment 14: Plans. Sheet C-1.0 – Do the wetland impacts shown on the plan (1,985 SF) include the wetlands located in the building envelopes for lots 23 & 24?

Response: We have revised the plan to square off wetland impacts on lots 23 & 24. This will make it easier for both the homeowner and the town to understand the limits of fill.

Comment 15: Plans. Sheet C-3.0 – Is the footprint shown below (south) of the primary septic system the area to be set aside for system failure? If so, it should be labelled accordingly.

Response: We have labeled the backup septic system location on the Site, Grading & Utility plans.

Comment 16: Plans. Sheet C-3.0 – Provide a drainage schedule/table for the drainage & sewer structures, or label each individually on the plan.

Response: The stormwater structures are labeled on both C-3.0 & C-6.0. The sewer structures are labeled on both C-4.0 & C-6.0.

Comment 17: Plans. Sheet C-5.0 – Demolition notes reference the City of Westbrook and should be revised.

Response: The Demolition Plan notes have been corrected.

Comment 18: Plans. Sheet C-7.5 – Detail is labelled as storm drain manhole only. Provide additional detail or label as sanitary sewer manhole.

Response: A sewer manhole detail is shown on Sheet C-7.3.

Comment 19: Plans. Provide details for a stop sign and sanitary sewer pump station.

Response: A stop sign detail has been added to sheet C-7.1. The sewer pump station detail is shown on sheet C-7.3.

Comment 20: Waiver Request. The cover letter narrative indicates that the applicant will be requesting a waiver of the High Intensity Soil Survey. Based on the information provided and the comments above related to hydrogeologic assessment, the request for this project is reasonable. A waiver request checklist was not included and needs to be provided.

Response: Comment acknowledged

We hope that these responses addresses your concerns. Please contact me directly with additional questions or concerns.

Sincerely,

Terradyn Consultants, LLC

Jeffrey D. Amos, P.E.



January 5, 2017

Jeff Amos Terradyn Consultants, LLC P.O. Box 339 New Gloucester, ME 04260

Re: 19 Roosevelt Trail, WI

Ability to Serve with PWD Water

Dear Mr. Amos:

The Portland Water District has received your request for an Ability to Serve Determination for the noted site submitted on November 18, 2016. Based on the information provided per plans dated 1/5/17, we can confirm that the District will be able to serve the proposed project as further described in this letter. Please note that this letter does not constitute approval of this project from the District. Review and approval of final plans is required.

Conditions of Service

The following conditions of service apply:

- A new 8-inch combined service may be installed from the water main in Roosevelt Trail. The service should enter through the properties frontage on Roosevelt Trail at least 10-feet from any side property lines.
- Since the length of this service line will exceed 300-feet, a fireline meter pit will be required. The meter pit should be located on private property within 10-20 feet of the property line at Roosevelt Trail. Please note that only one meter and one bill will be associated to each domestic service line. This one master meter would be located in a common space that all tenants could gain access to if necessary.
- The existing services(SV33NW1133 and SVNW1134) will no longer be used as a result of the development and they must be retired per PWD standards. This includes shutting the corporation valve and cutting the pipe from the water main.
- Water District approval of water infrastructure plans will be required for the project prior to construction. As your project progresses, we advise that you submit any preliminary design plans to MEANS for review of the water main and water service line configuration. We will work with you to ensure that the design meets our current standards.
- Once the project is ready for construction, the owner or contractor will need to make an appointment to come in and complete a service application form and pay the necessary fees.

Existing Site Service

According to District records, the project site does currently have existing water service. A 3/4-inch copper and a 2-inch copper line provide water service to this site. Please refer to the "Conditions of Service" section of this letter for requirements related to the use of these services.

Water System Characteristics

According to District records, there is an 12-inch diameter cast iron water main in Roosevelt Trail and a public fire hydrant located 75 feet from the site. The most recent static pressure reading was 75 psi on May 3, 2016.

Public Fire Protection

The installation of new public hydrants to be accepted into the District water system will most likely not be required. It is your responsibility to contact the Windham Fire Department to ensure that this project is adequately served by existing and/or proposed hydrants.

Domestic Water Needs

The data noted above indicates there should be adequate pressure and volume of water to serve the domestic water needs of your proposed project.

Private Fire Protection Water Needs

You have indicated that this project will not require water service to provide private fire protection to the site. Please note that the District does not guarantee any quantity of water or pressure through a fire protection service.

Should you disagree with this determination, you may request a review by the District's Internal Review Team. Your request for review must be in writing and state the reason for your disagreement with the determination. The request must be sent to MEANS@PWD.org or mailed to 225 Douglass Street, Portland Maine, 04104 c/o MEANS. The Internal Review Team will undertake review as requested within 2 weeks of receipt of a request for review.


If the District can be of further assistance in this matter, please let us know.


Sincerely,

Portland Water District

Gordon S. Johnson, P.E.

Engineering Services Manager





Traffic Solutions William J. Bray, P.E. 235 Bancroft Street Portland, ME 04102 (207) 774-3603

(207) 400-6890 mobile trafficsolutions@maine.rr.com

December 3, 2016 (Revised January 26, 2017)

Traffic Assessment **Proposed Highland Views Residential Subdivision** Windham, Maine

INTRODUCTION

Chase Custom Homes & Finance are proposing a residential subdivision with 24 single-family house lots, 10 market rate apartments, and 10 self storage units on a parcel of property located on Route 302 in the Town of Windham near the Westbrook City Line. Access to the property will be provided with construction a "new" roadway intersecting U.S. Route 302 opposite Land of Nod Road.

This document determines peak hour trip generation of the proposed project during both peak commuter time periods; examines current roadway safety trends in the general vicinity of the proposed project, and conducts a review of vehicle sight distance at the proposed street entrance on U.S. Route 302.

SITE TRAFFIC

Site Trip Generation: Trip generation was determined for the proposed project based upon trip tables presented in the ninth edition of the Institute of Transportation Engineers (ITE) "TRIP GENERATION" handbook. The following trip rates were used in that effort:

Land-Use Code #151 - Mini Warehouse (Total of 6,000 sf of Combined Gross Floor Area)

Street Peak Hour - AM Peak

= 0.14 trips/1000sf gross floor area

Street Peak Hour - PM Peak = 0.26 trips/1000sf gross floor area

Street Peak Hour - AM Peak

<u>Land-Use Code #210 – Single-Family Detached Housing (24 Homes)</u> = 0.75 trips/dwelling unit

Street Peak Hour - PM Peak

= 1.00 trips/dwelling unit

Land-Use Code #220 - Apartment (10 Market Rate Apartments)

Street Peak Hour – AM Peak

= 0.51 trips/dwelling unit

Street Peak Hour - PM Peak

= 0.62 trips/dwelling unit

Table 1, as follows, summarizes the projected peak hour trip generation of the proposed project:

Table 1 Peak Hour Trips Generation Summary

Proposed Use	Number of Units	AM Peak Hour Trip Generation		PM Peak Hour Trip Generation	
		Trip Rate	<u>Trips</u>	Trip Rate	Trips
Self-Storage Units	6,000sf gross floor area	0.14 trips/1000sf	1 trip	0.26 trips/1000sf	2 trips
Single-Family Home	24 lots	0.75 trips/lot	18 trips	1.00 trip/lot	24 trips
Apartment	10 units	0.51 trips/unit	5 trips	0.62 trips/unit	6 trips
TOTAL			24 trips		32 trips

The proposed residential subdivision can be expected to generate a total of $\underline{24}$ vehicle trips in the "morning" peak hour and $\underline{32}$ trips during the "evening" peak hour.

EXISTING SAFETY CONDITIONS

The Maine Department of Transportation's (MaineDOT) Accident Records Section provided the latest three-year (2013 through 2015) crash data for the section of U.S. Route 302 between the Westbrook City Line and Pope Road, a distance of approximately 0.85 miles. Their report is summarized as follows and attached as an appendix to the report:

2013 -2015 Traffic Accident Summary

Location	Total Crashes	Critical Rate Factor
1. U.S. Route 302 @ Vance Drive	2	0.39
2. U.S. Route 302 @ Land of Nod Road	2	0.39
3. U.S. Route 302 @ Percy Hawkes Road	1	0.18
4. U.S. Route 302 @ Haven Road	1	0.18
5. U.S. Route 302 @ Pope Road	1	0.18
6. U.S. Route 302 btw Westbrook TL and Vance Dr.	1	0.12
7. U.S. Route 302 btw Vance Dr. and Land of Nod Rd.	4	0.70
8. U.S. Route 302 btw Land of Nod Rd. and Percy Hawkes Rd.	6	0.40
9. U.S. Route 302 btw Percy Hawkes Rd. and Haven Rd.	4	0.35
10. U.S. Route 302 btw Haven Rd. and Pope Rd.	2	0.21

The MaineDOT considers any roadway intersection or segment a high crash location if both of the following criteria are met:

- 8 or more accidents
- A Critical Rate Factor greater than 1.00

As the data presented in the table shows, the incidence of traffic crashes occurring on each of the noted roadway segments and intersections are below MaineDOT's threshold criteria for identification of a high crash location.

SIGHT DISTANCE

The Maine Department of Transportation's Highway Entrance and Driveway Rules require the following sight distances for a Retrograde/Mobility roadway:

Sight Distance Standards

Speed Limit	Sight Distance
25 mph	Not Applicable
30	Not Applicable
35	Not Applicable
40	580 feet
45	710 feet
50	840 feet
55	990 feet

U.S. Route 302 is currently posted at 40mph across the frontage of the proposed project site, which requires an unobstructed sightline of 580 feet. Sight distance "looking" both right and left from the proposed street entrance on U.S. Route 302 exceeds 640 feet in both directions.

CONCLUSIONS

- The proposed residential subdivision project can be expected to generate 24 trips in the morning peak hour and 32 trips during the afternoon peak commuter hour.
- The Maine Department of Transportation's most recent three-year (2013 to 2015) accident safety report, for the section of U.S. Route 302 between Pope Road and the Westbrook City Line, a distance of roughly 0.85 miles, shows the frequency of traffic crashes for all roadway intersections and segments is less than MaineDOT's threshold criteria for identification of a high crash location.
- Sightline measurements (640 feet plus) recorded at the centerline of the proposed street entrance with U.S. Route 302 exceed MaineDOT's Mobility Highway standard (580 feet) for a posted speed limit of 40mph, which reflects the current posted speed limit of U.S. Route 302 along the frontage of the proposed project site.
- A MaineDOT Highway entrance permit will be required for the proposed street entrance onto U.S. Route 302.





93 Mill Road • North Yarmouth, Maine 04097 Cell: 207.329.3524 • mark@markcenci.com www.markcenci.com



Addendum to the Hydrogeologic Assessment of the Proposed Highland Views Manufactured Housing Park Roosevelt Trail, Windham

Date: February 8, 2017

Purpose of the Assessment:

The purpose of this assessment is to predict the location and possible effects of wastewater plumes on ground water from two septic systems serving apartment buildings, not studied in the December 16, 2016 assessment, in order to meet the requirements of the Town of Windham Subdivision Ordinance.

Section 911.H. 1.b. of the Windham Subdivision Ordinance, Impact on Ground Water Quality or Quantity, stipulates, in part:

No subdivision shall increase any contaminant concentration in the ground water at any ... project boundary to more than the Primary Drinking Water Standards. No subdivision shall increase any contaminant concentration in the ground water at said locations to more than the Secondary Drinking Water Standards.

Summary:

The proposed wastewater disposal systems satisfy the Windham Subdivision Ordinance.

Information used:

Information used in this study includes library research of published literature, a plan of the project by Terradyn Consultants, soil test pit information by Mark Cenci Geologic, Inc. and a wetland delineation and analysis by Mark Cenci Geologic, Inc.

Project summary:

The two systems will serve two apartment buildings; each with 15 bedrooms. Wastewater disposal will be by on-site subsurface wastewater disposal systems. Water will be provided by the Portland Water District. Because no ground water will be withdrawn from the property, the requirements of the Ordinance regarding ground water quantity are met.

The wastewater disposal areas will each have a design flow of 1,350 gallons per day. The disposal areas will be Eljen Indrain systems comprised of 75 units. It will be constructed in an array of 5 rows of 15 units and will be 19' x 60' in size.

Summary of geology:

The site is located on the lower, easterly facing slopes of a northerly trending ridge between Milliken Hill and Jones Hill (see Figure 1 of 12/16/16 assessment). The average surface slope across the property is 4%. Drainage is easterly and southeasterly to Highland Lake via wetlands associated with the lake.

Michael J. Ratelle depicts the surficial geology of the area as glacial till on the *Surficial Geology* of the Cumberland Center Quadrangle, Maine (see Figure 2 of 12/16/16 assessment).

The site is not mapped as a significant surficial aquifer by Craig D. Neil on the Significant Sand and Gravel Aquifers of the Cumberland Center Quadrangle, Maine.

Wetlands are mapped on the site on the *National Wetlands Inventory* (see attached photomap of 12/16/16 assessment). The wetlands are classified as Palustrine forested and scrub-shrub. This mapping agrees with on-site wetlands delineation, however, there are also emergent wetlands on the site.

The site is depicted as an association of Paxton very stony fine sandy loam, Woodbridge fine sandy loam, Scantic silt loam, Ridgebury fine sandy loam and Sebago mucky peat on the *National Cooperative Soil Survey* (see attached photomap and descriptions of 12/16/16 assessment). This mapping generally agrees with the published surficial geology and wetland mapping, in addition to on-site soil testing.

Hydrogeology:

The source of ground water on this site is precipitation. Precipitation falling on this site seeps into the soil and descends until restrictive soil layers or the water table is encountered. Thereupon, the flow of ground water is down gradient toward the wetlands bordering the southwestern side of Highland Lake.

At both disposal areas the soils are medium to coarse sands. Slopes are gentle. Recharge is above average at these sites. The ground water flow directions on this property can be discerned from topography.

An estimated hydraulic conductivity of the soil is estimated to be 40 feet per day, based on soil test pits and published geologic information. The hydraulic gradient is assumed to be 0.01 (1%), based on the surface slopes. The background concentration of nitrate-nitrogen in ground water is assumed to be minimal, as this is a wooded site.

Impact on groundwater quality:

Secondary Drinking Water Standards are not an issue with this project. Nitrate-nitrogen is the chemical to assess for impact on ground water. Nitrate-nitrogen is generated by subsurface wastewater disposal systems. It is a conservative contaminant, meaning it does not readily degrade in ground water, nor does it attenuate or attach itself to soil particles. Nitrate-nitrogen is limited to 10 mg/liter in public drinking water supplies by the Primary Drinking Water Standard. The accepted practice for the analysis of impacts on ground water quality is to estimate the concentration of NO3-N in ground water at the downgradient property line of the project.

The analysis of nitrate-nitrogen impacts was calculated by SOLUTRANS, a 32-bit Windows program for modeling three-dimensional solute transport written by Dr. Charles R. Fitts of Fitts Geosolutions and the University of Southern Maine. The program is based on the analytical solutions of Liej *et. al.* (1991 and 1993). The solutions in SOLUTRANS all assume a uniform one-dimensional flow field, and allow three-dimensional dispersion, retardation and first-order decay. The model is not a dilution/mass balance model, so the requirement that drought conditions be assumed is met.

Variables entered into the calculations that are site specific include an estimated seepage velocity of 1.6 feet per day, and a hydraulic gradient of 1%. Other assumed variables include a porosity of 30%, an initial wastewater concentration of 40 mg/liter NO3-N, retardation of 1, a decay constant of zero and longitudinal, lateral and vertical dispersivities of 9 feet, 3 feet and 0.3 foot respectively.


Calculations were made and reveal the 10 mg/liter NO3-N plume will be approximately 50 feet in length. A plot of the concentration versus distance curve is enclosed. Using the inferred ground water flow direction, the calculated 10 mg/liter NO3-N isocon lines were drawn on the plan of the project by Mark Cenci Geologic, Inc. and forwarded to Terradyn Consultants. All plumes will eventually filter through wetland soils before seeping into Highland Lake.

Conclusions:

The proposed development of two, 15 bedroom apartments on this parcel meets the standards of the Town of Windham Subdivision Ordinance, with regard to ground water quality. Ground water quantity is not as issue, as the project is served by public water.

Mark Cenci, Certified Maine Geologist #467

Concentration of NO3-N versus Distance from Disposal Area





STORMWATER MANAGEMENT PLAN

Highland Views Windham, Maine

The following Stormwater Management Plan has been prepared for the Highland Views Project to evaluate stormwater runoff and erosion control for the proposed 24 unit manufactured housing park and 10 unit mixed use development located at 19 Roosevelt Trail, in Windham, Maine.

Site Calculations

Total Property Area	38.3 Ac (+/-)
Existing Impervious Area	0.67 Ac
Re-Development Area	0.39 Ac
Total Project Impervious Area	3.37 Ac
Total New Impervious Area	2.98 Ac
Total Developed Area	8.04 Ac

Existing Conditions

The development parcel is located on the north side of Route 302 at 19 Roosevelt Trail, just west of the Town of Windham/Town of Falmouth & Town of Windham/City of Westbrook town lines. The site contains the remnants of an old RV campground. There are a series of paved and gravel roads that run through the site. There are numerous camp sites throughout. The site is located just upstream of Highland Lake. Highland Lake is identified as a lake watershed most at risk by the Maine DEP. A copy of the composite U.S.G.S. Quadrangle Map (North Windham) is attached to this submittal.

The developed area generally drains into a large forested wetland that lies between the site & Highland Lake. The onsite slopes are generally between 3%-5%. There is a man-made ditch that runs along the outer edge of the park that diverts offsite runoff around the developed area and to Highland Lake. The outlet of the man-made ditch and the forested wetland are modeled as Study Point #1 and Study Point #2, respectively in the attached stormwater calculations.

Proposed Development

The applicant proposes to create a 24 unit manufactured housing park as well as a 10 unit mixed use development that will be composed of ground floor self-storage units with apartments located above.

Much of the existing development will be removed during construction.

Flooding

The development area is not located within an area of flood hazard according to the Federal Insurance Rate Maps 230045 0006 B, 230045 0010 B, 230054 0001 B & 230189 0030 B. See attached map.

Modeling Assumptions

The onsite stormwater facilities were sized utilizing the USDA Soil Conservation Service (SCS) TR-20 Runoff Simulation Model, as contained in the HydroCAD computer software program (Version 9.0). Runoff curve numbers were determined for each direct watershed by measuring the area of each hydrologic soil group within each type of land cover. Weighted curve numbers were then calculated using curve numbers for various cover types and hydrologic soil groups, assuming "good" conditions as defined in U.S Soil Conservation Service (SCS) publications. Times of concentration and travel times were determined from site topographic maps in accordance with SCS procedures. A maximum length of 150 feet was used for sheet flow.

All of the watersheds' peak runoff rates were analyzed for the 2, 10, and 25-year frequency, 24-hour duration storm events. A Type III rainfall distribution was applied to these storms. The rainfall amounts for Cumberland County are as follows:

Storm Frequency Precipitation (in./24 hr)			
2-year 3.1			
10-year	4.6		
25-year	5.8		

Onsite Soils

The soils were delineated from the Cumberland County Medium Intensity Soil Survey as shown on the Soil Data Viewer on the NRCS website (See attached map). The soil survey reports the watershed soils are generally hydrologic group C soils with relatively small inclusions of group B soils. We've taken the conservative approach of modeling all non-wetland soils as HSG C soils and all wetlands as HSG D. See attached map.

Water Quantity (Flooding Standard)

The following table summarizes the results of stormwater calculations for the design storm events for the project areas. Calculations and computer modeling sheets are provided with this report.

Table 1 - Stormwater Runoff Summary Table Pre-Development vs. Post-Development						
Study	Study 2Yr/24Hr (cfs)		10Yr/24Hr (cfs)		25Yr/24Hr (cfs)	
Point #	Pre	Post	Pre	Post	Pre	Post
1	21.2	20.4	48.1	48.0	72.1	72.0
2	9.4	7.3	21.4	19.9	32.1	31.8

As the above result table shows, the post-development flow rates for the 2, 10, and 25-year/24 hour design storm events do not exceed the pre-development conditions.

Water Quality (Phosphorus Export Calculations)

Best Management Practices (BMPs) will be implemented to reduce the impacts of site development on downstream water quality. The property is located in the Highland Lake Watershed. Highland Lake is identified by the MDEP as a lake most at risk from development.

Highland Lake Watershed

The allowable per acre allocation of phosphorus export for the portion of the site that is within the Highland Lake Watershed is 0.027 lbs/acre of developable land. There are approximately 38.3 developable acres within the Town of Windham that have an associated allocation of 1.034 9lbs/year of allowable phosphorus export. The applicant also owns 15.02 acres adjacent to the property within the Town of Falmouth that has an associated allocation of 0.062 lbs/year of allowable export. The total amount of allowable export is 1.10 lbs/year. Note: We spoke to Jeff Dennis of MDEP & he advised us to use the Windham allocation of 0.027 lbs/acre for the Falmouth property. Falmouth does not have an allocation and he believed that the Windham allocation would be conservative. See attached NWI Map.

A worksheet that summarizes the phosphorus export has been included in the calculations. An oversized gravel wetland, an oversized underdrained filter basin, a rain gardens, extensive use of roof drain filters and the removal of untreated existing infrastructure were used to reduce the total expected phosphorus export to 1.08 lbs/year. This value is equal to the allocated amount. Calculations have been provided detailing the water quality volume derivations for the gravel wetland.

Housekeeping and Maintenance & Inspection guidelines are attached to this report.

BMP Sizing

Roof Dripline Filter Bed

We propose to provide treatment for the rear half of the roof for each of the 24 manufactured homes. The bed is required to provide volume for 1" of runoff from the contributing area and store it within a reservoir bed. The bed sizing is as follows:

Area of Watershed: = 291 SF

Treatment Volume Required: Area x runoff depth: 291 SF x 1/12 FT = 24.25 CF

Bed Sizing:

Porosity = 40% Bed Length = 21' Bed Width = 3' Bed Depth = 1.5

Available Volume= $21' \times 3' \times 1.5' \times 0.40 = 37.8 \text{ CF}.$

The design is adequate since the available volume exceeds the required volume. The filter strips meet the standard sizing criteria and will have a corresponding treatment factor of 0.4.

Filtration Basin

STAGE	AREA	STORAGE
(FT)	(SF)	(CF)
205.5	4200	0
206	4627	2207
207	5480	7260
208	6333	13167
208.5	6760	16440

WATERSHED IMPERVIOUS AREA=

WATERSHED LANDSCAPED AREA=

REQUIRED WATER QUALITY VOLUME=

REQUIRED WATER QUALITY VOLUME=

TREATMENT FACTOR=

31,374

SF

57,272

SF

CF (No Pre-Treatment)

CF (With Pre-Treatment)

0.25 (0.25 Max)

The required water quality volume was calculated by multiplying the impervious area by 1.0" and the landscaped area by 0.4".

Gravel Wetland

Forebay

STAGE	AREA	STORAGE
(FT)	(SF)	(CF)
193	900	0
194	1300	1100
194.5	1500	1800

Cell #1

STAGE	AREA	STORAGE
(FT)	(SF)	(CF)
193	4350	0
194	5117	4733
194.5	5500	7388

Cell #2

STAGE	AREA	STORAGE
(FT)	(SF)	(CF)
193	5300	0
194	6033	5667
194.5	6400	8775

Total Pond

STAGE	AREA	STORAGE
(FT)	(SF)	(CF)
193	10550	0
194	12450	11500
194.5	13400	17963
194.51	13800	17963
195	14046	24638
196	15773	39547
197	17500	56425

WATERSHED IMPERVIOUS AREA=	89000	SF
WATERSHED LANDSCAPED AREA=	121000	SF
REQUIRED WATER QUALITY VOLUME=	11450	CF (No Pre-Treatment)
REQUIRED WATER QUALITY VOLUME=	17963	CF (With Pre-Treatment)
TREATMENT FACTOR=	0.25	(0.25 Max)

The required water quality volume was calculated by multiplying the impervious area by 1.0" and the landscaped area by 0.4".

Forested Buffer with Level Lip Spreader

The buffer contains soils that are consistent with Soil Group C sandy loam or loamy sand. *Table 6* – *Sizing Requirements for a buffer with 0-8% slope and stone bermed level lip spreader* of Chapter 500 shows that standard sizing requires that the berm length for a forested buffer must be 75' per acre of impervious area and 25' per acre of lawn. Evaluation of the watershed shows that it contains the following:

```
Impervious area = 13,068 SF (0.30 Ac)
Lawn area = 5,000 SF (0.11 Ac)
```

Standard sizing: 75(0.30) + 0.11(25) = 22.5' + 2.9' = 25.4'. 25.4' would yield a treatment factor of 0.4.

Oversized to TF of 0.2: $BMP_{TF} = 0.4(BMP_{TF} / TF) = 0.4(25.4/0.2) = 50'$

Forested Buffer Adjacent to Residential Lot

The buffer contains soils that are consistent with Soil Group C sandy loam or loamy sand. *Table 9* – *Buffer Size Requirements Based on Soil & Vegetative Cover Types* of Chapter 500 shows that standard sizing requires that the standard length of flow path for a forested buffer to be 75'. We are proposing a buffer with a 100' long flow path which yields a treatment factor of 0.2:



SHEET DESCRIPTION

AERIAL PHOTO ADRESS, WINDHAM ME

PREPARED FOR


CHASE CUSTOM HOME AND FINANCE 19 ROOSEVELT TRAIL WINDHAM, ME 04062



P.O. Box 339 111 Elderberry Lane New Gloucester, ME 04280 Office: (207) 926-5111 Fax: (207) 221-1317 www.terradynconsultants.com

Civil Engineering - Land Planning - Stormwater Design - Environmental Permitting

JOB NO.	FIGURE
1636	2
DATE	3
9/12/16	OF
SCALE	_
1"=300'	5



PREPARED FOR

CHASE CUSTOM HOME AND FINANCE 19 ROOSEVELT TRAIL WINDHAM, ME 04062




P.O. Box 339
111 Elderberry Lane
New Gloucester, ME 04260
Office: (207) 926-5111
Fax: (207) 221-1317

CONSULTANTS, LLC Fax: (207) 221-1317
CONSULTANTS, LLC www.terradynconsultants.com

Civil Engineering - Land Planning - Stormwater Design - Environmental Permitting

1636	0
DATE	
9/10/16	OF
SCALE	_
1"=2000'	5



MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at 1:24,000. Area of Interest (AOI) С Area of Interest (AOI) C/D Warning: Soil Map may not be valid at this scale. Soils D Enlargement of maps beyond the scale of mapping can cause Soil Rating Polygons misunderstanding of the detail of mapping and accuracy of soil line Not rated or not available Α placement. The maps do not show the small areas of contrasting **Water Features** soils that could have been shown at a more detailed scale. A/D Streams and Canals В Please rely on the bar scale on each map sheet for map Transportation measurements. Rails ---Source of Map: Natural Resources Conservation Service Interstate Highways Web Soil Survey URL: http://websoilsurvey.nrcs.usda.gov C/D **US Routes** Coordinate System: Web Mercator (EPSG:3857) D Major Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Not rated or not available Local Roads \sim distance and area. A projection that preserves area, such as the **Soil Rating Lines** Albers equal-area conic projection, should be used if more accurate Background Α calculations of distance or area are required. Aerial Photography A/D This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Cumberland County and Part of Oxford County, Survey Area Data: Version 12, Sep 15, 2016 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. D Date(s) aerial images were photographed: Jun 20, 2010—Jul 18, Not rated or not available **Soil Rating Points** The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. В B/D

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
Cu	Cut and fill land	•	3.6	8.9%
PbB	Paxton fine sandy loam, 3 to 8 percent slopes	С	3.7	9.1%
PfB	Paxton very stony fine sandy loam, 3 to 8 percent slopes	С	18.8	46.4%
RbA	· · · ·		2.1	5.2%
RgA	Ridgebury very stony fine sandy loam, 0 to 3 percent slopes	C/D	0.1	0.2%
Sn	Scantic silt loam, 0 to 3 percent slopes	D	2.7	6.7%
Sp	Sebago mucky peat	A/D	1.9	4.6%
Sz	Swanton fine sandy loam	C/D	3.0	7.3%
W	Water		0.7	1.6%
WrB	Woodbridge fine sandy loam, 0 to 8 percent slopes	С	3.7	9.2%
WsB	Woodbridge very stony fine sandy loam, 0 to 8 percent slopes	С	0.3	0.7%
Totals for Area of Inte	rest		40.6	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.


Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher








Estuarine and Marine Wetland

Freshwater Emergent Wetland

1636 Wetlands Inventory Map



Riverine

Freshwater Pond

Lake

Worksheet 1 PPB calculations

<u>Project name: Highland Views</u> <u>Lake name: Highland Lake</u>

Town name: Windham

Standard Calculation

Windham Area

PAPB_	0.027	Ibs P/acre/year
TA	38.3	acres
WA	0	acres
SA	0	acres
_	0	— acres
Α	38.3	 acres
РРВ	1.0341	lbs P/year
PAPB TA WA	0.027 15.02 12.72	lbs P/acre/year acres acres
SA		
_	0	acres acres
Α	2.3	acres
PPB	0.0621	 Ibs P/year
РРВ	1.0962	
	PAPB TA WA SA PPB PPB PPB PPB PPB PPB PPB PPB PPB PP	TA 38.3 WA 0 SA 0 O A 38.3 PPB 1.0341 PAPB 0.027 TA 15.02 WA 12.72 SA 0 O O A 2.3 PPB 0.0621

Worksheet

Worksheet 2

Pre-PPE and Post-PPE Calculations

Calculate phosphorus export from development for before and after treatment
Use as many sheets as needed for each development type (commercial, roads, residential lots, etc.)

Project name: Highland Views Project Development type: Mixed Sheet #

	Land Surface Type or Lot #(s) with description	Acres or # of lots	Export Coefficient from Table 3.1 Table 3.2	Pre- treatment Algal Av. P Export (lbs P/year)	Treatment Factor for BMP(s) from Chapter 6	Post- treatment Algal Av. P Export (lbs P/year)	Description of BMPs	
	Subdivision							
WS-1				ı		ı		
	Roadway Impervious	0.164	1.25	0.205	0.25	0.05125	Gravel Wetland	
	Roadway Pervious	0.093	0.3	0.0279	0.25	0.006975	Gravel Wetland	
WS-2				ı		ı		
	Roadway Impervious	0.029	1.25	0.03625	0.25	0.0090625	Gravel Wetland	
	Roadway Pervious	0.002	0.3	0.0006	0.25	0.00015	Gravel Wetland	
	Apartment Pervious	0.046	0.3	0.0138	0.25	0.00345	Gravel Wetland	
WS-3								
	Roadway Impervious	0.026	1.25	0.0325	0.25	0.008125	Gravel Wetland	
	Roadway Pervious	0.002	0.3	0.0006	0.25	0.00015	Gravel Wetland	
	Apartment Pervious	0.034	0.3	0.0102	0.25	0.00255	Gravel Wetland	
WS-4				ı		ı		
	Roadway Impervious	0.018	1.25	0.0225	0.25	0.005625	Gravel Wetland	
	Roadway Pervious	0.001	0.3	0.0003	0.25	0.000075	Gravel Wetland	
WS-5				T		T		
	Roadway Impervious	0.046	1.25	0.0575	0.25	0.014375	Gravel Wetland	
	Roadway Pervious	0.02	0.3	0.006	0.25	0.0015	Gravel Wetland	
WS-6				T		T		
	Roadway Impervious	0.031	1.25	0.03875	0.25	0.0096875	Gravel Wetland	
	Roadway Pervious	0.042	0.3	0.0126	0.25	0.00315	Gravel Wetland	
WS-7				T		T		
	Roadway Impervious	0.034	1.25	0.0425	0.25	0.010625	Gravel Wetland	
	Roadway Pervious	0.035	0.3	0.0105	0.25	0.002625	Gravel Wetland	
WS-8				T		T		
	Roadway Impervious	0.019	1.25	0.02375	0.25	0.0059375	Gravel Wetland	
WS-9				1		1		
	Roadway Impervious	0.029	1.25	0.03625	0.25	0.0090625	Gravel Wetland	
WS-10				1		1		
	Roadway Impervious	0.035	1.25	0.04375	0.25	0.0109375	Gravel Wetland	
	Roadway Pervious	0.017	0.3	0.0051	0.25	0.001275	Gravel Wetland	
WS-11						1		
	Roadway Impervious	0.04	1.25	0.05	0.25	0.0125	Gravel Wetland	
	Roadway Pervious	0.017	0.3	0.0051	0.25	0.001275	Gravel Wetland	
WS-12								
	Roadway Impervious	0.046	1.25	0.0575	0.25	0.014375	Gravel Wetland	
	Roadway Pervious	0.018	0.3	0.0054	0.25	0.00135	Gravel Wetland	

WC 42							
WS-13	Poodway Importious	0.084	1.25	0.105	0.25	0.02625	Gravel Wetland
	Roadway Impervious						
	Roadway Pervious	0.056	0.3	0.0168	0.25	0.0042	Gravel Wetland
	Apartment Impervious	0.1	1.25	0.125	0.25	0.03125	Gravel Wetland
	Apartment Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
	Apartment Pervious	0.213	0.3	0.0639	0.25	0.015975	Gravel Wetland
WS-14							<u> </u>
	Roadway Impervious	0.103	1.25	0.12875	0.25	0.0321875	Gravel Wetland
	Roadway Pervious	0.042	0.3	0.0126	0.25	0.00315	Gravel Wetland
WS-15						1	
	Roadway Impervious	0.085	1.25	0.10625	0.25	0.0265625	Gravel Wetland
	Roadway Pervious	0.012	0.3	0.0036	0.25	0.0009	Gravel Wetland
WS-15A							
	Roadway Impervious	0	1.25	0	0.25	0	Gravel Wetland
	Roadway Pervious	0	0.3	0	0.25	0	Gravel Wetland
WS-16							
	Roadway Impervious	0.203	1.25	0.25375	0.25	0.0634375	Filter Basin
	Roadway Pervious	0.108	0.5	0.054	0.25	0.0135	Filter Basin
WS-FB							
-	Roadway Impervious	0	1.25	0	0.25	0	Gravel Wetland
	Roadway Pervious	0	0.3	0	0.25	0	Gravel Wetland
WS-GW	rtodaway i orviodo		0.0	, , ,	0.20		Oravor Worland
****	Roadway Impervious	0	1.25	0	0.25	0	Gravel Wetland
	Roadway Pervious	0	0.3	0	0.25	0	Gravel Wetland
WS-LS	Roadway Fervious	U	0.3	U	0.25	0	Graver Welland
WS-LS	Dandunu Innaniau	0	4.05	0	0.0		450H and Duffer with Lavel Consoler
	Roadway Impervious	0	1.25	0	0.2	0	150' Long Buffer with Level Spreader
	Roadway Pervious	0	0.3	0	0.2	0	150' Long Buffer with Level Spreader
	Apartment Impervious	0.233	1.25	0.29125	0.2	0.05825	150' Long Buffer with Level Spreader
	Apartment Roof	0.067	0.5	0.0335	0.2	0.0067	150' Long Buffer with Level Spreader
	Apartment Pervious	0.12	0.3	0.036	0.2	0.0072	150' Long Buffer with Level Spreader
WS-RD							T
	Apartments Roof	0.067	0.5	0.0335	0.4	0.0134	Roof Drain Filter
Lots to Gra	avel Wetland	ı ı		T		T	T
	Lot 1 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
	Lot 1 Roof	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
	Lot 1 Roof (Rear)	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
	Lot 1 Grass	0.126	0.3	0.0378	0.25	0.00945	Gravel Wetland
	Lot 2 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
	Lot 2 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
	Lot 2 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
	Lot 2 Grass	0.069	0.3	0.0207	0.25	0.005175	Gravel Wetland
	Lot 3 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
	Lot 3 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
	Lot 3 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
	Lot 3 Grass	0.126	0.3	0.0378	0.25	0.00945	Gravel Wetland
	Lot 4 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
	·	0.043	0.5	0.0085	0.25		
	Lot 4 Roof	0.017	0.0	0.0065	0.25	0.002125	Gravel Wetland

Lot 4 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 4 Grass	0.069	0.3	0.0207	0.25	0.005175	Gravel Wetland
Lot 5 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 5 Roof	0.043	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 5 Roof (Rear)	0.017	0.5	0.0085	0.16	0.002125	Gravel Wetland + Roof Filter
Lot 5 Grass	0.103	0.3	0.0309	0.10	0.007725	Gravel Wetland
Lot 6 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 6 Roof	0.043	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 6 Roof (Rear)	0.017	0.5	0.0085	0.16	0.002123	Gravel Wetland + Roof Filter
Lot 6 Grass	0.195	0.3	0.0585	0.10	0.00130	Gravel Wetland
Lot 7 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 7 Roof	0.043	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 7 Roof (Rear)	0.017	0.5	0.0085	0.16	0.002123	Gravel Wetland + Roof Filter
Lot 7 Grass	0.195	0.3	0.0585	0.16	0.00136	Gravel Wetland
		1.25		0.25		Gravel Wetland
Lot 8 Impervious	0.043	0.5	0.05375			
Lot 8 Roof				0.25	0.002125	Gravel Wetland
Lot 8 Cross	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 8 Grass	0.15	0.3	0.045	0.25	0.01125	Gravel Wetland
Lot 9 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 9 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 9 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 9 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland
Lot 10 Impervious	0.033	1.25	0.04125	0.25	0.0103125	Gravel Wetland
Lot 10 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 10 Grass	0.062	0.3	0.0186	0.25	0.00465	Gravel Wetland
Lot 11 Impervious	0.033	1.25	0.04125	0.25	0.0103125	Gravel Wetland
Lot 11 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 11 Grass	0.062	0.3	0.0186	0.25	0.00465	Gravel Wetland
Lot 20 Grass	0.07	0.3	0.021	0.25	0.00525	Gravel Wetland
Lot 21 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 21 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 21 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 21 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland
Lot 22 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 22 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 22 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 22 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland
Lot 23 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
Lot 23 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 23 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 23 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland
Lot 24 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Gravel Wetland
	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland
Lot 24 Roof		0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter
Lot 24 Roof Lot 24 Roof (Rear)	0.017	0.5	0.0003	01.10		
	0.017	0.3	0.0378	0.25	0.00945	Gravel Wetland

			Total Pre-PPE (Ibs P/year)	4.84695	Total PostPPE (lbs P/year)	1.2247155	
	LUL 13 GIASS	80.0	0.3	0.024	0.27	0.00046	110' Forested Buffer, HSG C
	Lot 15 Roof Rear Lot 15 Grass	0.017	0.5	0.0085	0.17	0.001445	100' Forested Buffer + Roof Filter
	Lot 15 Roof	0.017	0.5	0.0085	0.27	0.002295	110' Forested Buffer, HSG C
	Lot 15 Impervious	0.043	1.25	0.05375	0.27	0.0145125	110' Forested Buffer, HSG C
	Lot 14 Grass	0.161	0.3	0.0483	0.27	0.013041	110' Forested Buffer, HSG C
	Lot 14 Roof Rear	0.017	0.5	0.0085	0.17	0.001445	100' Forested Buffer + Roof Filter
	Lot 14 Roof	0.017	0.5	0.0085	0.27	0.002295	110' Forested Buffer, HSG C
	Lot 14 Impervious	0.043	1.25	0.05375	0.27	0.0145125	110' Forested Buffer, HSG C
	Lot 13 Grass	0.172	0.3	0.0516	0.27	0.013932	110' Forested Buffer, HSG C
	Lot 13 Roof Rear	0.017	0.5	0.0085	0.17	0.001445	100' Forested Buffer + Roof Filter
	Lot 13 Roof	0.017	0.5	0.0085	0.27	0.002295	110' Forested Buffer, HSG C
	Lot 13 Impervious	0.043	1.25	0.05375	0.27		110' Forested Buffer, HSG C
	Lot 12 Grass	0.172	0.3	0.0516	0.4	0.02064	Rain Garden #4
	Lot 12 Roof Rear	0.017	0.5	0.0085	0.4	0.0034	Roof Drain Filter
	Lot 12 Roof	0.017	0.5	0.0085	0.4	0.0034	Rain Garden #4
	Lot 12 Impervious	0.043	1.25	0.05375	0.4	0.0215	Rain Garden #4
	Lot 11 Grass	0.11	0.3	0.033	0.4	0.0132	Rain Garden #4
	Lot 11 Roof Rear	0.017	0.5	0.0085	0.4	0.0034	Roof Drain Filter
	Lot 11 Impervious	0.01	1.25	0.0125	0.4	0.005	Rain Garden #4
	Lot 10 Grass	0.133	0.3	0.0399	0.4	0.01596	Rain Garden
	Lot 10 Roof (Rear)	0.017	0.5	0.0085	0.4	0.0034	Roof Drain Filter
	Lot 10 Impervious	0.01	1.25	0.0125	0.4	0.005	Rain Garden
Lots to Oth							
	Lot 20 Grass	0.125	0.3	0.0375	0.25	0.009375	Filter Basin
	Lot 20 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Filter Basin + Roof Filter
	Lot 20 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin
	Lot 20 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Filter Basin
	Lot 19 Grass	0.195	0.3	0.0585	0.25	0.014625	Filter Basin
	Lot 19 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Filter Basin + Roof Filter
	Lot 19 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin
	Lot 19 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Filter Basin
	Lot 18 Grass	0.195	0.3	0.0585	0.25	0.014625	Filter Basin
	Lot 18 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Filter Basin + Roof Filter
	Lot 18 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin
	Lot 18 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Filter Basin
	Lot 17 Grass	0.103	0.3	0.0309	0.25	0.007725	Filter Basin
	Lot 17 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Filter Basin + Roof Filter
	Lot 17 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin
	Lot 17 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Filter Basin
	Lot 16 Grass	0.195	0.3	0.0585	0.25	0.014625	Filter Basin
	Lot 16 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Filter Basin + Roof Filter
	LOT 16 ROOT	0.017	0.5	0.0085	0.25	0.002125	Filter Basin

Lot 16 Roof

0.017

0.5

0.0085

0.25

0.002125 Filter Basin

Worksheet 1

Pre-PPE and Post-PPE Calculations
Calculate phosphorus export from development for before and after treatment Use as many sheets as needed for each development type (commercial, roads, residential lots, etc.)

Project name: Vista Project Development type: Mixed Sheet #

Land Surface Type or Lot #(s) with description	Acres or # of lots	Export Coefficient from Table 3.1 Table 3.2	Pre- treatment Algal Av. P Export (Ibs P/year)	Treatment Factor for BMP(s) from Chapter 6	Post- treatment Algal Av. P Export (Ibs P/year)	Description of BMPs
			Subd	livision		
Existing House	0.079	1.25	0.09875	0.5	0.049375	50% of the house that drains to ditches
Existing Roads	0.392	0.5	0.196	0.5	0.098	50% of roads that have channelized flow
		Total Pre-PPE (Ibs P/year)	0.29475	Total PostPPE (lbs P/year)	0.147375	


Worksheet 1 Project Phosphorus Export Summary

Summarizing the project's algal available phosphorus export (PPE)

Project name: Highland Views			
Project Phoenic and Product - Western at 4	DDD		
Project Phosphorus Budget - Worksheet 1	PPB	1.10	lbs P / year
Total Pre-Treatment Phosphorus Export - Worksheet 2	Pre-PPE	4.85	lbs P / year
			,
Total Post-Treatment Phosphorus Export - Worksheet 2	Post-PPE		
Total Post-Treatment Phosphorus Export - Worksheet 2	POST-PPE	1.22	lbs P / year
Total Phosphorus Mitigation Credit - Worksheet 3	TMC	0.15	lbs P / year
Project Phosphorus Export (Post-PPE - TMC)	PPE	4.00	lha D / vaar
(Foctorial Expert	• • =	1.08	lbs P / year
Is the Project Phosphorus Export sufficiently reduced?			
(PPE< PPB)		-0.02	lbs P / year
W			
If PPE is less than or equal to PPB, the project me	•	•	` • /
If PPE is more than PPB, more reduction in phospho	rus export i	nay be requir	ea (pos. #)
OTHERWISE:			
Is the Post-Treatment Phosphorus Export less than 40%			
of the Pre-Treatment Export? It is equivalent to more than		2	5.27%
60% removal efficiency.		2	0.21 /0
(Post-PPE < 40% Pre-PPE)			

It Post-PPE is less than 40% of Pre-PPE, a compensation fee may be appropriate at the cost of \$22,733 per pound of phosphorus over budget. (see table 3 Phosphorus Compensation Fee in updated phosphorus manual) The compensation fee option is only available in some lake watersheds. Check with the DEP project manager or with the DEP Division of Watershed Management to see if the watershed in which the project is located is eligible before proposing a project that incorporates a compensation fee.

The following compensation fee must be paid \$13,9*(PPE-PPB)



2 Year - 24 Hour Pre Development Type III 24-hr Rainfall=3.10" Printed 12/20/2016

1636 Pre

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Page 2

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 100: Runoff Area=984,874 sf 5.27% Impervious Runoff Depth>0.82"

Flow Length=1,300' Tc=54.5 min CN=73 Runoff=9.36 cfs 1.537 af

Subcatchment 200: Runoff Area=136,701 sf 1.99% Impervious Runoff Depth>0.71"

Flow Length=720' Tc=80.8 min CN=71 Runoff=0.87 cfs 0.186 af

Subcatchment 300: Runoff Area=58,171 sf 2.75% Impervious Runoff Depth>0.73"

Flow Length=270' Slope=0.1000 '/' Tc=28.9 min CN=71 Runoff=0.66 cfs 0.081 af

Subcatchment 400: Offsite Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>0.80"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=12.52 cfs 2.836 af

Subcatchment 500: Offsite Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>0.87"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=9.13 cfs 1.457 af

Reach R1: Perimeter Ditch

Avg. Depth=0.69' Max Vel=6.52 fps Inflow=21.00 cfs 4.452 af

n=0.035 L=150.0' S=0.0533 '/' Capacity=512.84 cfs Outflow=20.99 cfs 4.449 af

Reach R2: Perimeter Ditch Avg. Depth=0.72' Max Vel=5.94 fps Inflow=20.16 cfs 4.273 af

n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=20.13 cfs 4.266 af

Reach R3: Perimeter Ditch

Avg. Depth=0.78' Max Vel=3.05 fps Inflow=9.13 cfs 1.457 af

n=0.040 L=1,250.0' S=0.0144 '/' Capacity=195.24 cfs Outflow=8.93 cfs 1.438 af

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=21.20 cfs 4.530 af

Outflow=21.20 cfs 4.530 af

Reach SP#2: Study Point #2 - Wetland adjacent to Highland Inflow=9.36 cfs 1.537 af

Outflow=9.36 cfs 1.537 af

Pond CB: CB Inflow=9.13 cfs 1.457 af

Primary=9.13 cfs 1.457 af

Total Runoff Area = 89.863 ac Runoff Volume = 6.096 af Average Runoff Depth = 0.81" 95.56% Pervious = 85.874 ac 4.44% Impervious = 3.990 ac

1636 Pre

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Subcatchment 100:

Runoff = 9.36 cfs @ 12.81 hrs, Volume= 1.537 af, Depth> 0.82"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

_	Α	rea (sf)	CN D	escription				
*		20,200	92 F	load with F	Row			
*		24,909	98 C	Camp Roads & House				
*		10,950	98 C	8 Onsite driveway in easement				
		80,000	79 1	acre lots,	20% imp, I	HSG C		
		80,000	74 >	75% Gras	s cover, Go	ood, HSG C		
	6	643,288	70 V	Voods, Go	od, HSG C			
_	1	25,527	77 V	Voods, Go	od, HSG D			
	9	984,874	73 V	Veighted A	verage			
933,015 94.73% Pervious Area					vious Area			
		51,859	5	.27% Impe	ervious Area	a		
	Tc	Length	Slope	Velocity	Capacity	Description		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
_		_		•		Description Sheet Flow,		
_	(min)	(feet)	(ft/ft)	(ft/sec)		<u>'</u>		
_	(min)	(feet)	(ft/ft)	(ft/sec)		Sheet Flow,		
_	(min) 33.9 8.4	(feet) 150	(ft/ft) 0.0600 0.0330	(ft/sec) 0.07		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Woodland Kv= 5.0 fps		
_	(min) 33.9	(feet) 150	(ft/ft) 0.0600	(ft/sec) 0.07		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Pipe Channel,		
_	(min) 33.9 8.4 0.1	(feet) 150 460	(ft/ft) 0.0600 0.0330 0.0100	(ft/sec) 0.07 0.91 4.91	(cfs)	Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012		
_	(min) 33.9 8.4	(feet) 150 460	(ft/ft) 0.0600 0.0330	0.07 0.91	(cfs)	Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012 Shallow Concentrated Flow,		
_	(min) 33.9 8.4 0.1	(feet) 150 460 30	(ft/ft) 0.0600 0.0330 0.0100	(ft/sec) 0.07 0.91 4.91	(cfs)	Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012		

Summary for Subcatchment 200:

Runoff = 0.87 cfs @ 13.20 hrs, Volume= 0.186 af, Depth> 0.71"

	Area (sf)	CN	Description
*	2,722	98	Camp Roads
	133,979	70	Woods, Good, HSG C
	136,701	71	Weighted Average
	133,979		98.01% Pervious Area
	2,722		1.99% Impervious Area

	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	69.3	150	0.0100	0.04		Sheet Flow,
						Woods: Dense underbrush n= 0.800 P2= 3.10"
	9.0	380	0.0200	0.71		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
	0.1	20	0.0100	4.91	3.86	Pipe Channel,
						12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
	2.4	170	0.0580	1.20		Shallow Concentrated Flow,
_						Woodland Kv= 5.0 fps
	80.8	720	Total			

Summary for Subcatchment 300:

Runoff = 0.66 cfs @ 12.46 hrs, Volume= 0.081 af, Depth> 0.73"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

_	Α	rea (sf)	CN D	escription		
*		1,600	98 C	amp Road	ls	
56,571 70 Woods, Good, HSG C					od, HSG C	
58,171 71 Weighted Average					verage	
56,571 97.25% Pervious Area					vious Area	
		1,600	2	.75% Impe	ervious Area	a
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	27.6	150	0.1000	0.09		Sheet Flow,
						Woods: Dense underbrush n= 0.800 P2= 3.10"
	1.3	120	0.1000	1.58		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
	28.9	270	Total			

Summary for Subcatchment 400: Offsite

Runoff = 12.52 cfs @ 13.32 hrs, Volume= 2.836 af, Depth> 0.80"

	Area (ac)	CN	Description
*	2.000	92	Road with Row
*	0.500	83	Commercial Lot
	5.000	79	1 acre lots, 20% imp, HSG C
	29.900	70	Woods, Good, HSG C
	5.200	77	Woods, Good, HSG D
	42.600	73	Weighted Average
	41.600		97.65% Pervious Area
	1.000		2.35% Impervious Area

	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	33.9	150	0.0600	0.07		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10"
	4.4	380	0.0840	1.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
	52.2	700	0.0020	0.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
_	2.3	340	0.0140	2.45	5.51	Trap/Vee/Rect Channel Flow, Bot.W=4.00' D=0.50' Z= 1.0 '/' Top.W=5.00' n= 0.040
	92.8	1,570	Total			

Summary for Subcatchment 500: Offsite

Runoff = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af, Depth> 0.87"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	cription						
*	0.	800	92	Road	ad with Row						
*	0.	500	98	Com	ommercial Impervious						
	6.	000	79	1 acı	re lots, 209	% imp, HS0	G C				
	12.	880	70	Woo	ds, Good,	HSG C					
	20.	180	74	Weig	hted Aver	age					
	18.	480		91.5	8% Pervio	us Area					
1.700 8.42% Impervious Area				8.42	% Impervi	ous Area					
	_	_									
	Tc	Lengt		Slope	Velocity	Capacity	Description				
_	(min)	(feet	:)	(ft/ft)	(ft/sec)	(cfs)					
	35.6	15	0 0	.0530	0.07		Sheet Flow,				
							Woods: Dense underbrush n= 0.800 P2= 3.10"				
	16.9	1,22	0 0	0.0580	1.20		Shallow Concentrated Flow,				
_							Woodland Kv= 5.0 fps				
	52.5	1,37	T C	otal							

Summary for Reach R1: Perimeter Ditch

[61] Hint: Exceeded Reach R2 outlet invert by 0.69' @ 13.15 hrs

Inflow Area = 65.918 ac, 4.19% Impervious, Inflow Depth > 0.81" Inflow = 21.00 cfs @ 13.16 hrs, Volume= 4.452 af

Outflow = 20.99 cfs @ 13.17 hrs, Volume= 4.449 af, Atten= 0%, Lag= 0.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Max. Velocity= 6.52 fps, Min. Travel Time= 0.4 min Avg. Velocity = 3.79 fps, Avg. Travel Time= 0.7 min

2 Year - 24 Hour Pre Development Type III 24-hr Rainfall=3.10" Printed 12/20/2016


Page 6

1636 Pre

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Peak Storage= 483 cf @ 13.16 hrs, Average Depth at Peak Storage= 0.69' Bank-Full Depth= 4.00', Capacity at Bank-Full= 512.84 cfs

4.00' x 4.00' deep channel, n= 0.035 Side Slope Z-value= 1.0 '/' Top Width= 12.00' Length= 150.0' Slope= 0.0533 '/' Inlet Invert= 206.00', Outlet Invert= 198.00'



Summary for Reach R2: Perimeter Ditch

[62] Warning: Exceeded Reach R3 OUTLET depth by 0.14' @ 13.75 hrs

Inflow Area = 62.780 ac, 4.30% Impervious, Inflow Depth > 0.82" Inflow = 20.16 cfs @ 13.12 hrs, Volume= 4.273 af


Outflow = 20.13 cfs @ 13.15 hrs, Volume= 4.266 af, Atten= 0%, Lag= 2.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Max. Velocity= 5.94 fps, Min. Travel Time= 0.8 min

Avg. Velocity = 3.50 fps, Avg. Travel Time= 1.4 min

Peak Storage= 983 cf @ 13.14 hrs, Average Depth at Peak Storage= 0.72' Bank-Full Depth= 6.00', Capacity at Bank-Full= 1,055.19 cfs

4.00' x 6.00' deep channel, n= 0.040 Earth, cobble bottom, clean sides Side Slope Z-value= 1.0 '/' Top Width= 16.00' Length= 290.0' Slope= 0.0552 '/' Inlet Invert= 222.00', Outlet Invert= 206.00'



Summary for Reach R3: Perimeter Ditch

Inflow Area = 20.180 ac, 8.42% Impervious, Inflow Depth > 0.87" Inflow = 9.13 cfs @ 12.78 hrs. Volume= 1.457 af

Outflow = 8.93 cfs @ 12.97 hrs, Volume= 1.438 af, Atten= 2%, Lag= 11.9 min

Page 7

1636 Pre

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 3.05 fps, Min. Travel Time= 6.8 min Avg. Velocity = 1.62 fps, Avg. Travel Time= 12.9 min


Peak Storage= 3,669 cf @ 12.86 hrs, Average Depth at Peak Storage= 0.78' Bank-Full Depth= 4.00', Capacity at Bank-Full= 195.24 cfs

 $3.00' \times 4.00'$ deep channel, n= 0.040 Earth, cobble bottom, clean sides

Side Slope Z-value= 1.0 '/' Top Width= 11.00'

Length= 1,250.0' Slope= 0.0144 '/'

Inlet Invert= 240.00', Outlet Invert= 222.00'



Summary for Reach SP#1: Study Point #1 - Outlet of Ditch

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 67.254 ac, 4.16% Impervious, Inflow Depth > 0.81" Inflow = 21.20 cfs @ 13.16 hrs, Volume= 4.530 af

Outflow = 21.20 cfs @ 13.16 hrs, Volume= 4.530 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Reach SP#2: Study Point #2 - Wetland adjacent to Highland

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 22.610 ac, 5.27% Impervious, Inflow Depth > 0.82" Inflow = 9.36 cfs @ 12.81 hrs, Volume= 1.537 af

Outflow = 9.36 cfs @ 12.81 hrs, Volume= 1.537 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond CB: CB


Not modeled because watershed enters closed stormwater system over a series of catch basins.

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 20.180 ac, 8.42% Impervious, Inflow Depth > 0.87" Inflow = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af

Primary = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs



10 Year - 24 Hour Pre Development Type III 24-hr Rainfall=4.60" Printed 12/20/2016

1636 PrePrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Page 2

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 100: Runoff Area=984,874 sf 5.27% Impervious Runoff Depth>1.78"

Flow Length=1,300' Tc=54.5 min CN=73 Runoff=21.36 cfs 3.361 af

Subcatchment 200: Runoff Area=136,701 sf 1.99% Impervious Runoff Depth>1.62"

Flow Length=720' Tc=80.8 min CN=71 Runoff=2.11 cfs 0.423 af

Subcatchment 300: Runoff Area=58,171 sf 2.75% Impervious Runoff Depth>1.66"

Flow Length=270' Slope=0.1000 '/' Tc=28.9 min CN=71 Runoff=1.59 cfs 0.184 af

Subcatchment 400: Offsite Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>1.75"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=28.76 cfs 6.222 af

Subcatchment 500: Offsite Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>1.86"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=20.31 cfs 3.127 af

Reach R1: Perimeter Ditch

Avg. Depth=1.11' Max Vel=8.41 fps Inflow=47.61 cfs 9.735 af

n=0.035 L=150.0' S=0.0533 '/' Capacity=512.84 cfs Outflow=47.59 cfs 9.730 af

Reach R2: Perimeter Ditch Avg. Depth=1.16' Max Vel=7.64 fps Inflow=45.56 cfs 9.322 af

n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=45.51 cfs 9.312 af

Reach R3: Perimeter Ditch

Avg. Depth=1.23' Max Vel=3.85 fps Inflow=20.31 cfs 3.127 af

 $n = 0.040 \quad L = 1,250.0' \quad S = 0.0144 \; \text{$^{\prime}$} \quad Capacity = 195.24 \; \text{cfs} \quad Outflow = 20.02 \; \text{cfs} \; \; 3.100 \; \text{af} \; \; \text{$^{\prime}$} \quad Capacity = 195.24 \; \text{$^{\prime}$} \quad Capacity = 195.2$

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=48.09 cfs 9.915 af

Outflow=48.09 cfs 9.915 af


Reach SP#2: Study Point #2 - Wetland adjacent to Highland Inflow=21.36 cfs 3.361 af

Outflow=21.36 cfs 3.361 af

Pond CB: CB Inflow=20.31 cfs 3.127 af

Primary=20.31 cfs 3.127 af

Total Runoff Area = 89.863 ac Runoff Volume = 13.318 af Average Runoff Depth = 1.78" 95.56% Pervious = 85.874 ac 4.44% Impervious = 3.990 ac



25 Year - 24 Hour Pre Development Type III 24-hr Rainfall=5.80" Printed 12/20/2016

Page 2

1636 Pre

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 100: Runoff Area=984,874 sf 5.27% Impervious Runoff Depth>2.67"

Flow Length=1,300' Tc=54.5 min CN=73 Runoff=32.10 cfs 5.025 af

Subcatchment 200: Runoff Area=136,701 sf 1.99% Impervious Runoff Depth>2.46"

Flow Length=720' Tc=80.8 min CN=71 Runoff=3.24 cfs 0.644 af

Subcatchment 300: Runoff Area=58,171 sf 2.75% Impervious Runoff Depth>2.52"

Flow Length=270' Slope=0.1000 '/' Tc=28.9 min CN=71 Runoff=2.44 cfs 0.280 af

Subcatchment 400: Offsite Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>2.62"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=43.31 cfs 9.317 af

Subcatchment 500: Offsite Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>2.76"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=30.23 cfs 4.640 af

Reach R1: Perimeter Ditch

Avg. Depth=1.40' Max Vel=9.46 fps Inflow=71.34 cfs 14.555 af

n=0.035 L=150.0' S=0.0533 '/' Capacity=512.84 cfs Outflow=71.33 cfs 14.550 af

Reach R2: Perimeter Ditch Avg. Depth=1.45' Max Vel=8.60 fps Inflow=68.12 cfs 13.923 af

n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=68.11 cfs 13.912 af

Reach R3: Perimeter Ditch

Avg. Depth=1.53' Max Vel=4.30 fps Inflow=30.23 cfs 4.640 af

n=0.040 L=1,250.0' S=0.0144 '/' Capacity=195.24 cfs Outflow=29.86 cfs 4.607 af

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=72.08 cfs 14.829 af

Outflow=72.08 cfs 14.829 af


Reach SP#2: Study Point #2 - Wetland adjacent to Highland Inflow=32.10 cfs 5.025 af

Outflow=32.10 cfs 5.025 af

Pond CB: CB Inflow=30.23 cfs 4.640 af

Primary=30.23 cfs 4.640 af

Total Runoff Area = 89.863 ac Runoff Volume = 19.906 af Average Runoff Depth = 2.66" 95.56% Pervious = 85.874 ac 4.44% Impervious = 3.990 ac



Subcatchment 15a:

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Reach routing by Stor-Ind+	Trans method - Pond routing by Stor-Ind method
Subcatchment1:	Runoff Area=0.540 ac 46.09% Impervious Runoff Depth>1.56" Flow Length=230' Tc=10.4 min CN=85 Runoff=0.90 cfs 0.070 af
Subcatchment 2:	Runoff Area=0.446 ac 26.21% Impervious Runoff Depth>1.15" Flow Length=370' Tc=33.5 min CN=79 Runoff=0.35 cfs 0.043 af
Subcatchment3:	Runoff Area=0.574 ac 23.14% Impervious Runoff Depth>1.09" Flow Length=300' Tc=30.8 min CN=78 Runoff=0.44 cfs 0.052 af
Subcatchment 4:	Runoff Area=0.019 ac 94.74% Impervious Runoff Depth>2.60" Tc=2.0 min CN=97 Runoff=0.06 cfs 0.004 af
Subcatchment 5:	Runoff Area=0.066 ac 69.70% Impervious Runoff Depth>2.04" Tc=2.0 min CN=91 Runoff=0.18 cfs 0.011 af
Subcatchment 6:	Runoff Area=0.297 ac 20.44% Impervious Runoff Depth>1.03" Flow Length=240' Tc=34.9 min CN=77 Runoff=0.20 cfs 0.026 af
Subcatchment7:	Runoff Area=0.076 ac 44.74% Impervious Runoff Depth>1.49" Tc=2.0 min CN=84 Runoff=0.16 cfs 0.009 af
Subcatchment8:	Runoff Area=0.032 ac 100.00% Impervious Runoff Depth>2.68" Tc=2.0 min CN=98 Runoff=0.10 cfs 0.007 af
Subcatchment9:	Runoff Area=0.029 ac 100.00% Impervious Runoff Depth>2.68" Tc=2.0 min CN=98 Runoff=0.09 cfs 0.006 af
Subcatchment 10:	Runoff Area=0.054 ac 68.52% Impervious Runoff Depth>1.95" Tc=2.0 min CN=90 Runoff=0.14 cfs 0.009 af
Subcatchment11:	Runoff Area=0.057 ac 70.18% Impervious Runoff Depth>2.04" Tc=2.0 min CN=91 Runoff=0.16 cfs 0.010 af
Subcatchment 12:	Runoff Area=0.271 ac 39.89% Impervious Runoff Depth>1.42" Flow Length=140' Tc=7.2 min CN=83 Runoff=0.46 cfs 0.032 af
Subcatchment 13:	Runoff Area=0.607 ac 33.11% Impervious Runoff Depth>1.28" Flow Length=294' Tc=13.2 min CN=81 Runoff=0.77 cfs 0.065 af
Subcatchment 14:	Runoff Area=0.145 ac 71.03% Impervious Runoff Depth>2.04" Tc=2.0 min CN=91 Runoff=0.40 cfs 0.025 af
Subcatchment 15:	Runoff Area=2.638 ac 18.28% Impervious Runoff Depth>0.97" Flow Length=630' Tc=44.3 min CN=76 Runoff=1.50 cfs 0.214 af

Runoff Area=0.704 ac 18.32% Impervious Runoff Depth>1.04"

Flow Length=285' Tc=28.0 min CN=77 Runoff=0.53 cfs 0.061 af

 Subcatchment 16:
 Runoff Area=0.690 ac 45.77% Impervious Runoff Depth>1.55" Flow Length=360' Tc=28.0 min CN=85 Runoff=0.79 cfs 0.089 af

 Subcatchment 100:
 Runoff Area=551,455 sf 5.75% Impervious Runoff Depth>0.91" Flow Length=380' Tc=60.3 min CN=75 Runoff=5.63 cfs 0.964 af

Subcatchment 300:Runoff Area=71,335 sf 2.24% Impervious Runoff Depth>0.73"
Flow Length=270' Slope=0.1000'/' Tc=28.9 min CN=71 Runoff=0.81 cfs 0.100 af

Subcatchment 400: Offsite

Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>0.80"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=12.52 cfs 2.836 af

Subcatchment 500: Offsite

Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>0.87"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=9.13 cfs 1.457 af

Subcatchment FB:Runoff Area=69,332 sf 25.41% Impervious Runoff Depth>1.19"
Flow Length=250' Tc=72.0 min CN=80 Runoff=0.85 cfs 0.158 af

Subcatchment GW: Runoff Area=100,679 sf 22.37% Impervious Runoff Depth>1.15" Flow Length=480' Tc=34.0 min CN=79 Runoff=1.78 cfs 0.221 af

Subcatchment LS:

Runoff Area=44,374 sf 29.45% Impervious Runoff Depth>1.20"
Flow Length=410' Tc=46.3 min CN=80 Runoff=0.71 cfs 0.102 af

Subcatchment RG:

Runoff Area=26,952 sf 28.89% Impervious Runoff Depth>1.28"
Flow Length=470' Tc=17.9 min CN=81 Runoff=0.70 cfs 0.066 af

Reach R2: Perimeter DitchAvg. Depth=0.72' Max Vel=5.94 fps Inflow=20.16 cfs 4.273 af n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=20.13 cfs 4.266 af

Reach R3: Perimeter DitchAvg. Depth=0.78' Max Vel=3.05 fps Inflow=9.13 cfs 1.457 af n=0.040 L=1,250.0' S=0.0144 '/' Capacity=195.24 cfs Outflow=8.93 cfs 1.438 af

Reach R4: Downstream of BufferAvg. Depth=0.09' Max Vel=0.72 fps Inflow=0.71 cfs 0.102 af n=0.080 L=270.0' S=0.0407 '/' Capacity=13.95 cfs Outflow=0.70 cfs 0.101 af

Reach R5: Avg. Depth=0.13' Max Vel=0.96 fps Inflow=0.67 cfs 0.048 af n=0.080 L=78.0' S=0.0538 '/' Capacity=9.53 cfs Outflow=0.65 cfs 0.048 af

Reach R6: Avg. Depth=0.26' Max Vel=3.57 fps Inflow=0.65 cfs 0.048 af 15.0" Round Pipe n=0.012 L=40.0' S=0.0100 '/' Capacity=7.00 cfs Outflow=0.64 cfs 0.048 af

Reach R7: Avg. Depth=0.12' Max Vel=0.64 fps Inflow=0.64 cfs 0.048 af n=0.100 L=360.0' S=0.0400 '/' Capacity=6.57 cfs Outflow=0.44 cfs 0.047 af

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=20.39 cfs 4.441 af Outflow=20.39 cfs 4.441 af

Page 4

1636 Post

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Reach SP#2: Study Point #2 - Wetland adjacent to Highland Inflow=6.71 cfs 1.474 af

Outflow=6.71 cfs 1.474 af

Pond CB: CB Inflow=9.13 cfs 1.457 af Primary=9.13 cfs 1.457 af

Pond CB1: Peak Elev=201.41' Inflow=3.99 cfs 0.644 af

24.0" Round Culvert n=0.012 L=144.0' S=0.0308 '/' Outflow=3.99 cfs 0.644 af

Pond CB10: Peak Elev=232.92' Inflow=0.14 cfs 0.009 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.14 cfs 0.009 af

Pond CB11: Peak Elev=203.21' Inflow=0.16 cfs 0.010 af

15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.16 cfs 0.010 af

15.0" Round Culvert n=0.012 L=112.0' S=0.0381 '/' Outflow=2.61 cfs 0.437 af

Pond CB12: Peak Elev=208.60' Inflow=0.46 cfs 0.032 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.46 cfs 0.032 af

Pond CB13: Peak Elev=223.48' Inflow=0.77 cfs 0.065 af

15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.77 cfs 0.065 af

Pond CB14: Peak Elev=213.95' Inflow=1.96 cfs 0.300 af 15.0" Round Culvert n=0.012 L=128.0' S=0.0050 '/' Outflow=1.96 cfs 0.300 af

Pond CB15: Peak Elev=214.14' Inflow=1.92 cfs 0.275 af

15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=1.92 cfs 0.275 af

Pond CB16: Peak Elev=213.92' Inflow=1.20 cfs 0.247 af 18.0" Round Culvert n=0.012 L=50.0' S=0.0272 '/' Outflow=1.20 cfs 0.247 af

Pond CB2: Peak Elev=202.60' Inflow=3.58 cfs 0.574 af 18.0" Round Culvert n=0.012 L=124.0' S=0.0050 '/' Outflow=3.58 cfs 0.574 af

Pond CB3: Peak Elev=207.77' Inflow=3.20 cfs 0.521 af

18.0" Round Culvert n=0.012 L=122.0' S=0.0430 '/' Outflow=3.20 cfs 0.521 af

Pond CB4: Peak Elev=213.27' Inflow=2.61 cfs 0.437 af

Pond CB5: Peak Elev=213.51' Inflow=2.60 cfs 0.433 af

15.0" Round Culvert n=0.012 L=32.0' S=0.0063 '/' Outflow=2.60 cfs 0.433 af

Pond CB6: Peak Elev=216.27' Inflow=1.07 cfs 0.122 af

15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=1.07 cfs 0.122 af

Pond CB7: Peak Elev=223.34' Inflow=0.98 cfs 0.097 af 15.0" Round Culvert n=0.012 L=126.0' S=0.0563 '/' Outflow=0.98 cfs 0.097 af

Pond CB8: Peak Elev=229.53' Inflow=0.34 cfs 0.022 af 15.0" Round Culvert n=0.012 L=126.0' S=0.0510 '/' Outflow=0.34 cfs 0.022 af

2 post Type III 24-hr Rainfall=3.10" Printed 1/11/2017

1636 PostPrepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Page 5

Pond CB9: Peak Elev=232.78' Inflow=0.24 cfs 0.015 af

15.0" Round Culvert n=0.012 L=84.0' S=0.0393 '/' Outflow=0.24 cfs 0.015 af

Pond FB1: Filter Basin #1 Peak Elev=207.05' Storage=7,537 cf Inflow=1.20 cfs 0.247 af

Outflow=0.30 cfs 0.078 af

Pond GW1: Gravel Wetland #1 Peak Elev=194.98' Storage=24,443 cf Inflow=5.72 cfs 0.865 af

Outflow=0.90 cfs 0.362 af

Pond RG1: Rain Garden #1 Peak Elev=208.04' Storage=821 cf Inflow=0.70 cfs 0.066 af

Outflow=0.67 cfs 0.048 af

Total Runoff Area = 89.863 ac Runoff Volume = 6.636 af Average Runoff Depth = 0.89" 92.21% Pervious = 82.864 ac 7.79% Impervious = 6.999 ac

1636 PostPrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Subcatchment 1:

Runoff = 0.90 cfs @ 12.15 hrs, Volume= 0.070 af, Depth> 1.56"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	escription								
*	0.	164	98	Prop	osed Road	dway Impe	rvious						
*	0.	093	74		oadway >75% Grass cover, Good, HSG C,								
	0.	283	81	1/3 a	/3 acre lots, 30% imp, HSG C								
*	0.	000	98 Apartments Impervious										
*	0.	000	74	Apar	tments Gr	ass, HSG (
	0.540 85 Weighted Average												
	0.	291		53.9	, 1% Pervio	us Area							
	0.	249		46.09	9% Imperv	rious Area							
					-								
	Tc	Lengtl	า :	Slope	Velocity	Capacity	Description						
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)							
	9.3	100	0 0	.0600	0.18		Sheet Flow,						
							Grass: Dense n= 0.240 P2= 3.10"						
	1.1	130	0 (.0100	2.03		Shallow Concentrated Flow,						
							Paved Kv= 20.3 fps						
	10.4	230) T	otal	•								

Summary for Subcatchment 2:

Runoff = 0.35 cfs @ 12.49 hrs, Volume= 0.043 af, Depth> 1.15"

	Area (ac)	CN	Description					
*	0.029	98	Proposed Roadway Impervious					
*	0.002	74	Roadway >75% Grass cover, Good, HSG C,					
	0.293	81	1/3 acre lots, 30% imp, HSG C					
*	0.000	98	Apartments Impervious					
*	0.046	74	Apartments Grass, HSG C					
	0.076	70	Woods, Good, HSG C					
	0.446	79	Weighted Average					
	0.329		73.79% Pervious Area					
	0.117		26.21% Impervious Area					

	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
_	32.4	150	0.0670	0.08		Sheet Flow,
						Woods: Dense underbrush n= 0.800 P2= 3.10"
	0.5	130	0.0700	3.97		Shallow Concentrated Flow,
						Grassed Waterway Kv= 15.0 fps
	0.6	90	0.0150	2.49		Shallow Concentrated Flow,
_						Paved Kv= 20.3 fps
	33.5	370	Total			

Summary for Subcatchment 3:

Runoff = 0.44 cfs @ 12.45 hrs, Volume= 0.052 af, Depth> 1.09"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac) (CN De	scription								
*	0.	026	98 Pr	roposed Roadway Impervious								
*	0.	002	74 Rc	oadway >75% Grass cover, Good, HSG C,								
	0.	356	81 1/3	3 acre lots, 30% imp, HSG C								
*	0.	000		artments Im								
*	0.	034		artments Gi		${\tt C}$						
_	0.	156	70 W	ods, Good,	HSG C							
	0.574 78 Weighted Average											
	0.	441	76	76.86% Pervious Area								
	0.133		23	.14% Imper	vious Area							
	_											
	Tc	Length		•	Capacity	Description						
	(min)	(feet)	(ft/f1) (ft/sec)	(cfs)							
	30.2	150	0.080	0.08		Sheet Flow,						
						Woods: Dense underbrush n= 0.800 P2= 3.10"						
	0.5	120	0.067	3.88		Shallow Concentrated Flow,						
						Grassed Waterway Kv= 15.0 fps						
	0.1	30	0.080	5.74		Shallow Concentrated Flow,						
						Paved Kv= 20.3 fps						
	30.8	300	Total									

Summary for Subcatchment 4:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.06 cfs @ 12.03 hrs, Volume= 0.004 af, Depth> 2.60"

	Area ((ac)	CN	Desc	Description						
*	0.0	018	98	Prop	roposed Roadway Impervious						
*	0.0	001	74	Road	dway >75%	6 Grass co	ver, Good, HSG C,				
	0.0	000	81	1/3 a	cre lots, 3	0% imp, H	SG C				
*	0.0	000	98	Apar	partments Impervious						
*	0.0	000	74	Apar	partments Grass, HSG C						
	0.0	.000 70 Woods, Good, HSG C									
	0.0	019	97	Weig	hted Aver	age					
	0.0	001		5.26	5.26% Pervious Area						
	0.0	018		94.7	4% Imperv	rious Area					
	Tc	Lengt	th	Slope	Velocity	Capacity	Description				
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	2.0						Direct Entry, Assumed Min Tc				

Summary for Subcatchment 5:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.18 cfs @ 12.04 hrs, Volume= 0.011 af, Depth> 2.04"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	Description						
*	0.	046	98	Prop	Proposed Roadway Impervious						
*	0.	020	74	Road	dway >75%	6 Grass co	ver, Good, HSG C,				
	0.	000	81	1/3 a	/3 acre lots, 30% imp, HSG C						
*	0.	000	98	Apar	tments Im	pervious					
*	0.	000	74	Apar	tments Gr	ass, HSG (
	0.	000	00 70 Woods, Good, HSG C								
	0.	066	91	Weig	hted Aver	age					
	0.	020		30.3	0% Pervio	us Area					
	0.	046		69.7	0% Imperv	rious Area					
	Тс	Leng	•	Slope	Velocity	Capacity	Description				
	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	2.0						Direct Entry, Assumed Min Tc				

Summary for Subcatchment 6:

Runoff = 0.20 cfs @ 12.52 hrs, Volume= 0.026 af, Depth> 1.03"

	Area	(ac)	CN	Desc	cription								
*	0.	031	98	Prop	osed Road	dway Impe	rvious						
*	0.	042	74	Road	oadway >75% Grass cover, Good, HSG C,								
	0.	099	81	1/3 a	cre lots, 3	0% imp, H	SG C						
*	0.	000	98	Apar	tments Im	pervious							
*	0.	000	74	Apar	Apartments Grass, HSG C								
_	0.	125	70	Woo	ds, Good,	HSG C							
	0.	297	77	Weig	hted Aver	age							
	0.236			79.5	79.56% Pervious Area								
	0.061		20.4	4% Imperv	vious Area								
	Tc	Length	h	Slope	Velocity	Capacity	Description						
	(min)	(feet	:)	(ft/ft)	(ft/sec)	(cfs)							
	33.9	150	0 0	0.0600	0.07		Sheet Flow,						
							Woods: Dense underbrush n= 0.800 P2= 3.10"						
	0.9	60	0 0	.0500	1.12		Shallow Concentrated Flow,						
							Woodland Kv= 5.0 fps						
	0.1	30	0 0	.0500	4.54		Shallow Concentrated Flow,						
							Paved Kv= 20.3 fps						
	34.9	240	T C	otal									

Summary for Subcatchment 7:

[49] Hint: Tc<2dt may require smaller dt

0.16 cfs @ 12.04 hrs, Volume= 0.009 af, Depth> 1.49" Runoff

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	cription							
*	0.	034	98	Prop	Proposed Roadway Impervious							
*	0.	035	74	Road	Roadway >75% Grass cover, Good, HSG C,							
	0.	000	81	1/3 a	1/3 acre lots, 30% imp, HSG C							
*	0.	000	98	Apar	Apartments Impervious							
*	0.	000	74	Apar	partments Grass, HSG C							
_	0.	007	70	Woo	Woods, Good, HSG C							
	0.	076	84	Weig	hted Aver	age						
	0.	042		55.2	6% Pervio	us Area						
	0.	034		44.7	4% Imperv	rious Area						
	Tc	Leng	jth	Slope	Velocity	Capacity	Description					
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)						
	2.0						Direct Entry	Accumed Min To				

2.0

Direct Entry, Assumed Min Tc

Summary for Subcatchment 8:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.10 cfs @ 12.03 hrs, Volume= 0.007 af, Depth> 2.68"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area (ac) CN	Desc	Description							
*	0.019	98	Prop	roposed Roadway Impervious							
*	0.000	74	Roa	Roadway >75% Grass cover, Good, HSG C,							
	0.000	0.000 81 1/3 acre lots, 30% imp, HSG C									
*	0.013	3 98	Rout	te 302							
*	0.000	74	Apaı	tments Gr	ass, HSG (
_	0.000	70	Woo	ds, Good,	HSG C						
	0.032	2 98	Weig	ghted Aver	age						
	0.032	2	100.	00% Impe	vious Area	l					
_		ength (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description					
	2.0					Direct Entry, Assumed Min Tc					

Summary for Subcatchment 9:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.09 cfs @ 12.03 hrs, Volume= 0.006 af, Depth> 2.68"

	Area	(ac)	CN	Desc	Description							
*	0.	029	98	Prop	Proposed Roadway Impervious							
*	0.	000	74	Road	Roadway >75% Grass cover, Good, HSG C,							
	0.	000	81	1/3 a	1/3 acre lots, 30% imp, HSG C							
*	0.	000	98	Apar	partments Impervious							
*	0.	000	74	Apar	partments Grass, HSG C							
	0.	000	70	Woo	ds, Good,	HSG C						
	0.	029	98	Weig	hted Aver	age						
	0.	029		100.	00% Impei	rvious Area	A					
	Tc	Leng		Slope	Velocity	Capacity	Description					
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)						

1636 PostPrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Subcatchment 10:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.14 cfs @ 12.04 hrs, Volume= 0.009 af, Depth> 1.95"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	Description							
*	0.	.035	98	Prop	Proposed Roadway Impervious							
*	0.	.017	74	Road	Roadway >75% Grass cover, Good, HSG C,							
*	0.	.002	98	Rout	e 302							
	0.054 90 Weighted Average											
	0.017 31.48% Pervious Area											
	0.037 68.52% Impervious Area				2% Imperv	rious Area						
	Tc	Leng		Slope	Velocity	Capacity	Description					
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)						
	2.0						Direct Entry, Assumed Min Tc					

Summary for Subcatchment 11:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.16 cfs @ 12.04 hrs, Volume= 0.010 af, Depth> 2.04"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	ription							
*	0.	040	98	Prop	oposed Roadway Impervious							
*	0.	017	74	Road	padway >75% Grass cover, Good, HSG C,							
	0.057 91 Weighted Average											
	0.017 29.82% Pervious Area											
	0.040			70.1	8% Imperv	rious Area						
	Tc (min)	Leng (fee		Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description					
	2.0	•			,	, ,	Direct Entry, Assumed Min Tc					

Summary for Subcatchment 12:

Runoff = 0.46 cfs @ 12.11 hrs, Volume= 0.032 af, Depth> 1.42"

	Area	(ac)	CN	Desc	cription							
*	0.	046	98	Prop	osed Road	dway Impe	rvious					
*	0.	018	74		padway >75% Grass cover, Good, HSG C,							
	0.	207	81		3 acre lots, 30% imp, HSG C							
*	0.	000	98		tments Ím							
*	0.	000	74			ass, HSG (
	0.271 83 Weighted Average											
	0.163 60.11% Pervious Area											
	0.108			39.89	9% Imperv	vious Area						
					•							
	Tc	Lengtl	h	Slope	Velocity	Capacity	Description					
	(min)	(feet	:)	(ft/ft)	(ft/sec)	(cfs)						
	7.0	7	0 (0.0600	0.17		Sheet Flow,					
							Grass: Dense n= 0.240 P2= 3.10"					
	0.2	70	0 (0.080.0	5.74		Shallow Concentrated Flow,					
							Paved Kv= 20.3 fps					
	7.2	140	0 -	Total								

Summary for Subcatchment 13:

Runoff = 0.77 cfs @ 12.19 hrs, Volume= 0.065 af, Depth> 1.28"

	Area	(ac)	CN	Desc	ription						
*	0.	084	98	Prop	osed Road	dway Impe	rvious				
*	0.	056	74				ver, Good, HSG C,				
	0.	000	81			0% imp, H					
*	0.	117	98		tments Ím						
*	0.	213	74			ass, HSG (C				
	0.	137	70		ds, Good,						
	0.	607	81	Weig	hted Aver	age					
	0.406				66.89% Pervious Area						
	0.201		33.1	1% Imperv	ious Area						
					•						
	Tc	Length	1 5	Slope	Velocity	Capacity	Description				
	(min)	(feet		(ft/ft)	(ft/sec)	(cfs)	•				
	12.3	100	0.	0300	0.14		Sheet Flow,				
							Grass: Dense n= 0.240 P2= 3.10"				
	0.1	24	ŀ 0.	0200	2.87		Shallow Concentrated Flow,				
							Paved Kv= 20.3 fps				
	0.3	40	0.	0300	2.60		Shallow Concentrated Flow,				
							Grassed Waterway Kv= 15.0 fps				
	0.5	130	0.	0420	4.16		Shallow Concentrated Flow,				
							Paved Kv= 20.3 fps				
	13.2	294	l To	otal							

Summary for Subcatchment 14:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.40 cfs @ 12.04 hrs, Volume= 0.025 af, Depth> 2.04"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	(ac) CN Description									
*	0.	103	98	Prop	oposed Roadway Impervious							
*	0.	042	74	Road	padway >75% Grass cover, Good, HSG C,							
	0.145 91 Weighted Average											
	0.	042		28.9	7% Pervio	us Area						
	0.103			71.0	3% Imperv	ious Area						
	Tc (min)	Leng (fee		Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description					
	2.0						Direct Entry, Assumed Min Tc					

Summary for Subcatchment 15:

Runoff = 1.50 cfs @ 12.65 hrs, Volume= 0.214 af, Depth> 0.97"

	Area	(ac)	CN	Desc	cription					
*	0.	085	98	Prop	osed Road	dway Impe	rvious			
*	0.	012	74	Road	dway >75%	% Grass co	ver, Good, HSG C,			
	1.	237	81	1/3 a	icre lots, 3	0% imp, H	SG C			
*	0.	026	98	Rout	e 302					
	1.278 70 Woods, Good, HSG C									
2.638 76 Weighted Average										
	2.156			81.7	81.72% Pervious Area					
	0.482		18.2	8% Imperv	ious Area					
	_			-						
	Tc	Lengt		Slope	Velocity	Capacity	Description			
	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
	36.4	15	0 0.	.0500	0.07		Sheet Flow,			
							Woods: Dense underbrush n= 0.800 P2= 3.10"			
	7.5	43	0 0.	.0370	0.96		Shallow Concentrated Flow,			
							Woodland Kv= 5.0 fps			
	0.4	5	0 0.	.0100	2.03		Shallow Concentrated Flow,			
							Paved Kv= 20.3 fps			
	44.3	63	0 T	otal						

Summary for Subcatchment 15a:

Runoff = 0.53 cfs @ 12.42 hrs, Volume= 0.061 af, Depth> 1.04"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac) C	N Des	cription						
0.430 81 1/3 acre lots, 30% imp, HS0						SG C				
_	0.	274	70 Woo	Woods, Good, HSG C						
	0.	704	77 Weig	ghted Aver	age					
0.575 81.68% Pervious Ar										
0.129			18.3	18.32% Impervious Area						
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
	25.5	105	0.0600	0.07		Sheet Flow,				
_	2.5	180	0.0300	1.21		Woods: Dense underbrush n= 0.800 P2= 3.10" Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps				
	28.0	285	Total							

Summary for Subcatchment 16:

Runoff = 0.79 cfs @ 12.39 hrs, Volume= 0.089 af, Depth> 1.55"

	Area	(ac)	CN	Desc	ription						
*	0.	203	98 Proposed Roadway Impervious								
* 0.108 74 Roadway >75% Grass cover, Good, HSG C,											
	0.	376	SG C								
	0.003 70 Woods, Good, HSG C										
	0.	690	85	Weig	hted Aver	age					
	0.	374		54.23	54.23% Pervious Area						
0.316		45.77	7% Imperv	ious Area							
	Tc (min)	Lengt (fee		Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
	26.5	15	0 0	0.0100	0.09		Sheet Flow,				
	1.5	21	0 0).0130	2.31		Grass: Dense n= 0.240 P2= 3.10" Shallow Concentrated Flow, Paved Kv= 20.3 fps				
	28.0	36	0 7	Total							

Summary for Subcatchment 100:

Runoff = 5.63 cfs @ 12.87 hrs, Volume= 0.964 af, Depth> 0.91"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Α	rea (sf)	CN D	escription		
*		20,200	92 F	load with F	Row	
*		10,950	98 C	Insite drive	eway in eas	sement
		40,000	79 1	acre lots,	20% imp, I	HSG C
		80,000	74 >	75% Gras	s cover, Go	ood, HSG C
		32,774			s, 30% imp	,
		39,086			od, HSG C	
	1	25,527		,	od, HSG D	
* 2,918 98 Roof area from Apartments (to RD filter strip)						
551,455 75 Weighted Average						
519,755 94.25% Pervious Area						
	31,700 5.75% Impervious Area					a
	To	Longth	Clana	\/alaaitı	Conneitu	Description
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	(min)			, ,	(618)	Chaot Flour
	23.0	100	0.0700	0.07		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.10"
	0.8	70	0.0100	1.50		
	0.6	70	0.0100	1.50		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
	35.6	150	0.0530	0.07		Sheet Flow, Level Spreader
	55.0	130	0.0330	0.07		Woods: Dense underbrush n= 0.800 P2= 3.10"
	0.9	60	0.0500	1.12		Shallow Concentrated Flow,
	0.0	50	3.0000	1.12		Woodland Kv= 5.0 fps
_	60.3	380	Total			

Summary for Subcatchment 300:

Runoff = 0.81 cfs @ 12.46 hrs, Volume= 0.100 af, Depth> 0.73"

	Area (sf)	CN	Description			
*	1,600	98	Camp Roads			
	69,735	70	Woods, Good, HSG C			
	71,335	71	Weighted Average			
	69,735		97.76% Pervious Area			
	1,600		2.24% Impervious Area			

	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	27.6	150	0.1000	0.09		Sheet Flow,
						Woods: Dense underbrush n= 0.800 P2= 3.10"
	1.3	120	0.1000	1.58		Shallow Concentrated Flow,
_						Woodland Kv= 5.0 fps
	28.9	270	Total			

Summary for Subcatchment 400: Offsite

Runoff = 12.52 cfs @ 13.32 hrs, Volume= 2.836 af, Depth> 0.80"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	Area	(ac)	CN	Desc	cription					
*	2.	000	92	Road	d with Row	1				
*	0.	500	83	Com	mercial Lo	ot				
	5.	000	79	1 acı	re lots, 209	% imp, HSC	G C			
	29.	900	70	Woo	ds, Good,	HSG C				
	5.	200	77	Woo	ds, Good,	HSG D				
	42.600 73		73	Weig	Weighted Average					
	41.	600		97.6	5% Pervio	us Area				
	1.	000		2.35	% Impervi	ous Area				
	Tc	Lengtl	n S	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	33.9	150	0.	0600	0.07		Sheet Flow,			
							Woods: Dense underbrush n= 0.800 P2= 3.10"			
	4.4	380	0.	0840	1.45		Shallow Concentrated Flow,			
							Woodland Kv= 5.0 fps			
	52.2	700	0.	0020	0.22		Shallow Concentrated Flow,			
							Woodland Kv= 5.0 fps			
	2.3	340	0.	0140	2.45	5.51	Trap/Vee/Rect Channel Flow,			
_							Bot.W=4.00' D=0.50' Z= 1.0 '/' Top.W=5.00' n= 0.040			
	92.8	1,570) To	otal						

Summary for Subcatchment 500: Offsite

Runoff = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af, Depth> 0.87"

	Area	(ac)	CN [Desc	ription							
*	0.	800	92 F	Road	with Row							
*	0.	500	98 (Com	ommercial Impervious							
6.000 79 1 acre lots, 20% imp, HSG C							3 C					
12.880 70 Woods, Good, HSG C												
20.180 74 Weighted Average												
18.480 91.58% Pervious Area						us Area						
1.700			8	8.42% Impervious Area								
			•									
	Tc	Length	Slo	ре	Velocity	Capacity	Description					
	(min)	(feet)	(ft	t/ft)	(ft/sec)	(cfs)						
	35.6	150	0.05	530	0.07		Sheet Flow,					
							Woods: Dense underbrush n= 0.800 P2= 3.10"					
	16.9	1,220	0.05	580	1.20		Shallow Concentrated Flow,					
		•					Woodland Kv= 5.0 fps					
	52.5	1,370	Tota	al								

Summary for Subcatchment FB:

Runoff = 0.85 cfs @ 13.01 hrs, Volume= 0.158 af, Depth> 1.19"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

	А	rea (sf)	CN Description							
		58,716	81 ′	1 1/3 acre lots, 30% imp, HSG C						
		3,616	70 \							
*	7,000 74 Swale & Pond Grass									
		69,332	80 \	80 Weighted Average						
		51,717	7 74.59% Pervious Area							
		17,615	2	25.41% lmp	pervious Ar	ea				
	Tc	Length	Slope	Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
	69.3	150	0.0100	0.04		Sheet Flow,				
						Woods: Dense underbrush n= 0.800 P2= 3.10"				
	2.7	100	0.0150	0.61		Shallow Concentrated Flow,				
_						Woodland Kv= 5.0 fps				
	72.0	250	Total							

Summary for Subcatchment GW:

Runoff = 1.78 cfs @ 12.50 hrs, Volume= 0.221 af, Depth> 1.15"

	Α	rea (sf)	CN [Description		
75,060 81 1/3 acre lots, 30% imp,					s. 30% imp	. HSG C
3,400 70 Woods, Good, HSG C						
* 22,219 74 Swale & Pond Grass					•	
100,679 79 Weighted Average					verage	
78,161 77.63% Pervious Area						
	22,518 22.37% Impervious Are					
		22,010	-	.2.07 70 11116	7 (1 VIO 40 7 (1 V	
	Тс	Length	Slope	Velocity	Capacity	Description
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
_	29.3	150	0.0860	0.09	,	Sheet Flow,
						Woods: Dense underbrush n= 0.800 P2= 3.10"
	4.2	220	0.0300	0.87		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
	0.5	110	0.0200	3.41	5.96	· ·
						Bot.W=2.00' D=0.50' Z= 3.0 '/' Top.W=5.00' n= 0.030
	34.0	480	Total			

Summary for Subcatchment LS:

Runoff = 0.71 cfs @ 12.66 hrs, Volume= 0.102 af, Depth> 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr Rainfall=3.10"

_	Α	rea (sf)	CN [Description				
*		13,068	98 Apartments Impervious					
*		23,000	74 <i>A</i>	Apartments	Grass, HS	GC		
		8,306	70 \	Woods, Good, HSG C				
		44,374	ا 80	Veighted A	verage			
	31,306 70.55% Pervious Area							
	13,068 29.45% Impervious Are					ea		
				_				
	Tc	Length	Slope	Velocity	Capacity	Description		
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	11.5	150	0.0800	0.22		Sheet Flow,		
						Grass: Dense n= 0.240 P2= 3.10"		
	0.9	110	0.0800	1.98		Shallow Concentrated Flow,		
						Short Grass Pasture Kv= 7.0 fps		
	33.9	150	0.0600	0.07		Sheet Flow,		
_						Woods: Dense underbrush n= 0.800 P2= 3.10"		
	46.3	410	Total					

Summary for Subcatchment RG:

Runoff = 0.70 cfs @ 12.26 hrs, Volume= 0.066 af, Depth> 1.28"

	Α	rea (sf)	CN D	escription		
		25,952	81 1	/3 acre lot	s, 30% imp	, HSG C
*		1,000	74 S	Swale & Po	nd Grass	
26,952 81 Weighted Average					verage	
	19,166 71.11% Pervious Area					
		7,786	2	8.89% lmp	pervious Are	ea
	_					
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	13.2	140	0.0500	0.18		Sheet Flow,
						Grass: Dense n= 0.240 P2= 3.10"
	4.2	220	0.0300	0.87		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
	0.5	110	0.0200	3.41	5.96	Trap/Vee/Rect Channel Flow,
_						Bot.W=2.00' D=0.50' Z= 3.0 '/' Top.W=5.00' n= 0.030
	17.9	470	Total			

Summary for Reach R1: Perimeter Ditch

[61] Hint: Exceeded Reach R2 outlet invert by 0.67' @ 13.15 hrs

Inflow Area = 65.062 ac, 5.26% Impervious, Inflow Depth > 0.80" Inflow = 20.13 cfs @ 13.15 hrs, Volume= 4.344 af


Outflow = 20.12 cfs @ 13.17 hrs, Volume= 4.341 af, Atten= 0%, Lag= 0.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 6.43 fps, Min. Travel Time= 0.4 min Avg. Velocity = 3.77 fps, Avg. Travel Time= 0.7 min

Peak Storage= 470 cf @ 13.16 hrs, Average Depth at Peak Storage= 0.67' Bank-Full Depth= 4.00', Capacity at Bank-Full= 512.84 cfs

4.00' x 4.00' deep channel, n= 0.035 Side Slope Z-value= 1.0 '/' Top Width= 12.00' Length= 150.0' Slope= 0.0533 '/' Inlet Invert= 206.00', Outlet Invert= 198.00'



Summary for Reach R2: Perimeter Ditch

[62] Warning: Exceeded Reach R3 OUTLET depth by 0.14' @ 13.75 hrs

2 post Type III 24-hr Rainfall=3.10" Printed 1/11/2017

Page 20

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Inflow Area = 62.780 ac, 4.30% Impervious, Inflow Depth > 0.82" Inflow = 20.16 cfs @ 13.12 hrs, Volume= 4.273 af

Outflow = 20.13 cfs @ 13.15 hrs, Volume= 4.266 af, Atten= 0%, Lag= 2.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Max. Velocity= 5.94 fps, Min. Travel Time= 0.8 min Avg. Velocity = 3.50 fps, Avg. Travel Time= 1.4 min

Peak Storage= 983 cf @ 13.14 hrs, Average Depth at Peak Storage= 0.72' Bank-Full Depth= 6.00', Capacity at Bank-Full= 1,055.19 cfs

4.00' x 6.00' deep channel, n= 0.040 Earth, cobble bottom, clean sides Side Slope Z-value= 1.0 '/' Top Width= 16.00' Length= 290.0' Slope= 0.0552 '/' Inlet Invert= 222.00', Outlet Invert= 206.00'



Summary for Reach R3: Perimeter Ditch


Inflow Area = 20.180 ac, 8.42% Impervious, Inflow Depth > 0.87" Inflow = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af

Outflow = 8.93 cfs @ 12.97 hrs, Volume= 1.438 af, Atten= 2%, Lag= 11.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Max. Velocity= 3.05 fps, Min. Travel Time= 6.8 min Avg. Velocity = 1.62 fps, Avg. Travel Time= 12.9 min

Peak Storage= 3,669 cf @ 12.86 hrs, Average Depth at Peak Storage= 0.78' Bank-Full Depth= 4.00', Capacity at Bank-Full= 195.24 cfs

3.00' x 4.00' deep channel, n= 0.040 Earth, cobble bottom, clean sides Side Slope Z-value= 1.0 '/' Top Width= 11.00' Length= 1,250.0' Slope= 0.0144 '/' Inlet Invert= 240.00', Outlet Invert= 222.00'



1636 Post

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Reach R4: Downstream of Buffer

Inflow Area = 1.019 ac, 29.45% Impervious, Inflow Depth > 1.20" Inflow = 0.71 cfs @ 12.66 hrs, Volume= 0.102 af

Outflow = 0.70 cfs @ 12.84 hrs, Volume= 0.101 af, Atten= 2%, Lag= 10.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Max. Velocity= 0.72 fps, Min. Travel Time= 6.2 min

Avg. Velocity = 0.72 lps, Min. Travel Time= 6.2 min. Avg. Velocity = 0.31 fps, Avg. Travel Time= 14.3 min.

Peak Storage= 261 cf @ 12.73 hrs, Average Depth at Peak Storage= 0.09' Bank-Full Depth= 0.50', Capacity at Bank-Full= 13.95 cfs

10.00' x 0.50' deep channel, n= 0.080 Earth, long dense weeds Side Slope Z-value= 8.0 '/' Top Width= 18.00'

Length= 270.0' Slope= 0.0407 '/'

Inlet Invert= 204.00', Outlet Invert= 193.00'



Summary for Reach R5:

[81] Warning: Exceeded Pond RG1 by 0.08' @ 12.35 hrs

Inflow Area = 0.619 ac, 28.89% Impervious, Inflow Depth > 0.93" Inflow = 0.67 cfs @ 12.35 hrs, Volume= 0.048 af

Outflow = 0.65 cfs @ 12.41 hrs, Volume= 0.048 af, Atten= 4%, Lag= 3.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 0.96 fps, Min. Travel Time= 1.4 min Avg. Velocity = 0.38 fps, Avg. Travel Time= 3.4 min

Peak Storage= 59 cf @ 12.37 hrs, Average Depth at Peak Storage= 0.13' Bank-Full Depth= 0.50', Capacity at Bank-Full= 9.53 cfs

 $5.00' \times 0.50'$ deep channel, n= 0.080 Earth, long dense weeds

Side Slope Z-value= 8.0 '/' Top Width= 13.00'

Length= 78.0' Slope= 0.0538 '/'

Inlet Invert= 208.00', Outlet Invert= 203.80'



1636 Post

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Reach R6:

[52] Hint: Inlet/Outlet conditions not evaluated

[62] Warning: Exceeded Reach R5 OUTLET depth by 0.15' @ 12.40 hrs

Inflow Area = 0.619 ac, 28.89% Impervious, Inflow Depth > 0.93" Inflow = 0.65 cfs @ 12.41 hrs, Volume= 0.048 af


Outflow = 0.64 cfs @ 12.41 hrs, Volume= 0.048 af, Atten= 1%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 3.57 fps, Min. Travel Time= 0.2 min Avg. Velocity = 1.70 fps, Avg. Travel Time= 0.4 min

Peak Storage= 7 cf @ 12.41 hrs, Average Depth at Peak Storage= 0.26' Bank-Full Depth= 1.25', Capacity at Bank-Full= 7.00 cfs

15.0" Round Pipe n= 0.012 Length= 40.0' Slope= 0.0100 '/' Inlet Invert= 203.80', Outlet Invert= 203.40'



Summary for Reach R7:

[63] Warning: Exceeded Reach R6 INLET depth by 4.60' @ 5.00 hrs

Inflow Area = 0.619 ac, 28.89% Impervious, Inflow Depth > 0.93" Inflow = 0.64 cfs @ 12.41 hrs. Volume= 0.048 af

Outflow = 0.44 cfs @ 12.74 hrs, Volume= 0.047 af, Atten= 32%, Lag= 19.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 0.64 fps, Min. Travel Time= 9.4 min Avg. Velocity = 0.31 fps, Avg. Travel Time= 19.6 min

Peak Storage= 246 cf @ 12.58 hrs, Average Depth at Peak Storage= 0.12' Bank-Full Depth= 0.50', Capacity at Bank-Full= 6.57 cfs

 $5.00' \times 0.50'$ deep channel, n= 0.100 Earth, dense brush, high stage Side Slope Z-value= 8.0 '/' Top Width= 13.00' Length= 360.0' Slope= 0.0400 '/' Inlet Invert= 208.40', Outlet Invert= 194.00'

1636 PostPrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC



Summary for Reach SP#1: Study Point #1 - Outlet of Ditch

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 66.699 ac, 5.18% Impervious, Inflow Depth > 0.80" Inflow = 20.39 cfs @ 13.16 hrs, Volume= 4.441 af

Outflow = 20.39 cfs @ 13.16 hrs, Volume= 4.441 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Reach SP#2: Study Point #2 - Wetland adjacent to Highland

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 23.163 ac, 15.29% Impervious, Inflow Depth > 0.76" Inflow = 6.71 cfs @ 12.85 hrs, Volume= 1.474 af

Outflow = 6.71 cfs @ 12.85 hrs, Volume= 1.474 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond CB: CB

Not modeled because watershed enters closed stormwater system over a series of catch basins.

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 20.180 ac, 8.42% Impervious, Inflow Depth > 0.87" Inflow = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af

Primary = 9.13 cfs @ 12.78 hrs, Volume= 1.457 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond CB1:

[79] Warning: Submerged Pond CB2 Primary device # 1 OUTLET by 0.47'

Inflow Area = 6.555 ac, 27.74% Impervious, Inflow Depth > 1.18" Inflow = 3.99 cfs @ 12.40 hrs. Volume= 0.644 af

Outflow = 3.99 cfs @ 12.40 hrs, Volume= 0.644 af, Atten= 0%, Lag= 0.0 min

Primary = 3.99 cfs @ 12.40 hrs, Volume= 0.644 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

1636 Post

Prepared by {enter your company name here}
HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Page 24

Peak Elev= 201.41' @ 12.40 hrs

Flood Elev= 204.74'

Device	Routing	Invert	Outlet Devices
#1	Primary	200.44'	24.0" Round Culvert
			L= 144.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 196.00' S= 0.0308 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=3.99 cfs @ 12.40 hrs HW=201.41' (Free Discharge) 1=Culvert (Inlet Controls 3.99 cfs @ 2.65 fps)

Summary for Pond CB10:

Inflow Area = 0.054 ac, 68.52% Impervious, Inflow Depth > 1.95" Inflow = 0.14 cfs @ 12.04 hrs, Volume= 0.009 af

Outflow = 0.14 cfs @ 12.04 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary = 0.14 cfs @ 12.04 hrs, Volume= 0.009 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 232.92' @ 12.04 hrs

Flood Elev= 235.98'

Device	Routing	Invert	Outlet Devices
#1	Primary	232.73'	15.0" Round Culvert
			L= 16.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 232 53' S= 0.0125 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.14 cfs @ 12.04 hrs HW=232.92' (Free Discharge) 1=Culvert (Inlet Controls 0.14 cfs @ 1.17 fps)

Summary for Pond CB11:

Inflow Area = 0.057 ac, 70.18% Impervious, Inflow Depth > 2.04" Inflow = 0.16 cfs @ 12.04 hrs, Volume= 0.010 af

Outflow = 0.16 cfs @ 12.04 hrs, Volume= 0.010 af, Atten= 0%, Lag= 0.0 min

Primary = 0.16 cfs @ 12.04 hrs, Volume= 0.010 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 203.21' @ 12.03 hrs

Flood Elev= 206.26'

Device	Routing	Invert	Outlet Devices
#1	Primary	203.01'	15.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 202.81' S= 0.0125 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.15 cfs @ 12.04 hrs HW=203.21' (Free Discharge) 1=Culvert (Inlet Controls 0.15 cfs @ 1.19 fps)

1636 PostPrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Pond CB12:

Inflow Area = 0.271 ac, 39.89% Impervious, Inflow Depth > 1.42" Inflow = 0.46 cfs @ 12.11 hrs, Volume= 0.032 af

Outflow = 0.46 cfs @ 12.11 hrs, Volume= 0.032 af, Atten= 0%, Lag= 0.0 min

Primary = 0.46 cfs @ 12.11 hrs, Volume= 0.032 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 208.60' @ 12.11 hrs

Flood Elev= 211.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	208.25'	15.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 208.05' S= 0.0125 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.45 cfs @ 12.11 hrs HW=208.60' (Free Discharge) 1=Culvert (Inlet Controls 0.45 cfs @ 1.59 fps)

Summary for Pond CB13:

Inflow Area = 0.607 ac, 33.11% Impervious, Inflow Depth > 1.28" Inflow = 0.77 cfs @ 12.19 hrs, Volume= 0.065 af

Outflow = 0.77 cfs @ 12.19 hrs, Volume= 0.065 af, Atten= 0%, Lag= 0.0 min

Primary = 0.77 cfs @ 12.19 hrs. Volume= 0.065 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 223.48' @ 12.19 hrs

Flood Elev= 226.26'

Device	Routing	Invert	Outlet Devices
#1	Primary	223.01'	15.0" Round Culvert
	-		L= 16.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 222.81' S= 0.0125 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.76 cfs @ 12.19 hrs HW=223.48' (Free Discharge) 1=Culvert (Inlet Controls 0.76 cfs @ 1.83 fps)

Summary for Pond CB14:

[79] Warning: Submerged Pond CB15 Primary device # 1 INLET by 0.59'

Inflow Area = 3.487 ac, 20.48% Impervious, Inflow Depth > 1.03" Inflow = 1.96 cfs @ 12.58 hrs, Volume= 0.300 af

Outflow = 1.96 cfs @ 12.58 hrs, Volume= 0.300 af, Atten= 0%, Lag= 0.0 min

Primary = 1.96 cfs @ 12.58 hrs, Volume= 0.300 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Page 26

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Peak Elev= 213.95' @ 12.58 hrs

Flood Elev= 216.61'

Device	Routing	Invert	Outlet Devices
#1	Primary	213.16'	15.0" Round Culvert
			L= 128.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 212.52' S= 0.0050 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=1.96 cfs @ 12.58 hrs HW=213.95' (Free Discharge) 1=Culvert (Inlet Controls 1.96 cfs @ 2.39 fps)

Summary for Pond CB15:

Inflow Area = 3.342 ac, 18.29% Impervious, Inflow Depth > 0.99" Inflow = 1.92 cfs @ 12.59 hrs, Volume= 0.275 af

Outflow = 1.92 cfs @ 12.59 hrs, Volume= 0.275 af, Atten= 0%, Lag= 0.0 min

Primary = 1.92 cfs @ 12.59 hrs, Volume= 0.275 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 214.14' @ 12.59 hrs

Flood Elev= 216.61'

Device	Routing	Invert	Outlet Devices
#1	Primary	213.36'	15.0" Round Culvert
			L= 16.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert- 213 16' S- 0.0125 '/' Cc- 0.900 n- 0.012

Primary OutFlow Max=1.91 cfs @ 12.59 hrs HW=214.14' (Free Discharge) 1=Culvert (Barrel Controls 1.91 cfs @ 3.38 fps)

Summary for Pond CB16:

Inflow Area = 2.282 ac, 31.56% Impervious, Inflow Depth > 1.30"

Inflow = 1.20 cfs @ 12.63 hrs, Volume= 0.247 af

Outflow = 1.20 cfs @ 12.63 hrs, Volume= 0.247 af, Atten= 0%, Lag= 0.0 min

Primary = 1.20 cfs @ 12.63 hrs, Volume= 0.247 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 213.92' @ 12.63 hrs

Flood Elev= 216.61'

Device	Routing	Invert	Outlet Devices
#1	Primary	213.36'	18.0" Round Culvert L= 50.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 212.00' S= 0.0272 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=1.20 cfs @ 12.63 hrs HW=213.92' (Free Discharge) 1=Culvert (Inlet Controls 1.20 cfs @ 2.01 fps)

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Pond CB2:

[79] Warning: Submerged Pond CB3 Primary device # 1 OUTLET by 1.04'

Inflow Area = 6.015 ac, 26.09% Impervious, Inflow Depth > 1.14" Inflow 3.58 cfs @ 12.44 hrs, Volume= 0.574 af =

Outflow = 3.58 cfs @ 12.44 hrs, Volume= 0.574 af, Atten= 0%, Lag= 0.0 min

3.58 cfs @ 12.44 hrs. Volume= Primary 0.574 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 202.60' @ 12.44 hrs

Flood Elev= 206.26'

Device	Routing	Invert	Outlet Devices
#1	Primary	201.56'	18.0" Round Culvert
			L= 124.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 200.94' S= 0.0050 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=3.57 cfs @ 12.44 hrs HW=202.60' (Free Discharge)

1=Culvert (Inlet Controls 3.57 cfs @ 2.74 fps)

Summary for Pond CB3:

Inflow Area = 5.512 ac, 25.63% Impervious, Inflow Depth > 1.14" Inflow = 3.20 cfs @ 12.44 hrs. Volume= 0.521 af

3.20 cfs @ 12.44 hrs, Volume= Outflow 0.521 af, Atten= 0%, Lag= 0.0 min =

3.20 cfs @ 12.44 hrs, Volume= 0.521 af Primary

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 207.77' @ 12.44 hrs

Flood Elev= 211.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	206.80'	18.0" Round Culvert L= 122.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 201.56' S= 0.0430 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=3.20 cfs @ 12.44 hrs HW=207.77' (Free Discharge) 1=Culvert (Inlet Controls 3.20 cfs @ 2.65 fps)

Summary for Pond CB4:

[79] Warning: Submerged Pond CB5 Primary device # 1 INLET by 0.75'

Inflow Area = 4.667 ac, 25.11% Impervious, Inflow Depth > 1.12" Inflow 2.61 cfs @ 12.46 hrs, Volume= 0.437 af

Outflow 2.61 cfs @ 12.46 hrs, Volume= 0.437 af, Atten= 0%, Lag= 0.0 min

2.61 cfs @ 12.46 hrs, Volume= Primary 0.437 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Page 28

Peak Elev= 213.27' @ 12.46 hrs

Flood Elev= 217.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	212.32'	15.0" Round Culvert L= 112.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 208.05' S= 0.0381 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=2.61 cfs @ 12.46 hrs HW=213.27' (Free Discharge) 1=Culvert (Inlet Controls 2.61 cfs @ 2.61 fps)

Summary for Pond CB5:

[79] Warning: Submerged Pond CB14 Primary device # 1 INLET by 0.35'

Inflow Area = 4.648 ac, 24.82% Impervious, Inflow Depth > 1.12" Inflow = 2.60 cfs @ 12.47 hrs, Volume= 0.433 af

Outflow = 2.60 cfs @ 12.47 hrs, Volume= 0.433 af, Atten= 0%, Lag= 0.0 min

Primary = 2.60 cfs @ 12.47 hrs, Volume= 0.433 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 213.51' @ 12.47 hrs

Flood Elev= 218.96'

Device	Routing	Invert	Outlet Devices
#1	Primary	212.52'	15.0" Round Culvert
			L= 32.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 212.32' S= 0.0063 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=2.60 cfs @ 12.47 hrs HW=213.51' (Free Discharge) 1=Culvert (Barrel Controls 2.60 cfs @ 3.42 fps)

Summary for Pond CB6:

[82] Warning: Early inflow requires earlier time span

[79] Warning: Submerged Pond CB7 Primary device # 1 OUTLET by 0.56'

Inflow Area = 1.095 ac, 35.95% Impervious, Inflow Depth > 1.34" Inflow = 1.07 cfs @ 12.19 hrs, Volume= 0.122 af

Outflow = 1.07 cfs @ 12.19 hrs, Volume= 0.122 af, Atten= 0%, Lag= 0.0 min

Primary = 1.07 cfs @ 12.19 hrs, Volume= 0.122 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 216.27' @ 12.19 hrs

Flood Elev= 218.96'

Device	Routing	Invert	Outlet Devices
#1	Primary		15.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 215.51' S= 0.0125 '/' Cc= 0.900 n= 0.012

1636 PostPrepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Primary OutFlow Max=1.07 cfs @ 12.19 hrs HW=216.27' (Free Discharge) 1=Culvert (Inlet Controls 1.07 cfs @ 2.01 fps)

Summary for Pond CB7:

[82] Warning: Early inflow requires earlier time span

[79] Warning: Submerged Pond CB13 Primary device # 1 INLET by 0.33' [79] Warning: Submerged Pond CB8 Primary device # 1 OUTLET by 0.53'

Inflow Area = 0.798 ac, 41.73% Impervious, Inflow Depth > 1.45" Inflow = 0.98 cfs @ 12.18 hrs, Volume= 0.097 af

Outflow = 0.98 cfs @ 12.18 hrs, Volume= 0.097 af, Atten= 0%, Lag= 0.0 min

Primary = 0.98 cfs @ 12.18 hrs, Volume= 0.097 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 223.34' @ 12.18 hrs

Flood Elev= 226.26'

Device	Routing	Invert	Outlet Devices
#1	Primary	222.81'	15.0" Round Culvert L= 126.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 215.71' S= 0.0563.1/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.97 cfs @ 12.18 hrs HW=223.34' (Free Discharge) 1=Culvert (Inlet Controls 0.97 cfs @ 1.96 fps)

Summary for Pond CB8:

[82] Warning: Early inflow requires earlier time span

[79] Warning: Submerged Pond CB9 Primary device # 1 OUTLET by 0.30'

Inflow Area = 0.115 ac, 85.22% Impervious, Inflow Depth > 2.34" Inflow = 0.34 cfs @ 12.03 hrs, Volume= 0.022 af

Outflow = 0.34 cfs @ 12.03 hrs, Volume= 0.022 af, Atten= 0%, Lag= 0.0 min

Primary = 0.34 cfs @ 12.03 hrs, Volume= 0.022 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 229.53' @ 12.03 hrs

Flood Elev= 232.48'

Device	Routing	Invert	Outlet Devices
#1	Primary	229.23'	15.0" Round Culvert
			L= 126.0' CPP, projecting, no headwall, Ke= 0.900
			Outlet Invert= 222.81' S= 0.0510 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.33 cfs @ 12.03 hrs HW=229.53' (Free Discharge) 1=Culvert (Inlet Controls 0.33 cfs @ 1.46 fps)

1636 PostPrepared by {enter your company name here}

HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Pond CB9:

[82] Warning: Early inflow requires earlier time span

[79] Warning: Submerged Pond CB10 Primary device # 1 INLET by 0.05'

Inflow Area = 0.083 ac, 79.52% Impervious, Inflow Depth > 2.21" Inflow = 0.24 cfs @ 12.03 hrs, Volume= 0.015 af

Outflow = 0.24 cfs @ 12.03 hrs, Volume= 0.015 af, Atten= 0%, Lag= 0.0 min

Primary = 0.24 cfs @ 12.03 hrs, Volume= 0.015 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 232.78' @ 12.03 hrs

Flood Elev= 235.98'

Device	Routing	Invert	Outlet Devices
#1	Primary	232.53'	15.0" Round Culvert L= 84.0' CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 229.23' S= 0.0393 '/' Cc= 0.900 n= 0.012

Primary OutFlow Max=0.23 cfs @ 12.03 hrs HW=232.78' (Free Discharge) 1=Culvert (Inlet Controls 0.23 cfs @ 1.33 fps)

Summary for Pond FB1: Filter Basin #1

Inflow Area = 2.282 ac, 31.56% Impervious, Inflow Depth > 1.30" Inflow = 1.20 cfs @ 12.63 hrs, Volume= 0.247 af

Outflow = 0.30 cfs @ 14.76 hrs, Volume= 0.078 af, Atten= 75%, Lag= 128.2 min

Primary = 0.30 cfs @ 14.76 hrs, Volume= 0.078 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 207.05' @ 14.76 hrs Surf.Area= 5,523 sf Storage= 7,537 cf

Plug-Flow detention time= 255.2 min calculated for 0.078 af (32% of inflow)

Center-of-Mass det. time= 152.3 min (991.2 - 838.9)

Volume	Invert	Avail.Sto	rage Storage	Description	
#1	205.50'	16,44	40 cf Custom	Stage Data (Pi	rismatic)Listed below (Recalc)
Elevation (feet)	Sur	f.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	
205.50		4,200	0	0	
206.00		4,627	2,207	2,207	
207.00		5,480	5,054	7,260	
208.00		6,333	5,907	13,167	
208.50		6,760	3,273	16,440	
Device R	outing	Invert	Outlet Devices)	

#1 Primary 207.00' **10.0' long x 13.0' breadth Broad-Crested Rectangular Weir** Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60

Coef. (English) 2.60 2.64 2.70 2.66 2.65 2.66 2.65 2.63

Primary OutFlow Max=0.29 cfs @ 14.76 hrs HW=207.05' (Free Discharge) 1=Broad-Crested Rectangular Weir (Weir Controls 0.29 cfs @ 0.58 fps)

Summary for Pond GW1: Gravel Wetland #1

Inflow Area = 8.866 ac, 26.34% Impervious, Inflow Depth > 1.17"

Inflow = 5.72 cfs @ 12.44 hrs, Volume= 0.865 af

Outflow = 0.90 cfs @ 14.62 hrs, Volume= 0.362 af, Atten= 84%, Lag= 130.8 min

Primary = 0.90 cfs @ 14.62 hrs, Volume= 0.362 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 194.98' @ 14.62 hrs Surf.Area= 14,006 sf Storage= 24,443 cf

Plug-Flow detention time= 240.2 min calculated for 0.361 af (42% of inflow)

Center-of-Mass det. time= 147.3 min (968.7 - 821.4)

Volume	Inv	ert Ava	il.Storage	Storage	Description	
#1	193.	00'	56,317 cf	Custom	Stage Data (Pr	rismatic)Listed below (Recalc)
Elevation		Surf.Area		c.Store	Cum.Store	
(fee	et)	(sq-ft)	(cubi	c-feet)	(cubic-feet)	
193.0	00	10,550		0	0	
194.0	00	12,450		11,500	11,500	
194.5	50	13,400		6,463	17,963	
194.5	51	13,200		133	18,095	
195.0	00	14,046		6,675	24,771	
196.0	00	15,773	•	14,910	39,680	
197.0	00	17,500		16,637	56,317	
Device	Routing	In	vert Outl	et Device:	S	
#1	Primary	194	.50' 18.0	" Round	Culvert	
			L= 4	10.0' CPF	P, projecting, no	headwall, Ke= 0.900
			Outl	et Invert=	193.00' S= 0.0	0375 '/' Cc= 0.900 n= 0.012
#2	Primary	196	5.20' 15.0	long x	13.0' breadth B	road-Crested Rectangular Weir
	_		Hea	d (feet) 0	.20 0.40 0.60	0.80 1.00 1.20 1.40 1.60

Primary OutFlow Max=0.90 cfs @ 14.62 hrs HW=194.98' (Free Discharge)

T-1=Culvert (Inlet Controls 0.90 cfs @ 1.86 fps)

-2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Summary for Pond RG1: Rain Garden #1

Coef. (English) 2.60 2.64 2.70 2.66 2.65 2.66 2.65 2.63

Inflow Area = 0.619 ac, 28.89% Impervious, Inflow Depth > 1.28" Inflow = 0.70 cfs @ 12.26 hrs. Volume= 0.066 af

Outflow = 0.67 cfs @ 12.35 hrs, Volume= 0.048 af, Atten= 4%, Lag= 5.4 min

Primary = 0.67 cfs @ 12.35 hrs, Volume= 0.048 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Page 32


1636 PostPrepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Peak Elev= 208.04' @ 12.35 hrs Surf.Area= 970 sf Storage= 821 cf

Plug-Flow detention time= 101.3 min calculated for 0.048 af (73% of inflow) Center-of-Mass det. time= 37.6 min (849.3 - 811.7)

Volume	Inv	ert Avail	Storage	Storage D	Description				
#1	207.	00'	1,385 cf	Custom 9	Stage Data (P	rismatic)Listed below (Recalc)			
Elevation (fee		Surf.Area (sq-ft)		:.Store c-feet)	Cum.Store (cubic-feet)				
207.0	00	640		0	0				
208.0	00	920		780	780				
208.5	50	1,500		605	1,385				
Device	Routing	Inv	ert Outl	et Devices					
#1	Primary	208.	00' 30.0	long x 10	0.0' breadth B	road-Crested Rectangular Weir			
			Hea	Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60					
			Coe	f. (English)	2.49 2.56 2.	70 2.69 2.68 2.69 2.67 2.64			

Primary OutFlow Max=0.66 cfs @ 12.35 hrs HW=208.04' (Free Discharge) 1=Broad-Crested Rectangular Weir (Weir Controls 0.66 cfs @ 0.51 fps)



1636 PostPrepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Subcatchment 15a:

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method						
Subcatchment1:	Runoff Area=0.540 ac 46.09% Impervious Runoff Depth>2.81" Flow Length=230' Tc=10.4 min CN=85 Runoff=1.61 cfs 0.127 af					
Subcatchment 2:	Runoff Area=0.446 ac 26.21% Impervious Runoff Depth>2.27" Flow Length=370' Tc=33.5 min CN=79 Runoff=0.69 cfs 0.084 af					
Subcatchment3:	Runoff Area=0.574 ac 23.14% Impervious Runoff Depth>2.19" Flow Length=300' Tc=30.8 min CN=78 Runoff=0.89 cfs 0.105 af					
Subcatchment 4:	Runoff Area=0.019 ac 94.74% Impervious Runoff Depth>3.98" Tc=2.0 min CN=97 Runoff=0.09 cfs 0.006 af					
Subcatchment 5:	Runoff Area=0.066 ac 69.70% Impervious Runoff Depth>3.40" Tc=2.0 min CN=91 Runoff=0.29 cfs 0.019 af					
Subcatchment 6:	Runoff Area=0.297 ac 20.44% Impervious Runoff Depth>2.11" Flow Length=240' Tc=34.9 min CN=77 Runoff=0.42 cfs 0.052 af					
Subcatchment7:	Runoff Area=0.076 ac 44.74% Impervious Runoff Depth>2.73" Tc=2.0 min CN=84 Runoff=0.28 cfs 0.017 af					
Subcatchment8:	Runoff Area=0.032 ac 100.00% Impervious Runoff Depth>4.05" Tc=2.0 min CN=98 Runoff=0.16 cfs 0.011 af					
Subcatchment9:	Runoff Area=0.029 ac 100.00% Impervious Runoff Depth>4.05" Tc=2.0 min CN=98 Runoff=0.14 cfs 0.010 af					
Subcatchment 10:	Runoff Area=0.054 ac 68.52% Impervious Runoff Depth>3.30" Tc=2.0 min CN=90 Runoff=0.23 cfs 0.015 af					
Subcatchment11:	Runoff Area=0.057 ac 70.18% Impervious Runoff Depth>3.40" Tc=2.0 min CN=91 Runoff=0.25 cfs 0.016 af					
Subcatchment 12:	Runoff Area=0.271 ac 39.89% Impervious Runoff Depth>2.63" Flow Length=140' Tc=7.2 min CN=83 Runoff=0.85 cfs 0.059 af					
Subcatchment 13:	Runoff Area=0.607 ac 33.11% Impervious Runoff Depth>2.45" Flow Length=294' Tc=13.2 min CN=81 Runoff=1.47 cfs 0.124 af					
Subcatchment14:	Runoff Area=0.145 ac 71.03% Impervious Runoff Depth>3.40" Tc=2.0 min CN=91 Runoff=0.64 cfs 0.041 af					
Subcatchment 15:	Runoff Area=2.638 ac 18.28% Impervious Runoff Depth>2.02"					

Flow Length=630' Tc=44.3 min CN=76 Runoff=3.17 cfs 0.444 af

Flow Length=285' Tc=28.0 min CN=77 Runoff=1.10 cfs 0.124 af

Runoff Area=0.704 ac 18.32% Impervious Runoff Depth>2.11"

1636 Post Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Subcatchment 16: Runoff Area=0.690 ac 45.77% Impervious Runoff Depth>2.80" Flow Length=360' Tc=28.0 min CN=85 Runoff=1.41 cfs 0.161 af

Subcatchment 100: Runoff Area=551,455 sf 5.75% Impervious Runoff Depth>1.93" Flow Length=380' Tc=60.3 min CN=75 Runoff=12.25 cfs 2.035 af

Subcatchment 300: Runoff Area=71,335 sf 2.24% Impervious Runoff Depth>1.66" Flow Length=270' Slope=0.1000'/' Tc=28.9 min CN=71 Runoff=1.95 cfs 0.226 af

Subcatchment 400: Offsite

Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>1.75"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=28.76 cfs 6.222 af

Subcatchment 500: Offsite

Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>1.86"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=20.31 cfs 3.127 af

Subcatchment FB:Runoff Area=69,332 sf 25.41% Impervious Runoff Depth>2.32"
Flow Length=250' Tc=72.0 min CN=80 Runoff=1.67 cfs 0.308 af

Subcatchment GW:Runoff Area=100,679 sf 22.37% Impervious Runoff Depth>2.27"
Flow Length=480' Tc=34.0 min CN=79 Runoff=3.55 cfs 0.437 af

Subcatchment LS:

Runoff Area=44,374 sf 29.45% Impervious Runoff Depth>2.34"
Flow Length=410' Tc=46.3 min CN=80 Runoff=1.38 cfs 0.199 af

Subcatchment RG:

Runoff Area=26,952 sf 28.89% Impervious Runoff Depth>2.45"
Flow Length=470' Tc=17.9 min CN=81 Runoff=1.34 cfs 0.126 af

Reach R2: Perimeter DitchAvg. Depth=1.16' Max Vel=7.64 fps Inflow=45.56 cfs 9.322 af n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=45.51 cfs 9.312 af

Reach R3: Perimeter DitchAvg. Depth=1.23' Max Vel=3.85 fps Inflow=20.31 cfs 3.127 af n=0.040 L=1,250.0' S=0.0144 '/' Capacity=195.24 cfs Outflow=20.02 cfs 3.100 af

Reach R4: Downstream of BufferAvg. Depth=0.13' Max Vel=0.92 fps Inflow=1.38 cfs 0.199 af n=0.080 L=270.0' S=0.0407'/ Capacity=13.95 cfs Outflow=1.37 cfs 0.197 af

Reach R5: Avg. Depth=0.18' Max Vel=1.18 fps Inflow=1.34 cfs 0.108 af n=0.080 L=78.0' S=0.0538 '/' Capacity=9.53 cfs Outflow=1.33 cfs 0.108 af

Reach R6: Avg. Depth=0.37' Max Vel=4.38 fps Inflow=1.33 cfs 0.108 af 15.0" Round Pipe n=0.012 L=40.0' S=0.0100 '/' Capacity=7.00 cfs Outflow=1.32 cfs 0.108 af

Reach R7: Avg. Depth=0.20' Max Vel=0.89 fps Inflow=1.32 cfs 0.108 af n=0.100 L=360.0' S=0.0400 '/' Capacity=6.57 cfs Outflow=1.19 cfs 0.107 af

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=47.99 cfs 9.831 af Outflow=47.99 cfs 9.831 af

10 post Type III 24-hr Rainfall=4.60" Printed 1/11/2017

Page 4

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Reach SP#2: Study Point #2 - Wetland adjacent to Highland Inflow=18.54 cfs 3.501 af
Outflow=18.54 cfs 3.501 af

Pond CB: CB Inflow=20.31 cfs 3.127 af Primary=20.31 cfs 3.127 af

Pond CB1: Peak Elev=201.90' Inflow=7.99 cfs 1.254 af

24.0" Round Culvert n=0.012 L=144.0' S=0.0308 '/' Outflow=7.99 cfs 1.254 af

Pond CB10: Peak Elev=232.98' Inflow=0.23 cfs 0.015 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.23 cfs 0.015 af

Pond CB11: Peak Elev=203.27' Inflow=0.25 cfs 0.016 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.25 cfs 0.016 af

Pond CB12: Peak Elev=208.74' Inflow=0.85 cfs 0.059 af

15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.85 cfs 0.059 af

Pond CB13: Peak Elev=223.68' Inflow=1.47 cfs 0.124 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=1.47 cfs 0.124 af

Pond CB14: Peak Elev=214.57' Inflow=4.13 cfs 0.609 af

15.0" Round Culvert n=0.012 L=128.0' S=0.0050 '/' Outflow=4.13 cfs 0.609 af

Pond CB15: Peak Elev=214.74' Inflow=4.05 cfs 0.568 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=4.05 cfs 0.568 af

Pond CB16: Peak Elev=214.16' Inflow=2.29 cfs 0.468 af

18.0" Round Culvert n=0.012 L=50.0' S=0.0272 '/' Outflow=2.29 cfs 0.468 af

Pond CB2: Peak Elev=203.48' Inflow=7.27 cfs 1.128 af 18.0" Round Culvert n=0.012 L=124.0' S=0.0050 '/' Outflow=7.27 cfs 1.128 af

Pond CB3: Peak Elev=208.50' Inflow=6.54 cfs 1.027 af

18.0" Round Culvert n=0.012 L=122.0' S=0.0430 '/' Outflow=6.54 cfs 1.027 af

Pond CB4: Peak Elev=214.27' Inflow=5.38 cfs 0.863 af

Pond CB5: Peak Elev=214.47' Inflow=5.36 cfs 0.857 af

15.0" Round Culvert n=0.012 L=32.0' S=0.0063 '/' Outflow=5.36 cfs 0.857 af

Pond CB6: Peak Elev=216.52' Inflow=2.03 cfs 0.229 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=2.03 cfs 0.229 af

Pond CB7: Peak Elev=223.56' Inflow=1.81 cfs 0.177 af

15.0" Round Culvert n=0.012 L=126.0' S=0.0563 '/' Outflow=1.81 cfs 0.177 af

Pond CB8: Peak Elev=229.61' Inflow=0.53 cfs 0.035 af

15.0" Round Culvert n=0.012 L=126.0' S=0.0510 '/' Outflow=0.53 cfs 0.035 af

15.0" Round Culvert n=0.012 L=112.0' S=0.0381 '/' Outflow=5.38 cfs 0.863 af

10 post Type III 24-hr Rainfall=4.60" Printed 1/11/2017

1636 PostPrepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Pond CB9: Peak Elev=232.85' Inflow=0.38 cfs 0.025 af 15.0" Round Culvert n=0.012 L=84.0' S=0.0393 '/' Outflow=0.38 cfs 0.025 af

Pond FB1: Filter Basin #1 Peak Elev=207.18' Storage=8,237 cf Inflow=2.29 cfs 0.468 af

Outflow=1.92 cfs 0.298 af

Page 5


Pond GW1: Gravel Wetland #1 Peak Elev=195.74' Storage=35,693 cf Inflow=11.47 cfs 1.691 af

Outflow=4.69 cfs 1.162 af

Pond RG1: Rain Garden #1 Peak Elev=208.07' Storage=846 cf Inflow=1.34 cfs 0.126 af

Outflow=1.34 cfs 0.108 af

Total Runoff Area = 89.863 ac Runoff Volume = 14.095 af Average Runoff Depth = 1.88" 92.21% Pervious = 82.864 ac 7.79% Impervious = 6.999 ac



1636 Post Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Subcatchment 15a:

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method						
Subcatchment1:	Runoff Area=0.540 ac 46.09% Impervious Runoff Depth>3.87" Flow Length=230' Tc=10.4 min CN=85 Runoff=2.19 cfs 0.174 af					
Subcatchment 2:	Runoff Area=0.446 ac 26.21% Impervious Runoff Depth>3.25" Flow Length=370' Tc=33.5 min CN=79 Runoff=0.98 cfs 0.121 af					
Subcatchment3:	Runoff Area=0.574 ac 23.14% Impervious Runoff Depth>3.15" Flow Length=300' Tc=30.8 min CN=78 Runoff=1.28 cfs 0.151 af					
Subcatchment4:	Runoff Area=0.019 ac 94.74% Impervious Runoff Depth>5.07" Tc=2.0 min CN=97 Runoff=0.12 cfs 0.008 af					
Subcatchment 5:	Runoff Area=0.066 ac 69.70% Impervious Runoff Depth>4.50" Tc=2.0 min CN=91 Runoff=0.38 cfs 0.025 af					
Subcatchment 6:	Runoff Area=0.297 ac 20.44% Impervious Runoff Depth>3.06" Flow Length=240' Tc=34.9 min CN=77 Runoff=0.61 cfs 0.076 af					
Subcatchment7:	Runoff Area=0.076 ac 44.74% Impervious Runoff Depth>3.78" Tc=2.0 min CN=84 Runoff=0.38 cfs 0.024 af					
Subcatchment8:	Runoff Area=0.032 ac 100.00% Impervious Runoff Depth>5.15" Tc=2.0 min CN=98 Runoff=0.20 cfs 0.014 af					
Subcatchment9:	Runoff Area=0.029 ac 100.00% Impervious Runoff Depth>5.15" Tc=2.0 min CN=98 Runoff=0.18 cfs 0.012 af					
Subcatchment 10:	Runoff Area=0.054 ac 68.52% Impervious Runoff Depth>4.40" Tc=2.0 min CN=90 Runoff=0.31 cfs 0.020 af					
Subcatchment11:	Runoff Area=0.057 ac 70.18% Impervious Runoff Depth>4.50" Tc=2.0 min CN=91 Runoff=0.33 cfs 0.021 af					
Subcatchment12:	Runoff Area=0.271 ac 39.89% Impervious Runoff Depth>3.67" Flow Length=140' Tc=7.2 min CN=83 Runoff=1.16 cfs 0.083 af					
Subcatchment 13:	Runoff Area=0.607 ac 33.11% Impervious Runoff Depth>3.46" Flow Length=294' Tc=13.2 min CN=81 Runoff=2.06 cfs 0.175 af					
Subcatchment14:	Runoff Area=0.145 ac 71.03% Impervious Runoff Depth>4.50" Tc=2.0 min CN=91 Runoff=0.83 cfs 0.054 af					
Subcatchment 15:	Runoff Area=2.638 ac 18.28% Impervious Runoff Depth>2.95" Flow Length=630' Tc=44.3 min CN=76 Runoff=4.62 cfs 0.649 af					

Runoff Area=0.704 ac 18.32% Impervious Runoff Depth>3.06"

Flow Length=285' Tc=28.0 min CN=77 Runoff=1.59 cfs 0.180 af

1636 Post Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Subcatchment 16: Runoff Area=0.690 ac 45.77% Impervious Runoff Depth>3.85" Flow Length=360' Tc=28.0 min CN=85 Runoff=1.91 cfs 0.221 af

Subcatchment 100: Runoff Area=551,455 sf 5.75% Impervious Runoff Depth>2.84" Flow Length=380' Tc=60.3 min CN=75 Runoff=18.12 cfs 2.998 af

Subcatchment 300: Runoff Area=71,335 sf 2.24% Impervious Runoff Depth>2.52" Flow Length=270' Slope=0.1000'/' Tc=28.9 min CN=71 Runoff=3.00 cfs 0.343 af

Subcatchment 400: Offsite

Runoff Area=42.600 ac 2.35% Impervious Runoff Depth>2.62"

Flow Length=1,570' Tc=92.8 min CN=73 Runoff=43.31 cfs 9.317 af

Subcatchment 500: Offsite

Runoff Area=20.180 ac 8.42% Impervious Runoff Depth>2.76"

Flow Length=1,370' Tc=52.5 min CN=74 Runoff=30.23 cfs 4.640 af

Subcatchment FB:Runoff Area=69,332 sf 25.41% Impervious Runoff Depth>3.30"
Flow Length=250' Tc=72.0 min CN=80 Runoff=2.36 cfs 0.438 af

Subcatchment GW:Runoff Area=100,679 sf 22.37% Impervious Runoff Depth>3.25"
Flow Length=480' Tc=34.0 min CN=79 Runoff=5.05 cfs 0.625 af

Subcatchment LS:

Runoff Area=44,374 sf 29.45% Impervious Runoff Depth>3.33"
Flow Length=410' Tc=46.3 min CN=80 Runoff=1.96 cfs 0.283 af

Subcatchment RG:

Runoff Area=26,952 sf 28.89% Impervious Runoff Depth>3.46"
Flow Length=470' Tc=17.9 min CN=81 Runoff=1.88 cfs 0.178 af

Reach R2: Perimeter DitchAvg. Depth=1.45' Max Vel=8.60 fps Inflow=68.12 cfs 13.923 af n=0.040 L=290.0' S=0.0552 '/' Capacity=1,055.19 cfs Outflow=68.11 cfs 13.912 af

Reach R3: Perimeter DitchAvg. Depth=1.53' Max Vel=4.30 fps Inflow=30.23 cfs 4.640 af n=0.040 L=1,250.0' S=0.0144 '/' Capacity=195.24 cfs Outflow=29.86 cfs 4.607 af

Reach R4: Downstream of BufferAvg. Depth=0.16' Max Vel=1.04 fps Inflow=1.96 cfs 0.283 af n=0.080 L=270.0' S=0.0407'/ Capacity=13.95 cfs Outflow=1.94 cfs 0.281 af

Reach R5: Avg. Depth=0.21' Max Vel=1.32 fps Inflow=1.88 cfs 0.160 af n=0.080 L=78.0' S=0.0538 '/' Capacity=9.53 cfs Outflow=1.86 cfs 0.160 af

Reach R6: Avg. Depth=0.44' Max Vel=4.82 fps Inflow=1.86 cfs 0.160 af 15.0" Round Pipe n=0.012 L=40.0' S=0.0100 '/' Capacity=7.00 cfs Outflow=1.85 cfs 0.160 af

Reach R7: Avg. Depth=0.25' Max Vel=0.99 fps Inflow=1.85 cfs 0.160 af n=0.100 L=360.0' S=0.0400 '/' Capacity=6.57 cfs Outflow=1.73 cfs 0.158 af

Reach SP#1: Study Point #1 - Outlet of Ditch Inflow=71.96 cfs 14.737 af
Outflow=71.96 cfs 14.737 af

25 Post Type III 24-hr Rainfall=5.80" Printed 1/11/2017

Page 4

1636 Post Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Inflow=30.19 cfs 5.302 af Reach SP#2: Study Point #2 - Wetland adjacent to Highland Outflow=30.19 cfs 5.302 af Inflow=30.23 cfs 4.640 af Pond CB: CB Primary=30.23 cfs 4.640 af Peak Elev=202.34' Inflow=11.40 cfs 1.787 af Pond CB1: 24.0" Round Culvert n=0.012 L=144.0' S=0.0308 '/' Outflow=11.40 cfs 1.787 af Peak Elev=233.02' Inflow=0.31 cfs 0.020 af Pond CB10: 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.31 cfs 0.020 af Pond CB11: Peak Elev=203.31' Inflow=0.33 cfs 0.021 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=0.33 cfs 0.021 af Peak Elev=208.84' Inflow=1.16 cfs 0.083 af Pond CB12: 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=1.16 cfs 0.083 af Pond CB13: Peak Elev=223.83' Inflow=2.06 cfs 0.175 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=2.06 cfs 0.175 af Peak Elev=215.44' Inflow=6.01 cfs 0.883 af Pond CB14: 15.0" Round Culvert n=0.012 L=128.0' S=0.0050 '/' Outflow=6.01 cfs 0.883 af Peak Elev=215.59' Inflow=5.91 cfs 0.829 af Pond CB15: 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=5.91 cfs 0.829 af Peak Elev=214.33' Inflow=3.21 cfs 0.659 af Pond CB16: 18.0" Round Culvert n=0.012 L=50.0' S=0.0272 '/' Outflow=3.21 cfs 0.659 af Pond CB2: Peak Elev=204.73' Inflow=10.45 cfs 1.612 af 18.0" Round Culvert n=0.012 L=124.0' S=0.0050 '/' Outflow=10.45 cfs 1.612 af

Pond CB3:

Peak Elev=209.51' Inflow=9.40 cfs 1.470 af
18.0" Round Culvert n=0.012 L=122.0' S=0.0430 '/' Outflow=9.40 cfs 1.470 af

Pond CB4: Peak Elev=215.71' Inflow=7.76 cfs 1.237 af 15.0" Round Culvert n=0.012 L=112.0' S=0.0381 '/' Outflow=7.76 cfs 1.237 af

Pond CB5: Peak Elev=215.90' Inflow=7.74 cfs 1.228 af 15.0" Round Culvert n=0.012 L=32.0' S=0.0063 '/' Outflow=7.74 cfs 1.228 af

Pond CB6: Peak Elev=216.72' Inflow=2.83 cfs 0.321 af 15.0" Round Culvert n=0.012 L=16.0' S=0.0125 '/' Outflow=2.83 cfs 0.321 af

Pond CB7: Peak Elev=223.73' Inflow=2.50 cfs 0.245 af

15.0" Round Culvert n=0.012 L=126.0' S=0.0563 '/' Outflow=2.50 cfs 0.245 af

Pond CB8: Peak Elev=229.67' Inflow=0.68 cfs 0.046 af 15.0" Round Culvert n=0.012 L=126.0' S=0.0510 '/' Outflow=0.68 cfs 0.046 af

25 Post Type III 24-hr Rainfall=5.80" Printed 1/11/2017

1636 PostPrepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Pond CB9: Peak Elev=232.90' Inflow=0.49 cfs 0.032 af 15.0" Round Culvert n=0.012 L=84.0' S=0.0393 '/' Outflow=0.49 cfs 0.032 af

Pond FB1: Filter Basin #1 Peak Elev=207.24' Storage=8,604 cf Inflow=3.21 cfs 0.659 af

Outflow=3.08 cfs 0.488 af

Page 5

Pond GW1: Gravel Wetland #1 Peak Elev=196.36' Storage=45,414 cf Inflow=16.38 cfs 2.412 af

Outflow=9.49 cfs 1.865 af

Pond RG1: Rain Garden #1 Peak Elev=208.09' Storage=863 cf Inflow=1.88 cfs 0.178 af

Outflow=1.88 cfs 0.160 af

Total Runoff Area = 89.863 ac Runoff Volume = 20.830 af Average Runoff Depth = 2.78" 92.21% Pervious = 82.864 ac 7.79% Impervious = 6.999 ac

1636 Post

Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Summary for Pond FB1: Filter Basin #1

Inflow Area = 2.282 ac, 31.56% Impervious, Inflow Depth > 3.47" 3.21 cfs @ 12.63 hrs, Volume= Inflow 0.659 af

3.08 cfs @ 12.87 hrs, Volume= Outflow 0.488 af, Atten= 4%, Lag= 14.3 min

Primary 3.08 cfs @ 12.87 hrs, Volume= 0.488 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 207.24' @ 12.87 hrs Surf.Area= 5,685 sf Storage= 8,604 cf

Plug-Flow detention time= 105.8 min calculated for 0.488 af (74% of inflow)

Center-of-Mass det. time= 48.0 min (866.6 - 818.6)

Volume	Inv	ert Avail.Sto	rage Storage	Description	
#1	205.	50' 16,4	40 cf Custom	Stage Data (Pi	rismatic)Listed below (Recalc)
Elevatio	_	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	
205.5	50	4,200	0	0	
206.0	00	4,627	2,207	2,207	
207.0	00	5,480	5,054	7,260	
208.0	00	6,333	5,907	13,167	
208.5	50	6,760	3,273	16,440	
Device	Routing	Invert	Outlet Devices	i	
#1	Primary	207.00'	10.0' long x 1	3.0' breadth B	road-Crested Rectangular Weir
			Head (feet) 0.	20 0.40 0.60	0.80 1.00 1.20 1.40 1.60
			Coef. (English)	2.60 2.64 2.	70 2.66 2.65 2.66 2.65 2.63

Primary OutFlow Max=3.07 cfs @ 12.87 hrs HW=207.24' (Free Discharge) 1=Broad-Crested Rectangular Weir (Weir Controls 3.07 cfs @ 1.28 fps)

Summary for Pond GW1: Gravel Wetland #1

[79] Warning: Submerged Pond CB1 Primary device # 1 OUTLET by 0.61'

Inflow Area = 8.866 ac, 26.34% Impervious, Inflow Depth > 3.26" Inflow 16.38 cfs @ 12.43 hrs, Volume= 2.412 af

10.62 cfs @ 12.82 hrs, Volume= 1.404 af, Atten= 35%, Lag= 23.5 min Outflow =

10.62 cfs @ 12.82 hrs, Volume= 1.404 af Primary

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 196.62' @ 12.82 hrs Surf.Area= 16,835 sf Storage= 49,710 cf

Plug-Flow detention time= 151.9 min calculated for 1.404 af (58% of inflow)

Center-of-Mass det. time= 75.1 min (876.0 - 801.0)

1636 Post Prepared by {enter your company name here} HydroCAD® 9.00 s/n 03654 © 2009 HydroCAD Software Solutions LLC

Volume	Ir	nvert <i>P</i>	vail.Stor	age	Storage	Description	
#1	193	3.00'	56,31	7 cf	Custom	Stage Data (P	Prismatic)Listed below (Recalc)
Elevatio		Surf.Are			Store	Cum.Store	
(fee		(sq-		(cubic	:-feet)	(cubic-feet)	
193.0	00	10,5	50		0	0	
194.0	00	12,4	50	1	1,500	11,500	
194.5	50	13,40	00		6,463	17,963	
194.5	51	13,20	00		133	18,095	
195.0	00	14,04	16		6,675	24,771	
196.0	00	15,77	73	1	4,910	39,680	
197.0	00	17,50	00	1	6,637	56,317	
Device	Routin	g	Invert	Outle	et Device	S	
#1	Primar	у .	194.50'	18.0	' Round	Culvert X 0.00)
				L= 40	0.0' CPF	o, projecting, no	headwall, Ke= 0.900
							0375 '/' Cc= 0.900 n= 0.012
#2	Primar	γ .	196.20'	15.0'	long x	13.0' breadth E	Broad-Crested Rectangular Weir
		-			_		0.80 1.00 1.20 1.40 1.60
				Coef	. (EngÍlish	n) 2.60 2.64 2	.70 2.66 2.65 2.66 2.65 2.63

Primary OutFlow Max=10.55 cfs @ 12.82 hrs HW=196.61' (Free Discharge)

1=Culvert (Controls 0.00 cfs)

-2=Broad-Crested Rectangular Weir (Weir Controls 10.55 cfs @ 1.70 fps)

MAINTENANCE PLAN OF STORMWATER MANAGEMENT FACILITIES

FOR:

HIGHLAND VIEWS WINDHAM, MAINE

Project Developer: Chase Custom Homes & Finance

290 Bridgton Road Westbrook, ME 04092

Responsible Party: Chase Custom Homes & Finance

290 Bridgton Road Westbrook, ME 04092

Prepared By: Terradyn Consultants, LLC

PO Box 339

New Gloucester, ME 04260

LIST OF STORMWATER MEASURES:

Conveyance & Distribution System (Stormwater Channels & Culverts)
Roadways & Parking Surfaces
Catch Basin Systems
Gravel Wetland
Filter Basins:
Underdrain Soil Filter
Rain Gardens

INTRODUCTION:

Buffers

The owner or operator of the proposed project will be responsible for the maintenance of all stormwater management structures except the rain gardens located on individual lots, the establishment of any contract services required to implement the program, and the keeping of records and maintenance log book. Records of all inspections and maintenance work accomplished must be kept on file and retained for a minimum 5 year time span. The maintenance log book will be made available to the DEP upon request. At a minimum, the appropriate and relevant activities for each of the stormwater management systems will be performed on the prescribed schedule.

INSPECTION & MAINTENANCE TASKS:

Inspections should be performed by qualified erosion control professional. NOTE: The following instruction are excerpts from the Maine Department of Environmental Protection's *Stormwater Management for Maine, Volume III BMPs Technical Design Manual*, dated January 2006.

CONVEYANCE & DISTRIBUTION SYSTEMS: (STORMWATER CHANNELS & CULVERTS, ETC.)

1. Inspection schedule:

- 1.1. Inspect ditches, swales and other open stormwater channels in the spring, in late fall, and after heavy rains to remove any obstructions to flow, remove accumulated sediments and debris, to control vegetated growth that could obstruct flow, and to repair any erosion of the ditch lining. Vegetated ditches must be mowed at least annually or otherwise maintained to control the growth of woody vegetation and maintain flow capacity. Any woody vegetation growing through riprap linings must also be removed. Repair any slumping side slopes as soon as practicable. If the ditch has a riprap lining, replace riprap on areas where any underlying filter fabric or underdrain gravel is showing through the stone or where stones have dislodged. The channel must receive adequate routine maintenance to maintain capacity and prevent or correct any erosion of the channel's bottom or side-slopes.
- **1.2.** Inspect culverts in the spring, in late fall, and after heavy rains to remove any obstructions to flow; remove accumulated sediments and debris at the inlet, at the outlet, and within the conduit; and to repair any erosion damage at the culvert's inlet and outlet.
- **1.3.** Inspect vegetated areas, particularly slopes and embankments, early in the growing season or after heavy rains to identify active or potential erosion problems. Replant bare areas or areas with sparse growth. Where rill erosion is evident, armor the area with an appropriate lining or divert the erosive flows to on-site areas able to withstand the concentrated flows.
- 2. Mowing: Grass should not be trimmed extremely short, as this will reduce the filtering effect of the swale (MPCA, 1989). The cut vegetation should be removed to prevent the decaying organic litter from adding pollutants to the discharge from the swale. The mowed height of the grass should be 2-4 inches taller than the maximum flow depth of the design water quality storm. A minimum mow height of 6 inches is generally recommended (Galli, 1993).
- **3. Erosion:** It is important to install erosion and sediment control measures to stabilize this area as soon as possible and to retain any organic matter in the bottom of the trench.
- **4. Fertilization:** Routine fertilization and/or use of pesticides is strongly discouraged. If complete reseeding is necessary, half the original recommended rate of fertilizer should be applied with a full rate of seed.
- 5. Sediment Removal: The level of sediment deposition in the channel should be monitored regularly, and removed from grassed channels before permanent damage is done to the grassed vegetation, or if infiltration times are longer than 12 hours. Sediment should be removed from riprap channels when it reduces the capacity of the channel.

ROADWAYS & PARKING SURFACES:

1. Paved surfaces shall be swept or vacuumed at least twice annually in the Spring to remove all Winter sand, and periodically during the year on an as-needed basis to minimize transportation of sediment during rainfall events.

CATCH BASIN SYSTEMS:

1. Catch basins are designed with a deep sump to trap larger sediment. Catch basins shall be inspected for sediment depth in the spring and fall, and accumulated sediment shall be removed and disposed of lawfully when it reaches 50% of the design capacity of the sump.

GRAVEL WETLANDS (FROM UNH SUBSURFACE GRAVEL WETLAND DESIGN SPECIFICATIONS MANUAL):

1ST YEAR POST-CONSTRUCTION: Inspection frequency should be after every major storm in the first year following construction.

- **1.** Inspect to be certain system drains within 24-72 hrs (within the design period, but also not so quickly as to minimize stormwater treatment)).
- 2. Watering plants as necessary during the first growing season
- **3.** Re-vegetating poorly established areas as necessary
- 4. Treating diseased vegetation as necessary
- 5. Quarterly inspection of soil and repairing eroded areas, especially on slopes
- **6.** Checking inlets, outlets, and overflow spillway for blockage, structural integrity, and evidence of erosion.

<u>POST-CONSTRUCTION</u>: Inspection frequency should be at least every 6 months thereafter, as per USEPA Good House-Keeping Requirements. Inspection frequency can be reduced to annual following 2 years of monitoring that indicates the rate of sediment accumulation is less than the cleaning criteria listed below. Inspections should focus on:

- 1. Checking the filter surface for dense, complete, root mat establishment across the wetland surface. Thorough revegetation with grasses, forbs, and shrubs is necessary. Unlike bioretention, where mulch is commonly used, complete surface coverage with vegetation is needed.
- **2.** Checking the gravel wetland surface for standing water or other evidence of riser clogging, such as discolored or accumulated sediments.
- **3.** Checking the sedimentation chamber or forebay for sediment accumulation, trash, and debris.
- **4.** Inspect to be certain the sedimentation forebay drains within 24 to 72 hrs.
- **5.** Checking inlets, outlets, and overflow spillway for blockage, structural integrity, and evidence of erosion.
- **6.** Removal of decaying vegetation, litter, and debris.

CLEANING CRITERIA FOR SEDIMENTATION FOREBAY: Sediment should be removed from the sedimentation chamber (forebay) when it accumulates to a depth of more than 12 inches (30 cm) or 10 percent of the pretreatment volume. The sedimentation forebay should be cleaned of vegetation if persistent standing water and wetland vegetation becomes dominant. The cleaning interval is approximately every 4 years. A dry sedimentation forebay is the optimal condition while in practice this condition is rarely achieved. The sedimentation chamber, forebay, and treatment cell outlet devices should be cleaned when drawdown times exceed 60 to 72 hours. Materials can be removed with heavy construction equipment; however, this equipment should not track on the wetland surface. Revegetation of disturbed areas as necessary. Removed sediments should be dewatered (if necessary) and disposed of in an acceptable manner.

CLEANING CRITERIA FOR GRAVEL WETLAND TREATMENT CELLS: Sediment should be removed from the gravel wetland surface when it accumulates to a depth of several inches (>10 cm) across the wetland surface. Materials should be removed with rakes rather than heavy construction equipment to avoid compaction of the gravel wetland surface. Heavy equipment could be used if the system is designed with dimensions that allow equipment to be located outside the gravel wetland, while a backhoe shovel reaches inside the gravel wetland to remove sediment. Removed sediments should be dewatered (if necessary) and disposed of in an acceptable manner.

FILTER BASINS

GRASS UNDERDRAINED SOIL FILTER

- During the first year, the basin will be inspected semi-annually and following major storm events. Debris and sediment buildup shall be removed from the forebay and basin as needed. Any bare area or erosion rills shall be repaired with new filter media or sandy loam then planted and mulched. Maintaining a healthy plant cover will minimize clogging with fine sediments and if ponding exceeds 48 hours, the top of the filter bed must be rototilled to reestablish the soil's filtration capacity.
- 2. Soil Filter Inspection: The soil filter should be inspected after every major storm in the first year to be sure it is functioning properly and that the plants are establishing. Thereafter, the filter should be inspected at least once every six months to ensure that it is draining within 48 hours following a one inch storm or greater. If the system drains too fast, an orifice may need to be added on the underdrain outlet or, if already present, may need to be modified.
- 3. Soil Filter Replacement: The mulch shall be replaced with fresh material on an annual basis.
- **4. Sediment Removal:** Sediment and plant debris should be removed from the pretreatment structure at least annually. Removed sediments should be disposed of in an acceptable manner.
- **5. Fertilization:** Fertilization of the underdrained filter area should be avoided unless absolutely necessary to establish vegetation.
- **6. Harvesting and Weeding:** Harvesting and pruning of excessive growth will need to be done occasionally. Weeding to control unwanted or invasive plants may also be necessary. Plants that are not thriving shall be replaced.
- 7. Snow Storage: Snow should not be pushed from adjacent paved areas directly onto the filter basin. Plowed snow contains a high level of sediment, which can cause premature clogging of the filter media. Snow should be stored in a location that allows it to melt and flow through a pretreatment device, such as a grass swale or filter strip, prior to entering the filter basin.

RAIN GARDEN

- 1. Responsible Party: The owner of each lot where a rain garden is located is responsible for the maintenance of the rain garden, the establishment of any contract services required to implement the program, and the keeping of records and maintenance log book.
- 2. The rain garden should be inspected semi-annually and following major storm events. Debris and sediment buildup should be removed from the forebay and basin as needed. Any bare area or erosion rills should be repaired with new filter media, seeded and mulched.
- **3. Maintenance Agreement:** A legal entity should be established with responsibility for inspecting and maintaining any filter basin. The legal agreement establishing the entity should list specific maintenance responsibilities (including timetables) and provide for the funding to cover long-term inspection and maintenance.
- **4. Drainage:** The rain garden should be draining within 48 hours following a one-inch storm or greater. If the system drains too fast, an orifice may need to be added on the underdrain outlet or may need to be modified if already present.

- **5. Sediment Removal:** Sediment and plant debris should be removed from the pretreatment structure at least annually.
- **6. Remedial Cover:** The organic mulch should be removed and replaced with a 2-3 inch layer of fresh mulch annually or as needed.
- 7. Soil Filter Replacement: The mulch shall be replaced with fresh material on a yearly basis.
- **8. Fertilization:** Fertilization of the filter area should be avoided unless absolutely necessary to establish vegetation.
- **9. Harvesting and Weeding:** Harvesting and pruning of excessive growth should be done occasionally. Weeding to control unwanted or invasive plants may also be necessary.
- **10. Planting:** Maintaining a healthy vegetative cover will minimize clogging with fine sediments. If ponding exceeds 48 hours, the top of the filter bed should be rototilled to reestablish the soil's filtration capacity.
- **11. Soil Filter Replacement:** The top several inches of the filter can be replaced with fresh material if water is ponding for more than 72 hours.

VEGETATED STORMWATER BUFFERS

Buffers should be inspected annually for evidence of erosion or concentrated flows through or around the buffer. All eroded areas should be repaired, seeded and mulched.

- **1. Mowing:** Meadow buffers may be mown no more than twice per year. They may not be maintained as a lawn.
- **2.** Access and Use: Buffers should not be traversed by all-terrain vehicles or other vehicles. Activities within buffers should be conducted so as not to damage vegetation, disturb any organic duff layer, or expose soil.
- **3. Inspections:** Conduct periodic "buffer walks" to inspect the condition of the buffer network.

SAMPLE MAINTENANCE LOG SHEET:

Maintenance Log Sheet								
	BMP's		Date Inspected	Repairs Needed?	Date Repaired			
Example			8/17/2017	Υ	8/27/2017			
1. Conveyance	e & Distribution	n System						
2. Roadways &	& Parking							
3. Catch Basin	Systems							
4. Infiltration	Trench							
5. Gravel Wet	and							
6. Underdrain	Soil Filter							
7. Rain Garder	1							
8. Vegetated S	Stormwater Bu	ffer						
		Detailed R	epair Notes:					
BMP Type	Date	Description of Repa						
3	8/27/2017	Removed sediment from sump						

HOUSEKEEPING PERFORMANCE STANDARDS

FOR: HIGHLAND VIEWS WINDHAM, MAINE

Project Developer: Chase Custom Homes & Finance

290 Bridgton Road Westbrook, ME 04092

Responsible Party: Chase Custom Homes & Finance

290 Bridgton Road Westbrook, ME 04092

Introduction:

The contractor shall be responsible for maintaining proper housekeeping standards throughout the construction phase of the project. After the construction phase has been completed, the owner or operator of the project will be responsible.

Standards:

In accordance with the housekeeping performance standards required by MDEP chapter 500 stormwater regulations, the following standards shall be met:

- 1. **Spill prevention.** Controls must be used to prevent pollutants from being discharged from materials on site, including storage practices to minimize exposure of the materials to stormwater, and appropriate spill prevention, containment, and response planning and implementation.
- 2. Groundwater protection. During construction, liquid petroleum products and other hazardous materials with the potential to contaminate groundwater may not be stored or handled in areas of the site draining to an infiltration area. An "infiltration area" is any area of the site that by design or as a result of soils, topography and other relevant factors accumulates runoff that infiltrates into the soil. Dikes, berms, sumps, and other forms of secondary containment that prevent discharge to groundwater may be used to isolate portions of the site for the purposes of storage and handling of these materials.
- **3. Fugitive sediment and dust.** Actions must be taken to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil may not be used for dust control.

Operations during wet months that experience tracking of mud off the site onto public roads should provide for sweeping of road areas at least once a week and prior to significant storm events. Where chronic mud tracking occurs, a stabilized construction entrance should be provided. Operations during dry months, that experience fugitive dust problems, should wet down the access roads once a week or more frequently as needed.

4. Debris and other materials. Litter, construction debris, and chemicals exposed to stormwater must be prevented from becoming a pollutant source.

To prevent these materials from becoming a source of pollutants, construction and post-construction activities related to a project may be required to comply with applicable

provision of rules related to solid, universal, and hazardous waste, including, but not limited to, the Maine solid waste and hazardous waste management rules; Maine hazardous waste management rules; Maine oil conveyance and storage rules; and Maine pesticide requirements.

- 5. Trench or foundation de-watering. Trench de-watering is the removal of water from trenches, foundations, coffer dams, ponds, and other areas within the construction area that retain water after excavation. In most cases the collected water is heavily silted and hinders correct and safe construction practices. The collected water must be removed from the ponded area, either through gravity or pumping, and must be spread through natural wooded buffers or removed to areas that are specifically designed to collect the maximum amount of sediment possible, like a cofferdam sedimentation basin. Avoid allowing the water to flow over disturbed areas of the site. Equivalent measures may be taken if approved by the department.
- **6. Non-stormwater discharges.** Identify and prevent contamination by non-stormwater discharges.



93 Mill Road • North Yarmouth, Maine 04097 Cell: 207.329.3524 • mark@markcenci.com www.markcenci.com



Soil Investigation for Septic Systems and a Storm Water Control Feature, Windham Line M.H.P & Apartments

Date: September 2, 2016

To: Jeff Amos, PE

Terradyn Consultants, LLC

PO Box 339

New Gloucester, ME 04260

Date of Investigation: August 19, 2016.

Location, Purpose and Method of Investigation:

The property investigated is located at the east side of Roosevelt Trail, Windham, opposite the Land of Nod Road intersection.

The purpose of the investigation was to describe the soil at multiple locations for potential septic systems and one specific location for a storm water control feature.

The Windham Line M.H.P & Apartments Sketch Plan, by Terradyn Consultants, dated 8/17/2016 was used in the field to locate the areas for the test pits. The pits were dug by an excavator. The test pit sites were located by a Trimble Geo-XH GPS radio device. Location data was post processed for accuracy and sent as an AutoCAD drawing file.

Results of the Investigation:

The property is on the lower, easterly slope of Jones Hill, north of Milliken Hill (see Figure 1). These are northerly trending ridges of bedrock covered by glacial till. The *Surficial Geology of the Cumberland Center Quadrangle*, Maine depicts the property as a deposit of glacial till (see Figure 2).

The site is mapped as an association of Paxton fine sandy loam, Paxton very stony fine sandy loam, Swanton fine sandy loam, Ridgebury fine sandy loam and Scantic silt loam on the *National Cooperative Soil Survey* (see attached photomaps and descriptions).

These are soils formed in glacial till in close proximity to a glacio-marine or lacustrine basin filled with silts and clays. Soil testing generally agrees with this mapping.


Twelve test pits were investigated. Soil logs are enclosed. The soil textures vary from sand to fine sandy loamy to silt loam. Higher on the landscape, the soils are more coarse textured, and were deposited from sands washing off the glacial till on the ridges. Lower on the landscape, the sands of the washed tills are finer textured and mix with underlying silts and clays.

The soils are classified as 5B, 3C, and 8D. Wastewater disposal systems will be rated Medium, Medium-Large or Large according to the *Subsurface Wastewater Disposal Rules*, depending on the position on the landscape.


The site of the storm water control feature, at Test Pit #13, is classified as Hydrologic Group D

Mark Cenci


LSE # 262, CG # 467



Topographic Locus Map of the Area of the Chase Property, Roosevelt Trail, Windham



Where Pt = Glacial till





Web Soil Survey National Cooperative Soil Survey

MAP LEGEND

Special Line Features Streams and Canals Interstate Highways Aerial Photography Very Stony Spot Major Roads Local Roads Stony Spot US Routes Spoil Area Wet Spot Other Rails Water Features Transportation Background Œ 8 O ŧ Soil Map Unit Polygons Severely Eroded Spot Area of Interest (AOI) Miscellaneous Water Soil Map Unit Points Soil Map Unit Lines Closed Depression Marsh or swamp Perennial Water Mine or Quarry Special Point Features Rock Outcrop Gravelly Spot Sandy Spot Saline Spot **Borrow Pit** Lava Flow Gravel Pit Clay Spot Area of Interest (AOI) Sinkhole Blowout Landfill 9 Soils

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL: http://websoilsurvey.nrcs.usda.gov Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Cumberland County and Part of Oxford County, Maine

Survey Area Data: Version 11, Sep 17, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 20, 2010—Jul 18, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Slide or Slip

Sodic Spot

Map Unit Legend

	Cumberland County and Part of Ox	ford County, Maine (ME005)	
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
BgB	Belgrade very fine sandy loam, 0 to 8 percent slopes	1.2	1.1%
Cu	Cut and fill land	5.0	4.8%
PbB	Paxton fine sandy loam, 3 to 8 percent slopes	14.6	13.9%
PfB	Paxton very stony fine sandy loam, 3 to 8 percent slopes	33.3	31.7%
PfC	Paxton very stony fine sandy loam, 8 to 15 percent slopes	1.2	1.1%
RbA	Ridgebury fine sandy loam, 0 to 3 percent slopes	4.1	3.9%
RgA	Ridgebury very stony fine sandy loam, 0 to 3 percent slopes	0.9	0.9%
Sn	Scantic silt loam, 0 to 3 percent slopes	2.7	2.6%
Sp	Sebago mucky peat	16.3	15.5%
Sz	Swanton fine sandy loam	4.3	4.0%
W	Water	12.7	12.1%
WrB	Woodbridge fine sandy loam, 0 to 8 percent slopes	3.7	3.6%
WsB	Woodbridge very stony fine sandy loam, 0 to 8 percent slopes	5.2	4.9%
Totals for Area of Interest		105.3	100.0%


xplora		ARTMEN		HASECUS				UDHAM	
		zon thickness		oring Probe	Explora		TP.Z		and the second second
			Ground surface ration or to refus			_ " Organic horiz		Ground surface	
•	Texture	Consistency	Color	Redox Features			Depth of explor	T .	Later and the
0 -		Consistency	DARK	Redox reatures	0 -	Texture	Consistency	Color	Redox Feature
	FINE	FRIABLE	BROWN			FINE	FRIABLE	BROWN	
10-	SANDY	TO	PED		8 10-	SANN			
10-	Loby	LOOSE	BROWN		Depth below mineral soil surface (inches)			RED	
20-	10				90	LOAM			
20-	COAM	-			-02 rfa			BROWN	
	SAUD				ns II		LOOSE		
30 - 40 - 50 -	GRAVELLY		LIGHT		S 30-		240,2		
	STUNE	FIRM	BROWN	NONE	nera				
40-		-1.9.	12000	10010	i i	FINE		HANT	NONE
70	SAND				M 40-	SAND		BROWN	
					h be				
. 50-	1111	TOF	EXCAVA	FIDA	Jd 50-				
					-			CV-14-14	FIRE
60-					60-	LIMI	TOF	EXCAVA	1.04
S.E.	Soil Classific	cation Slop		Li Groundwater	S.E.	Soll Classific	cation Siop	e Limiting Factor	☐ Groundwater
S.S.	Profile C	Condition Perce	ent Depth	Restrictive Layer Bedrock	Details t	Profile C	Condition Perce	ent Depth	Restrictive Layer Bedrock
S.S.	Soil Series/Phase I	Name:	☐ Hydric	Hydrologic	S.S.	Soil Series/Phase		☐ Hydric	Hydrologic
*			☐ Non-hy	dric Soil Group	Soil			□ Non-hy	dric Soil Group
xplora	" Organic horiz	on thickness	CTest Pit ☐ Bo	elev.	Explora	" Organic horiz		Ground surface	elev
xplorat	" Organic horiz" Texture	on thickness		elev.	Explora 0 -	" Organic horiz		Ground surface ation or to refuse Color	elev
0	" Organic horiz Texture	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color	elev	0 -	Texture	on thickness Depth of explore	Ground surface ation or to refuse	elev
0	Texture	on thickness Depth of explora	Ground surface ation or to refuse Color DARK BROWN	elev	0 -	Texture	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color	elev
0	" Organic horiz Texture	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	elev	0 -	Texture	Depth of explore Consistency	Ground surface ation or to refuse Color	elev
0	Texture	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	elev	0 -	Texture FINE SAND	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK DROWN	eleval Redox Feature
0	Texture FINE SAND	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	elev	0 -	Texture	Depth of explore Consistency	Ground surface ation or to refuse Color	eleval Redox Feature
0 -	Texture	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	elev	oil surface (inches)	Texture FINE SAND	Depth of explore Consistency	Ground surface ation or to refuse Color DARK DROWN	eleval Redox Feature
0 -	Texture FINE FINE	on thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN!	eleval Redox Features	oil surface (inches)	Texture FINE SAND	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
0 -	Texture FINE SAND	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWNI	eleval Redox Features	oil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK DROWN	eleval Redox Feature
0 -	Texture FINE FINE	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN!	eleval Redox Features	oil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
0 -	Texture FINE FINE	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN!	eleval Redox Features	oil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
0 -	Texture FINE FINE	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN SROWN	eleval Redox Features	oil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
0 — 10— 20— 30—	Texture FINE FINE	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN SROWN	eleval Redox Features	mineral soil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
20 30 40 50	Texture FINE FINE	con thickness Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN SROWN	eleval Redox Features	Depth below mineral soil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency	Ground surface ation or to refuse Color DARK BROWN	eleval Redox Feature
0 -	"Organic horiz Texture FINE SAND FINE SAND SOII Classific	con thickness Depth of explore Consistency FRINGS atten Slope	Ground surface ation or to refuse Color DARK BROWN SROWN SRO	eleval Redox Features	Depth below mineral soil surface (inches)	"Organic horiz Texture FINE SAND LOM SILT LOM	Depth of explore Consistency FIASE 1 T OF	Ground surface ation or to refuse Color DARK BROWN ARA (BROWN)	eleval Redox Feature
0 - 10 - 20 - 30 - 40 - 60 - 60 - 60 - 60 - 60 - 60 - 6	Texture FINE SAND FINE SAND SOII Classific 5	Consistency Consistency Consistency Consistency Consistency Consistency Consistency Consistency Consistency	Ground surface ation or to refuse Color DARK BROWN SROWN SRO	eleval Redox Features	Depth below mineral soil surface (inches)	"Organic horiz Texture FINE SANDY LOMM LIM Soli Classific 8	Depth of explore Consistency FRASE FIRM asten Slope	Ground surface ation or to refuse Color DARK BROWN EXCAPT Limiting Factor 12 "	eleval Redox Feature COMMON Tron Groundwster Restrictive Layer
0 - 10 - 20 - 30 - 40 - 50 - 60 - S.E.	Texture FINE SAND FINE SAND SOII Classific 5	Consistency Consi	Ground surface ation or to refuse Color DARK BROWN SROWN SRO	eleval Redox Features Redox Features	Depth below mineral soil surface (inches)	"Organic horiz Texture FINE SANDY LOMM LIM Soli Classific 8	Depth of explore Consistency FRIABLE TO SIOPE Condition Perce	Ground surface ation or to refuse Color Color DARK BROWN EXCAPT CXCAPT CXCA	eleval Redox Feature Collinox Trory Staroundwster
0 - 10 - 20 - 30 - 40 - 50 - 50 - 50 - 50 - 50 - 50 - 5	Texture FINE SAND Soli Classific Profile C	Consistency Consi	Ground surface ation or to refuse Color DARK BROWN SROWN SRO	eleval Redox Features Redox Features Groundwater Restrictive Layer Bedrock Hydrologic	by Depth below mineral soil surface (inches)	"Organic horiz Texture FINE SAND LOM CITY SILT LOM SILT LOM Bell Classific Profile O Profile	Depth of explore Consistency FRIABLE TO SIOPE Condition Perce	Ground surface ation or to refuse Color DARK BROWN EXCAPT Limiting Factor 12 "	Redox Feature Continue C
0 - 10 - 20 - 30 - 40 - 50 - 50 - 50 - 50 - 50 - 50 - 5	Texture FINE SAND Soli Classific Profile C	Consistency Consi	Ground surface ation or to refuse Color DARK BROWN SPOUN SPO	eleval Redox Features Page	Soil Details by Depth below mineral soil surface (inches)	Scil Classific Profile C Soil Series/Phase P	Depth of explore Consistency FRIABLE TO SIOPE Condition Perce	Ground surface ation or to refuse Color DARK BROWN A RANGE BROWN A Limiting Factor 12 " Depth Hydric	eleval Redox Feature COMMON COM
0 - 10 - 20 - 30 - 40 - 50 - 50 - 50 - 50 - 50 - 50 - 5	Texture FINE SAND SOII Classific Profile Soil Series/Phase N	Consistency Consi	Ground surface ation or to refuse Color DARK BROWN SPOUN SPO	eleval Redox Features Redox Features Groundwater Restrictive Layer Bedrock Hydrologic	Soil Details by Depth below mineral soil surface (inches)	Scil Classific Profile C Soil Series/Phase P	Depth of explore Consistency FRIABLE TO SIOPE Condition Perce	Ground surface ation or to refuse Color DARK BROWN A RANGE BROWN A Limiting Factor 12 " Depth Hydric	Redox Feature Continue C

		DHAM L		N INFORMA			Project Locati	DITIONS AT PR on (municipality)	OJECT SITES
					MOTO	HOMES	h/1	NDHAM	
Explora		TPS 8		The second secon	Explora			▼Test Pit □ E	Boring Probe
_	_ " Organic horiz		Ground surface		-	_ " Organic horiz		Ground surface	
		Depth of explora	1	1			Depth of expl	oration or to refu	sal
0 -	Texture	Consistency	Color	Redox Features	0 -	Texture	Consistency		Redox Features
			BROWN					DARK	
\$ 10-	FINE	FRUBLE			20			BROWN	
Depth below mineral soil surface (inches) 0 0 0 0 1 1 1 1 1	SANDI		YELLAN		surface (inches)	FINE	FRIABLE	YEUR	
(inc	LOAM		BROWN		(in	SANDY		- Cuu	
8 20-	compl	V.D.	GRAJ	COMMON	e 20-	late	-	BROWN	
urfa		FIRM		Commen	Surf				
oil s			BROWN		Oil Si				
S 30-					Depth below mineral soil		FIRM	GRAY.	Course
ner	6	art of	EXCAVI	TION	iner		- `	BROWN	
E 40-					E 40-				
slow					NO P	610	1TO	EXCA	LATION
h be					P P				
td 50-					d 50-				
					2				
60-					60-				
S.E.	Soil Classific	ation Slop	a Limiting Factor	E Groundwater		Soll Classifi	cation S	ope Limiting Fact	Or A Groundwater
	Profile C	Condition Perce	17 "	Restrictive Layer Bedrock	Soil Details by	_ 2 _	<u>C</u>		Restrictive Layer
Soil Details	Soil Series/Phase			Hydrologic	Deta S.S.	Profile Soll Series/Phase		rcent Depth	Bedrock Hydrologic
Soil >>			☐ Hydric ☐ Non-hyd	inc	Soil I			☐ Hydrid	C
				Soil Group	00 11			□ Non-h	Soil Group
hes)	Texture FINE SAND	Depth of explora Consistency	Ground surface ation or to refuse Color		ches)	Texture FINE SANDI		Ground surface oration or to refuse Color	Redox Features
soil surface (inches)	LOAM	FIRM	atra	Common	soil surface (inches)	SILT	FIRM	apay	COMMON
Itac			BROWN		20-	LOAM		BROWN	
St	LIMI	TOF	EXCAUAT	2001	S III		INIT	OF EX	CA UAT YOU
00 00					300				
ner					ner				
Depth below mineral					Depth below mineral				
Mo					NOS 49				
ag c			-		h be				
g 50					d 50-				
0					0				
60					-				
	Soil Classific	ation Slope		Groundwater	60− ≥ S.E.	Soll Classific	cation SI	ope Limiting Factor	Groundwster
\$ ▶	8	<u> </u>	12 "	Restrictive Layer Bedrock	\$ ≥		0	12.	Restrictive Layer
S.S.	Profile C Soil Series/Phase N	ondition Percer		Hydrologic	Deta	Profile C	Condition Per	cent Depth	☐ Bedrock
Soil Details by			☐ Hydric ☐ Non-hyd	ric	Soil Details by			☐ Hydric	
-				Soil Group	00 11			□ Non-h	ydric Soil Group
-		INVESTIC	SATOR INFOR	RMATION AND	SIGNATI	JRE	1 1 1 1	302	
Signatur	е	Mar		2mi			1-16		
Name Pr	rinted MA	RK CE,				Cert/Lic/Reg. #	1467		
Title)	Licensed Site	Evaluator	Certified Soil S	cientist Ce	rtified Geol		fessional Engi	neer affix p	rofessional seal


				N INFORMA	TION	SUBS	URFACE CON	DESCRIPTION O	
MH	P WAS	ARTMEN.	TS APPIL	LASE CUS	TOM	HOMES		on (municipality):	
xplora	ation Symbol #	TP9	Test Pit Be	oring Probe	Explora	ation Symbol #	TPIO	Z Test Pit □ Bo	oring Probe
	" Organic horiz	zon thickness	Ground surface	e elev.		_ " Organic horiz		Ground surface	The second second
		Depth of explore	ation or to refus	al				oration or to refusa	
0 -	Texture	Consistency	Color	Redox Features	0 _	Texture	Consistency	1	Redox Feature
	FINE	Commission of the Commission o	DAR.		0 -	FINE	Control	DARK	TYGGOX F GALUIE
	SAND	FRABLE	BROWN		1			BRAWL	
10-	LOAM		JELLAN		\$ 10-	SANDY	FRIABLE.	27000	
	Long		BROWN		che	Later		YEUW	
		EPM	GRAJ	COMMON	(i)			BROWN	
20 - 30 - 40 -	SILL	177	BROWN		OR 20-	WERN	1 - 1	GRAJ	COMMON
	LOAM		30.54		sur	FINE	FIPM	Braw	
22						Long		Dame	
30-		UIT OF	EXCAU	ATION	s 30-	LIM	TOF	EXCAVAT	1001
					ner	Lim	1101	2/4/01	
40-					≥ 40-	*****			
10					NO 49				
					4 P				
50-					Depth below mineral soil surface (inches)				
60-	Soll Classifi	cation Slope	e Limiting Factor	Groundwater	60-	Soil Classifi	cetion Si	ope Limiting Factor	
S.E.	8	D	14		S.E.	3	C	18 "	Groundwater Restrictive Layer
	0 11 0 1 101	Condition Perce	nt Depth	☐ Bedrock	Details %	Profile	Condition Per	cent Depth	☐ Bedrock
S.S.	Soil Series/Phase	Name:	☐ Hydric	Hydrologic	º S.S.	Soil Series/Phase	Name:	☐ Hydric	Hydrologic
*			☐ Non-hy	dric Soil Group	Soil Soil			☐ Non-hy	dric Soil Group
0 -	Texture Time	Depth of explora Consistency	Color	Redox Features	0 -	Texture	Depth of explo	Color	Redox Features
	SANDY	FRIABLE	Beauty			FINE	(0,100.6	BROWN	
10-	LOSM		BROWN		S 10-	SAND	FRABIE.	NELLO Y	
					nch			BROWN	
00	VERY-	C.D.1	a RAY	COMMON	surface (inches)	LOW		SHOWN	
20-	S AAND	FIPM	BROWN		DE 20-				
	Lion				son		FIRM	aRay	COMMON
30-	-	MITER	EXCAMA	TIM	lios 30-			BROWN	
				01.00	ara s	1 11	III OF	EXCAM	TIDA
					nine		0.	- ACM	
40-					\$ 40-				
					olec				
	***************************************				\$				
50-	-				Depth below mineral s				
					-				
60					00				
S.E.	Soil Classific		Limiting Factor	Groundwater	60 → S.E.	Soil Classific	cation Slo	pe Limiting Factor	₫ Groundwater
*		D	14 "	Restrictive Layer	Soil Details by	3_	<u>C</u>	19	Restrictive Layer
s.s.	Profile C Soil Series/Phase N	Condition Percer Name:		☐ Bedrock Hydrologic	etal	Profile C	Condition Per	cent Depth	☐ Bedrock
S.S.		100	☐ Hydric		Q S.S.	Jon Jenea/Friase i	TOUTO.	☐ Hydric	Hydrologic
**			□ Non-hyd	Soil Group	S >>			☐ Non-hyd	Soil Group
30		INVESTIG	SATOR INFO	RMATION AND	SIGNATI	IRE	3000		
natur	re	11.					1.		
me D	rinted	mai		lui		7-	1-16		
	M	ark cei	121		(Cert/Lic/Reg. #	1467		
e y	Licensed Site	Evaluator -	Cortified Sall C	Calculiat Mr.	416-45		-161		
,	iveriago alte	LValuator U	Certified Soil S	Cientist	tified Geol	logist \square Pro	fessional Engir	neer affix pro	ofessional seal

	Name: WIN				oring Probe					MA	_	
piora					e elev	Explora	ation Symbol #					
				on or to refus			" Organic hor	zon tnickn	ess (Fround su	rface e	lev
	1	1			1			" Depth of	1	tion or to		
0 -	Texture	Consist	tency	Color	Redox Features	0 -	Texture	Consis	tency	Color		Redox Featu
	SAND	CLIAR	5	-								
	LOAM	FEITE	100	BROWN			manus permananta					
10-	40111	-		VELLOR		8 10-						
	VERY	FIP	M	CRAY	COMMON	ıch						
	FINE,		1.			(i)						
20-	SAND			BROWN		S 20-						THE PARTY OF THE P
	ram.) ji						
		_				<u>=====================================</u>						
30-	612	17	OF E	XXAUAT	700	o 30-		-	-			
		-				era						
	Table of Marine II and the Control of the Control o					nir.						
40-			-			≥ 40-						
						pel						***************************************
50-						Depth below mineral soil surface (inches)						
					-	de 50-				name of the latest		
60-						60-						
S.E.	Soil Classific	ation	Slope	Limiting Factor	Groundwater		Soll Classif	fication	Slope	Limiting	Factor	Groundwater
*	Profile C	P		10"	Restrictive Layer Bedrock	is b					0. [Restrictive Lay
,,		Condition	Percent	Depth		eta	Profile Soil Series/Phase	Condition	Percent	Dep	oth	Bedrock
		Name:			Hydrologic							Hydrologi
s.s.		Name:		☐ Hydric		S.S.	Sul Selles/Filese	itaing.				
s.s.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Soil	tion Symbol #		ess C	Test Pit Fround su	□ Bori	Soil Grou
s.s.	Soil Series/Phase I	on thickne	ess Grexploration	est Pit Bo	oring Probe		tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
s.s.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
s.s.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora 0 -	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S.	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	mineral soil surface (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thickno	ess Grexploration	est Pit Bo	oring Probe	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	tion Symbol # _ " Organic horiz " Texture	on thicknopeth of Consist	ess G exploration tency	est Pit Boround surface on or to refuse Color	oring Probe e eleval Redox Features	Explora (inches)	tion Symbol #	zon thickn	ess C	Test Pit Fround su	□ Bori	Soil Grou
S.S	Soil Series/Phase in tion Symbol # _ " Organic horiz	on thicknopeth of Consist	ess Grexploration	est Pit Boround surface on or to refuse Color	oring Probe e elev al Redox Features	Depth below mineral soil surface (inches) 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	tion Symbol #	zon thickn " Depth of Consis	ess C	Test Pit Fround su	Non-hydri □ Bori rface e refusal · F	ing Property
S.S.S. Polaria (10 - 10 - 10 - 10 - 10 - 10 - 10 - 10	soil Series/Phase in the series of the serie	con thicknown the consist of the con	ess Gi exploration de la company de la compa	est Pit Boround surface on or to refuse Color	vidric Soil Group pring Probe e elev. al Redox Features	Depth below mineral soil surface (inches) 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	tion Symbol # " Organic hori Texture Soll Classif	zon thickn " Depth of Consis	ess C explorat tency	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F	Ing Property
S.S.S. polora 0	soil Series/Phase in the series of the serie	Depth of Consist Consist	ess G exploration tency	est Pit Boround surface on or to refuse Color Limiting Factor Depth	oring Probe elev. al Redox Features	Depth below mineral soil surface (inches) 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	tion Symbol # " Organic hori Texture Soll Classif	zon thickn " Depth of Consis " Consis " Consis " Condition	ess C explorat tency	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F	Ing Property
S.S.S. Photograph of the state	Soil Series/Phase in the state of the state	Depth of Consist Consist	ess Gi exploration de la company de la compa	est Pit	oring Probe e elev. al Redox Features Groundwater Restrictive Layer Bedrock Hydrologic	Depth below mineral soil surface (inches) 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	tion Symbol # " Organic hori Texture Soli Classif	zon thickn " Depth of Consis " Consis " Consis " Condition	ess C explorat tency	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F th th	Groundwater Restrictive Ley Bedrock Hydrologi
S.S.S. polora 0	Soil Series/Phase in the state of the state	Depth of Consist Consist	ess Gi exploration de la company de la compa	est Pit Boround surface on or to refuse Color Limiting Factor Depth	oring Probe elev al Redox Features Groundwater Restrictive Layer Bedrock Hydrologic	etails by Depth below mineral soil surface (inches)	tion Symbol # " Organic hori Texture Soli Classif	zon thickn " Depth of Consis " Consis " Consis " Condition	ess C explorat tency	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F	Groundwater Restrictive Lay Bedrock Hydrologi
S.S.S. Polora 0 - 10 - 20 - 30 - 40 - 50 - 50 - 50 - 50 - 50 - 50 - 5	Soil Series/Phase in the street of the stree	Depth of Consist Consi	ess Gi exploration de la company de la compa	Est Pit	oring Probe e elev. al Redox Features Groundwater Restrictive Layer Bedrock Hydrologic	Soil Details by Depth below mineral soil surface (inches) Soil Details by Depth below mineral soil surface (inches) Soil Details by Depth below mineral soil surface (inches)	tion Symbol # " Organic hori Texture Soll Classift Profile Soil Series/Phase	zon thickn " Depth of Consis " Consis " Consis " Condition	ess C explorat tency	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F th th	Redox Featu
S.S.S. polora 0	Soil Series/Phase in the street of the stree	Depth of Consist Consi	ess Gi exploration de la company de la compa	Est Pit	oring Probe e elev al Redox Features Groundwater Restrictive Layer Bedrock Hydrologic dric Soil Group	Soil Details by Depth below mineral soil surface (inches) **Soil Details by Depth below mineral soil surface (inches) **Soil Details by Depth below mineral soil surface (inches)	tion Symbol # " Organic hori Texture Soli Classif Profile Soil Series/Phase	zon thickn " Depth of Consis " Consis " Consis " Condition	ess C explorat tency Siope Percent	Test Pit Ground su ition or to r Color	□ Bori rface e refusal · F th th	Groundwater Restrictive Lay Bedrock Hydrologi





Land Surface Type		Export Coefficient	Pre- treatment	Treatment Factor for	Post- treatment	Lot 5 Impervious Lot 5 Roof	0.043 0.017	1.25 0.5	0.05375 0.0085	0.25 0.25			Hydrologic Soil Group— Summary by Map Uni Map unit symbol Map unit name WATERSHED IMPERVIOUS AREA= 89000 SF Cu Cut and fill land
or Lot #(s) with description	or # of	from Table 3.1	Algal Av. P Export	BMP(s) from	Algal Av. P Description of BMPs Export	Lot 5 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter	WATERSHED LANDSCAPED AREA= 121000 SF HsC Hollis very rocky fine sandy loam, 8 to 20
		Table 3.2	(Ibs P/year)	Chapter 6	(lbs P/year)	Lot 5 Grass	0.103 0.043	0.3	0.0309	0.25	0.007725	Gravel Wetland Gravel Wetland	PROVIDED WQV= 17963 CF
			Subd	ivision		Lot 6 Impervious Lot 6 Roof	0.043	1.25 0.5	0.05375 0.0085	0.25 0.25		-	PbB Paxton fine sandy loam, C 3 to 8 percent slopes
WS-1 Roadway Impervious	0.164	1.25	0.205	0.25	0.05125 Gravel Wetland	Lot 6 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter	Forebay STAGE AREA STORAGE PfB Paxton very stony fine candy loam, 3 to 8
Roadway Pervious	0.093	0.3	0.0279	0.25	0.006975 Gravel Wetland	Lot 6 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland	(FT) (SF) (CF) PfC Paxton very stony fine sandy loam, 8 to 15 C
WS-2			Г			Lot 7 Impervious Lot 7 Roof	0.043	1.25 0.5	0.05375 0.0085	0.25 0.25		Gravel Wetland Gravel Wetland	194 1300 1100 RbA Ridgebury fine sandy C
Roadway Impervious	0.029	1.25	0.03625	0.25	0.0090625 Gravel Wetland	Lot 7 Roof (Rear)	0.017	0.5	0.0085	0.16	0.00136	Gravel Wetland + Roof Filter	loam, 0 to 3 percent slopes
Roadway Pervious Apartment Pervious	0.002	0.3	0.0006 0.0138	0.25	0.00015 Gravel Wetland 0.00345 Gravel Wetland	Lot 7 Grass	0.195	0.3	0.0585	0.25		Gravel Wetland	Cell #1 STAGE AREA STORAGE (FT) (SF) (CF) Ridgebury very stony fine sandy loam, 0 to 3 percent slopes
WS-3	5,5,5					Lot 8 Impervious Lot 8 Roof	0.043	1.25 0.5	0.05375 0.0085	0.25 0.25		Gravel Wetland Gravel Wetland	193 4350 0 Sn Scantic silt loam, 0 to 3 percent slopes
Roadway Impervious	0.026	1.25	0.0325	0.25	0.008125 Gravel Wetland	Lot 8 Roof (Rear)	0.017	0.5	0.0085	0.25	0.002123	Gravel Wetland + Roof Filter	194.5 5500 7388 Sp Sebago mucky peat A Sz Swanton fine sandy loam
Roadway Pervious	0.002	0.3	0.0006	0.25	0.00015 Gravel Wetland	Lot 8 Grass	0.15	0.3	0.045	0.25	0.01125	Gravel Wetland	Cell #2 STAGE AREA STORAGE W Water
Apartment Pervious WS-4	0.034	0.3	0.0102	0.25	0.00255 Gravel Wetland	Lot 9 Impervious	0.043	1.25	0.05375	0.25		Gravel Wetland	193 5300 0 loam, 0 to 8 percent slopes
Roadway Impervious	0.018	1.25	0.0225	0.25	0.005625 Gravel Wetland	Lot 9 Roof Lot 9 Roof (Rear)	0.017	0.5	0.0085 0.0085	0.25	0.002125	Gravel Wetland Gravel Wetland + Roof Filter	
Roadway Pervious	0.001	0.3	0.0003	0.25	0.000075 Gravel Wetland	Lot 9 Grass	0.195	0.3	0.0585	0.25	0.014625	Gravel Wetland	Total Pond STAGE AREA STORAGE
WS-5 Roadway Impervious	0.046	1.25	0.0575	0.25	0.014375 Gravel Wetland	Lot 10 Impervious	0.033	1.25	0.04125	0.25		Gravel Wetland	(FT) (SF) (CF) 193 10550 0
Roadway Pervious	0.02	0.3	0.006	0.25	0.0015 Gravel Wetland	Lot 10 Roof Lot 10 Grass	0.017	0.5	0.0085 0.0186	0.25 0.25		Gravel Wetland Gravel Wetland	194 12450 11500
WS-6			 		T T	Lot 11 Impervious	0.033	1.25	0.04125	0.25		Gravel Wetland	194.5 13400 17963 194.51 13200 17963
Roadway Impervious Roadway Pervious	0.031	1.25 0.3	0.03875 0.0126	0.25 0.25	0.0096875 Gravel Wetland 0.00315 Gravel Wetland	Lot 11 Roof	0.017	0.5	0.0085	0.25		Gravel Wetland	195 14046 24638 196 15773 39547
WS-7	0.042	0.3	0.0120	0.23	U.00313 Glavel VVetland	Lot 11 Grass Lot 20 Grass	0.062 0.07	0.3	0.0186 0.021	0.25 0.25		Gravel Wetland Gravel Wetland	
Roadway Impervious	0.034	1.25	0.0425	0.25	0.010625 Gravel Wetland	Lot 21 Impervious	0.043	1.25	0.021	0.25		Gravel Wetland	WATERSHED IMPERVIOUS AREA= 31374 SF
Roadway Pervious	0.035	0.3	0.0105	0.25	0.002625 Gravel Wetland	Lot 21 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland	WATERSHED LANDSCAPED AREA= 57272 SF REQUIRED WQV= 4524 CF
WS-8 Roadway Impervious	0.019	1.25	0.02375	0.25	0.0059375 Gravel Wetland	Lot 21 Roof (Rear)	0.017	0.5	0.0085	0.16		Gravel Wetland + Roof Filter	PROVIDED WQV= 7260 CF TREATMENT FACTOR= 0.25 (0.25 Max)
WS-9						Lot 21 Grass Lot 22 Impervious	0.195 0.043	0.3 1.25	0.0585 0.05375	0.25 0.25		Gravel Wetland Gravel Wetland	
Roadway Impervious	0.029	1.25	0.03625	0.25	0.0090625 Gravel Wetland	Lot 22 Roof	0.017	0.5	0.0085	0.25	0.002125	Gravel Wetland	STAGE AREA STORAGE (FT) (SF) (CF)
WS-10 Roadway Impervious	0.035	1.25	0.04375	0.25	0.0109375 Gravel Wetland	Lot 22 Roof (Rear)	0.017	0.5	0.0085	0.16		Gravel Wetland + Roof Filter	205.5 4200 0 206 4627 2207
Roadway Pervious	0.017	0.3	0.0051	0.25	0.001275 Gravel Wetland	Lot 22 Grass Lot 23 Impervious	0.195 0.043	0.3 1.25	0.0585 0.05375	0.25 0.25		Gravel Wetland Gravel Wetland	WQV EL= 207 5480 7260 208 6333 13167
WS-11			I I			Lot 23 Roof	0.017	0.5	0.0085	0.25		Gravel Wetland	208.5 6760 16440
Roadway Impervious Roadway Pervious	0.04	1.25 0.3	0.05 0.0051	0.25 0.25	0.0125 Gravel Wetland 0.001275 Gravel Wetland	Lot 23 Roof (Rear)	0.017	0.5	0.0085	0.16		Gravel Wetland + Roof Filter	Rain Garden #1
WS-12	0.017	0.3	0.0031	0.25	U.001273 Glavel Wetland	Lot 23 Grass Lot 24 Impervious	0.195	0.3 1.25	0.0585 0.05375	0.25 0.25		Gravel Wetland Gravel Wetland	WATERSHED IMPERVIOUS AREA= 2875 SF
Roadway Impervious	0.046	1.25	0.0575	0.25	0.014375 Gravel Wetland	Lot 24 Roof	0.017	0.5	0.0085	0.25		Gravel Wetland	WATERSHED LANDSCAPED AREA= 15000 SF REQUIRED WQV= 740 CF
Roadway Pervious	0.018	0.3	0.0054	0.25	0.00135 Gravel Wetland	Lot 24 Roof (Rear)	0.017	0.5	0.0085	0.16		Gravel Wetland + Roof Filter	PROVIDED WQV= 773 CF TREATMENT FACTOR= 0.38 (0.25 Max)
WS-13 Roadway Impervious	0.084	1.25	0.105	0.25	0.02625 Gravel Wetland	Lots to Filter Basin	0.126	0.3	0.0378	0.25	0.00945	Gravel Wetland	
Roadway Pervious	0.056	0.3	0.0168	0.25	0.0042 Gravel Wetland	Lot 16 Impervious	0.043	1.25	0.05375	0.25	0.0134375	Filter Basin	STAGE AREA STORAGE (FT) (SF) (CF)
Apartment Impervious	0.1	1.25	0.125	0.25	0.03125 Gravel Wetland	Lot 16 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin	WQV EL= 206 916 773
Apartment Roof Apartment Pervious	0.017	0.5	0.0085 0.0639	0.25 0.25	0.002125 Gravel Wetland 0.015975 Gravel Wetland	Lot 16 Roof (Rear) Lot 16 Grass	0.017 0.195	0.5	0.0085 0.0585	0.16 0.25		Filter Basin + Roof Filter Filter Basin	Forested Buffer with Level Lip Spreader
WS-14	5,2,0		0.0000	3,23		Lot 17 Impervious	0.193	1.25	0.05375	0.25		Filter Basin	The buffer contains soils that are consistent with Soil Group C sandy loam or loamy sand. <i>Table 6</i> — Sizing Requirements for a buffer with 0-8% slope and stone bermed level lip spreader of Chapter
Roadway Impervious	0.103	1.25	0.12875	0.25	0.0321875 Gravel Wetland	Lot 17 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin	500 shows that standard sizing requires that the berm length for a forested buffer must be 75' per acre of impervious area and 25' per acre of lawn. Evaluation of the watershed shows that it contains the following:
Roadway Pervious WS-15	0.042	0.3	0.0126	0.25	0.00315 Gravel Wetland	Lot 17 Roof (Rear) Lot 17 Grass	0.017	0.5	0.0085	0.16 0.25		Filter Basin + Roof Filter Filter Basin	Impervious area = 13,068 SF (0.30 Ac) Lawn area = 5,000 SF (0.11 Ac)
Roadway Impervious	0.085	1.25	0.10625	0.25	0.0265625 Gravel Wetland	Lot 18 Impervious	0.043	1.25	0.05375	0.25		Filter Basin	Standard sizing: 75(0.30) + 0.11(25)=22.5'+2.9'=25.4'. 25.4' would yield a treatment factor of 0.4.
Roadway Pervious	0.012	0.3	0.0036	0.25	0.0009 Gravel Wetland	Lot 18 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin	Oversized to TF of 0.2: BMP _{TF} =0.4(BMP _{TF} / TF) = 0.4(25.4/0.2)=50'
WS-15A Roadway Impervious	0	1.25	0	0.25	0 Gravel Wetland	Lot 18 Roof (Rear) Lot 18 Grass	0.017 0.195	0.5	0.0085 0.0585	0.16 0.25	0.00136 0.014625	Filter Basin + Roof Filter Filter Basin	Forested Buffer Adjacent to Residential Lot
Roadway Pervious	0	0.3	0	0.25	0 Gravel Wetland	Lot 19 Impervious	0.193	1.25	0.05375	0.25		Filter Basin	The buffer contains soils that are consistent with Soil Group C sandy loam or loamy sand. <i>Table 9</i> - Buffer Size Requirements Based on Soil & Vegetative Cover Types of Chapter 500 shows that standard sizing requires that the standard length of flow path for a forested buffer to be 75'. We
WS-16			Г		T T	Lot 19 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin	are proposing a buffer with a 100' long flow path which yields a treatment factor of 0.2:
Roadway Impervious Roadway Pervious	0.203	1.25 0.5	0.25375 0.054	0.25 0.25	0.0634375 Filter Basin 0.0135 Filter Basin	Lot 19 Roof (Rear)	0.017	0.5	0.0085	0.16		Filter Basin + Roof Filter	Oversized to 110' flow path: TF = 0.4 (BMP _{st} /BMP _{TF})= 0.4(75/110)=0.27
WS-FB	0.108	0.5	0.054	0.25	0.0133 Filter Basili	Lot 19 Grass Lot 20 Impervious	0.195 0.043	0.3 1.25	0.0585 0.05375	0.25 0.25		Filter Basin Filter Basin	Treatment Factors for Multiple BMPS TF=(most efficient BMP) x (least efficient BMP) ^{1/2}
Roadway Impervious	0	1.25	0	0.25	0 Gravel Wetland	Lot 20 Roof	0.017	0.5	0.0085	0.25	0.002125	Filter Basin	Roof drain filter strip with gravel wetland or filter basin: $0.25 \times (0.4^{1/2}) = 0.158 = 0.16$
Roadway Pervious	0	0.3	0	0.25	0 Gravel Wetland	Lot 20 Roof (Rear)	0.017	0.5	0.0085	0.16		Filter Basin + Roof Filter	Roof drain filter strip with 110' long buffer: $0.27 \times (0.4^{1/2}) = 0.171 = 0.17$
WS-GW Roadway Impervious	0	1.25	0	0.25	0 Gravel Wetland	Lot 20 Grass Lots to Other BMPs	0.125	0.3	0.0375	0.25	0.009375	Filter Basin	
Roadway Pervious	0	0.3	0	0.25	0 Gravel Wetland	Lot 10 Impervious	0.01	1.25	0.0125	0.4	0.005	Rain Garden	
WO 1 0			Γ		<u> </u>	Lot 10 Roof (Rear)	0.017	0.5	0.0085	0.4		Roof Drain Filter	
WS-LS		1.25	0	0.2	0 150' Long Buffer with Level Spreader 0 150' Long Buffer with Level Spreader	Lot 10 Grass Lot 11 Impervious	0.133	0.3 1.25	0.0399 0.0125	0.4		Rain Garden Rain Garden #4	
Roadway Impervious	0	U 3		0.2	0.05825 150' Long Buffer with Level Spreader	Lot 11 Roof Rear	0.017	0.5	0.0085	0.4		Roof Drain Filter	
	0 0 0.233	0.3 1.25	0.29125	0.2	100 Zong Baner With Zover Oproduce	201 111100111001			0.033	0.4	0.0132	Rain Garden #4	
Roadway Impervious Roadway Pervious	0		-	0.2	0.0067 150' Long Buffer with Level Spreader	Lot 11 Grass	0.11	0.3	0.000		1		
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious	0 0.233	1.25	0.29125			Lot 11 Grass Lot 12 Impervious	0.043	1.25	0.05375	0.4		Rain Garden #4	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD	0 0.233 0.067	1.25 0.5	0.29125 0.0335 0.036	0.2	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader	Lot 11 Grass				0.4 0.4 0.4	0.0034	Rain Garden #4 Rain Garden #4 Roof Drain Filter	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious	0 0.233 0.067 0.12	1.25 0.5 0.3	0.29125	0.2	0.0067 150' Long Buffer with Level Spreader	Lot 11 Grass Lot 12 Impervious Lot 12 Roof	0.043 0.017	1.25 0.5	0.05375 0.0085	0.4	0.0034 0.0034	Rain Garden #4	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious	0 0.233 0.067 0.12 0.067	1.25 0.5 0.3 0.5	0.29125 0.0335 0.036 0.0335	0.2 0.2 0.4 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious	0.043 0.017 0.017 0.172 0.043	1.25 0.5 0.5 0.3 1.25	0.05375 0.0085 0.0085 0.0516 0.05375	0.4 0.4 0.4 0.27	0.0034 0.0034 0.02064 0.0145125	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof	0 0.233 0.067 0.12 0.067	1.25 0.5 0.3 0.5 1.25 0.5	0.29125 0.0335 0.036 0.0335 0.05375 0.0085	0.2 0.2 0.4 0.25 0.16	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof	0.043 0.017 0.017 0.172 0.043 0.017	1.25 0.5 0.5 0.3 1.25 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085	0.4 0.4 0.4 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious	0 0.233 0.067 0.12 0.067	1.25 0.5 0.3 0.5	0.29125 0.0335 0.036 0.0335	0.2 0.2 0.4 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious	0.043 0.017 0.017 0.172 0.043	1.25 0.5 0.5 0.3 1.25	0.05375 0.0085 0.0085 0.0516 0.05375	0.4 0.4 0.4 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Roof (Rear)	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.5	0.29125 0.0335 0.036 0.0335 0.05375 0.0085 0.0085	0.2 0.4 0.25 0.16 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 14 Impervious	0.043 0.017 0.017 0.172 0.043 0.017 0.017 0.172 0.043	1.25 0.5 0.5 0.3 1.25 0.5 0.5 0.3 1.25	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0085 0.0516 0.05375	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof	0 0.233 0.067 0.12 0.067 0.043 0.017 0.126 0.043 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.3 1.25 0.5	0.29125 0.0335 0.036 0.0335 0.05375 0.0085 0.0378 0.05375 0.0085	0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.00945 Gravel Wetland 0.0134375 Gravel Wetland 0.00134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 14 Roof	0.043 0.017 0.017 0.172 0.043 0.017 0.172 0.043 0.017	1.25 0.5 0.5 0.3 1.25 0.5 0.5 0.3 1.25 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0085 0.05375 0.0085	0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 2 Roof Lot 2 Roof Lot 2 Roof (Rear)	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.126 0.043	1.25 0.5 0.3 0.5 1.25 0.5 0.5 0.3 1.25	0.29125 0.0335 0.036 0.0335 0.05375 0.0085 0.0085 0.0378 0.05375	0.2 0.4 0.25 0.16 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.00945 Gravel Wetland 0.0134375 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 14 Impervious	0.043 0.017 0.017 0.172 0.043 0.017 0.017 0.172 0.043	1.25 0.5 0.5 0.3 1.25 0.5 0.5 0.3 1.25	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0085 0.0516 0.05375	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof	0 0.233 0.067 0.12 0.067 0.043 0.017 0.126 0.043 0.017 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.3 1.25 0.5 0.5	0.29125 0.0335 0.036 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085	0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.25 0.16	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Lot 14 Grass Lot 14 Grass Lot 15 Impervious	0.043 0.017 0.017 0.172 0.043 0.017 0.172 0.043 0.017 0.017	1.25 0.5 0.5 0.3 1.25 0.5 0.3 1.25 0.5 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0516 0.05375 0.0085 0.0085	0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof Lot 2 Roof Lot 2 Roof (Rear) Lot 3 Grass Lot 3 Impervious Lot 3 Roof	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.018 0.017 0.017 0.017 0.069 0.043 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.3 1.25 0.5 0.3 1.25 0.5	0.29125 0.0335 0.0335 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085	0.2 0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.16 0.25 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.005175 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Lot 15 Roof	0.043 0.017 0.017 0.172 0.043 0.017 0.172 0.043 0.017 0.017 0.161 0.043 0.017	1.25 0.5 0.5 0.3 1.25 0.5 0.3 1.25 0.5 0.5 0.5 0.5 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0516 0.05375 0.0085 0.0085 0.0085 0.0085	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.17 0.27 0.27 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041 0.0145125 0.002295	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof Lot 2 Roof Lot 2 Roof Lot 3 Roof (Rear)	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.017 0.017 0.069 0.043 0.017 0.069	1.25 0.5 0.3 0.5 1.25 0.5 0.5 0.5 0.5 0.5 0.5 0.5 0.	0.29125 0.0335 0.036 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085	0.2 0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.16 0.25 0.25 0.25 0.16	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.005175 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Lot 14 Grass Lot 14 Grass Lot 15 Impervious	0.043 0.017 0.017 0.172 0.043 0.017 0.172 0.043 0.017 0.017 0.017 0.0161 0.043	1.25 0.5 0.5 0.3 1.25 0.5 0.3 1.25 0.5 0.5 0.5 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0085 0.05375 0.0085 0.0085 0.0085 0.0085	0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.17 0.27 0.17 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041 0.0145125 0.002295 0.001445	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof Lot 2 Roof Lot 2 Roof (Rear) Lot 3 Grass Lot 3 Impervious Lot 3 Roof	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.018 0.017 0.017 0.017 0.069 0.043 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.3 1.25 0.5 0.3 1.25 0.5	0.29125 0.0335 0.0335 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085 0.0085	0.2 0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.16 0.25 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.005175 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Rear Lot 15 Impervious Lot 15 Roof Lot 15 Roof Rear	0.043 0.017 0.017 0.172 0.043 0.017 0.017 0.043 0.017 0.0161 0.043 0.017 0.017	1.25 0.5 0.5 0.3 1.25 0.5 0.3 1.25 0.5 0.5 0.5 0.5 0.5 0.3 1.25 0.5	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0516 0.05375 0.0085 0.0483 0.05375 0.0085 0.0483 0.05375	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.17 0.27 0.17 0.27 0.27 0.27 0.27 0.27	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041 0.0145125 0.002295 0.001445	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof Lot 1 Grass Lot 2 Impervious Lot 2 Roof Lot 2 Roof Lot 2 Roof Lot 3 Grass	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.018 0.017 0.069 0.043 0.017 0.069 0.043 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.5 0.5 0.5 0.5 0.5 0.5 0.	0.29125 0.0335 0.036 0.0335 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085 0.0207 0.05375 0.0085 0.0085 0.0085	0.2 0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.16 0.25 0.25 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.005175 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.00945 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Rear Lot 15 Impervious Lot 15 Roof Lot 15 Roof Rear	0.043 0.017 0.017 0.172 0.043 0.017 0.017 0.043 0.017 0.0161 0.043 0.017 0.017	1.25	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0516 0.05375 0.0085 0.0483 0.05375 0.0085 0.0483 0.05375	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.17 0.27 0.17 0.27 0.27 Total PostPPE	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041 0.0145125 0.002295 0.001445 0.00648	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	
Roadway Impervious Roadway Pervious Apartment Impervious Apartment Roof Apartment Pervious WS-RD Apartments Roof Ots to Gravel Wetland Lot 1 Impervious Lot 1 Roof Lot 1 Roof (Rear) Lot 2 Impervious Lot 2 Roof Lot 2 Roof (Rear) Lot 2 Grass Lot 3 Impervious Lot 3 Roof Lot 3 Roof Lot 3 Roof (Rear) Lot 3 Grass Lot 4 Impervious	0 0.233 0.067 0.12 0.067 0.043 0.017 0.017 0.017 0.017 0.069 0.043 0.017 0.069 0.043 0.017 0.017	1.25 0.5 0.3 0.5 1.25 0.5 0.3 1.25 0.5 0.3 1.25 0.5 0.3 1.25 0.5	0.29125 0.0335 0.036 0.0335 0.0335 0.05375 0.0085 0.0085 0.0085 0.0085 0.0207 0.05375 0.0085 0.0085 0.0085	0.2 0.2 0.4 0.25 0.16 0.25 0.25 0.25 0.25 0.25 0.25 0.25 0.25 0.25 0.25	0.0067 150' Long Buffer with Level Spreader 0.0072 150' Long Buffer with Level Spreader 0.0134 Roof Drain Filter 0.0134375 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.002125 Gravel Wetland 0.0134375 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.005175 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.002125 Gravel Wetland 0.00136 Gravel Wetland + Roof Filter 0.00136 Gravel Wetland 0.00137 Gravel Wetland 0.00138 Gravel Wetland 0.00139 Gravel Wetland 0.00134375 Gravel Wetland	Lot 11 Grass Lot 12 Impervious Lot 12 Roof Lot 12 Roof Rear Lot 12 Grass Lot 13 Impervious Lot 13 Roof Lot 13 Roof Rear Lot 13 Grass Lot 14 Impervious Lot 14 Roof Lot 14 Roof Rear Lot 15 Impervious Lot 15 Roof Lot 15 Roof Rear	0.043 0.017 0.017 0.172 0.043 0.017 0.017 0.043 0.017 0.0161 0.043 0.017 0.017	1.25	0.05375 0.0085 0.0085 0.0516 0.05375 0.0085 0.0516 0.05375 0.0085 0.0085 0.0085 0.0085 0.0085 0.0483 0.05375 0.0085 0.0085	0.4 0.4 0.4 0.27 0.27 0.17 0.27 0.27 0.17 0.27 0.17 0.27 0.27 Total	0.0034 0.0034 0.02064 0.0145125 0.002295 0.001445 0.013932 0.0145125 0.002295 0.001445 0.013041 0.0145125 0.002295 0.001445 0.00648	Rain Garden #4 Roof Drain Filter Rain Garden #4 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C 100' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer + Roof Filter 110' Forested Buffer, HSG C 110' Forested Buffer, HSG C	



Observation Hole # Test Pit Boring


" Depth of organic horizon above mineral soil


•	Texture	Consistency	Color	Mottling		25	Texture	Consistency	1 0-1	1
°F			DARK		1	0	Availab	Consistency	Color	Mottling
6	SAIR		BRO. W		-	,	FINE		DARK	
12 18 24 30 36 36 42 42 42 42 42 42 42 42 42 42 42 42 42	com'		2000		Depth below mineral soil surface (inches)	6	SAND	60.00	BROWN	
12			DEN		i i	12	1.041	FRIABLE		
inco			I ALV		ge	14	ONSTRE		Vero 1	
18			BROWN		l I	18			YELLOW	
NOS -		LOOSE			1 1		VERI	FIRM	BROWN	COMMO
24		LOUDE			120	24		1	10	
í F	1.04				iner		FINE		OUNE	
30	DAMY		YELLOW	Approximately and the second	H A	30	SAID		SELIO!	
3	SANT	 	BROWN	NONE	No No		2777		100-1	
36			TO	740/00	h bo	36		 	BROWN	
42			CRALL		cht				ļ	- //
-	***************************************		BROWN		Η Α	42	P	IT DEP	M = -4	8
48	9.11					48	· · · · · ·			
		ificatioin Slope	Limiting Factor	☐ Groundwater		40	Soil Classi	ificatioin Slope	Limiting Factor	Groundwate
L.	5 6			☐ Restrictive Layer ☐ Bedrock		1	7 0		16	Restrictive L
	Profile Cor	ndition Percent	Depth	☐ Pit Depth			Profile Con	dition Percer		☐ Bedrock ☐ Pit Depth
Observa	ration Hole #	72-16	☑ Test Pit	☐ Boring	0	bser	vation Hole #_	TP-17	Test Pit	
Observ:	ration Hole #	1	I Test Pit		0	bser	vation Hole #_		Test Pit	
Observ:	ation Hole # _ " Texture	1			0)bser				neral soil
°E	"	Depth of organic	horizon above min	eral soil	-			Depth of organic	horizon above mir	neral soil
°E	"	Depth of organic	horizon above min	eral soil	_			Depth of organic	horizon above mir	neral soil
°E	"	Depth of organic	horizon above min	eral soil	_	0		Depth of organic	horizon above mir	neral soil
°E	Texture	Depth of organic Consistency	horizon above min	eral soil	_	0	Texture TANE	Depth of organic	Color	neral soil
°E	Texture	Depth of organic Consistency	horizon above min	Mottling	_	0 6 12		Depth of organic	Color	neral soil
°E	Texture	Depth of organic Consistency	horizon above min	eral soil	_	0	Texture TANE	Depth of organic	horizon above mir	neral soil
°E	Texture SAND/ LO/M SILT	Depth of organic Consistency	Color Color Color Color	Mottling	_	0 6 12	Texture TANE	Depth of organic	Color	neral soil
°E	Texture	Depth of organic Consistency	Color Color Color Color	Mottling	_	0 6 12	Texture TANE	Depth of organic	Color RED BROWN	Mottling
°E	Texture SAND/ LO/M SILT	Depth of organic Consistency	Color Color Color Color	Mottling COMMON	_	0 6 12 18	Texture TANE	Depth of organic	Color Color Brown	Mottling
°E	Texture SAND/ LO/M SILT	Depth of organic Consistency FRIABLE	Color	Mottling COMMON	_	0 6 12	Texture TANE	Depth of organic	Color RED BROWN	Mottling
°E	Texture SAND/ LO/M SILT	Depth of organic Consistency	Color Color Color Color	Mottling	_	0 6 12 18	Texture SAND/ LOAM	Depth of organic	Color Color Brown	Mottling
0 12 18 30 36 17 18 30 36 17 18 18 18 18 18 18 18	Texture SAND/ LO/M SILT	Depth of organic Consistency FRIABLE	Color	Mottling COMMON	_	0 6 12 18 24	Texture SAND/ LOAM	Depth of organic	Color Color Brown	Mottling
0 6 6 12 12 18 18 18 18 18 18 18 18 18 18 18 18 18	Texture SAND/ LO/M SILT	Depth of organic Consistency FRIABLE	Color	Mottling COMMON	Depth below mineral soil surface (inches)	0 6 12 18 24	Texture FANCE SAND/ LOMM SILV SAND/ LOMM SILV SAND/ LOMM SILV SILV	Depth of organic	Color Color Brown	Mottling
0 6 6 6 12 12 13 18 13 14 14 14 14 14 14 14 14 14 14 14 14 14	Texture SAND/ LO/M SILT	Depth of organic Consistency FRIABLE	Color	Mottling COMMON	_	0 6 12 18 24 30 36 42	Texture SAND/ LOMM SILV SAND/ COMM	Depth of organic	Color Color Brown	Mottling
0 12 18 30 36 17 18 30 36 17 18 18 18 18 18 18 18	Texture SAND/ LO/M SILT LOAM	Depth of organic Consistency RIABLE	Color Color RED ROWN CIPAL TOPAL TOPAL	Mottling COMMON	_	0 6 12 18 24 30	Texture FAND/ LOMM SILM SAND/ LOMM SILM COMM SILM COMM	Depth of organic Consistency	Color RED BROWN	Mottling Commo
0 6 6 12 12 13 18 18 12 24 14 30 36 42 42 48 48	Texture SAND LOM SICT LOAM Soil Class	Depth of organic Consistency RIABIE PIT DI	Color Co	Mottling OMMOA Groundwater Restrictive Layer	_	0 6 12 18 24 30 36 42	Texture TAND LOAM SLIN SAND LOAM SOIL Soil Classi	Depth of organic	Color Color BROWN Limiting Factor	Mottling Comme
0 6 6 12 12 13 18 18 12 24 14 30 36 42 42 48 48	Texture SAND LOM SICT LOAM Soil Class	Depth of organic Consistency RIABLE PIT Definition Slope	Color Co	Mottling COMMON Croundwater Restrictive Layer Bedrock	_	0 6 12 18 24 30 36 42	Texture SAND/ LOMM SAND/ LOMM SAND/ LOMM SOIL Classing	Depth of organic Consistency Fig. 14B4 Fig. 14B4	Color Color BROWN Limiting Factor	Mottling Groundwate Groundwate Groundwate Groundwate Groundwate
0 6 6 12 12 13 18 18 12 24 14 30 36 42 42 48 48	Texture SAND/ LO/M SILT LOAM Soil Class 8	Depth of organic Consistency RIABLE	Color Co	Mottling COMMON Croundwater Restrictive Layer Bedrock Pit Depth	Depth below mineral soil surface (notes)	0 6 12 18 24 30 36 42	Texture SAND/ COMM Soil Class Copple Copple Soil Class Copple	Depth of organic Consistency	Color Color BROWN Limiting Factor	Mottling Committee
0 6 12 18 18 19 19 19 19 19 19	Texture SAND COAM Soil Class Profile Cor	Depth of organic Consistency RIABLE PIT Definition Slope	Color Co	Mottling COMMON Croundwater Restrictive Layer Bedrock Pit Depth	_	0 6 12 18 24 30 36 42	Texture SANDA SANDA COMM Soil Classi Profile Con	Depth of organic Consistency Fig. 14B4 Fig. 14B4	Color Color BROWN Limiting Factor	Mottling Mottling

HIGHLAND VIEW MANUFACURED HOUSING, WINDHAM 1-5.17

Observation Hole # TP- | Test Pit | Boring

______ Depth of organic horizon above mineral soil





	'// _/	, ///	9 _N ,	AL III	1111	111	``		
SI	GN/	۱TU	RE [DAT	E: 1	/10/2	2017	7	
								APP'D BY	
								REVISIONS	
								DATE	
								NO.	
	39	je	00		[]	m		ermitting	

SHEET DESCRIPTION
HIGHLAND VIEWS
19 ROOSEVELT TRAIL, WINDHAM, ME
POST DEVELOPMENT WATERSHED MAP
PREPARED FOR
CHASE CUSTOM HOMES & FINANCE
290 BRIDGTON ROAD
WESTBROOK, MAINE, 04092

NTS JDA

DATE: 1/10/2017 SCALE: DESIGNED: JOB NO: 1636 FILE: 1636 S C-8.2



March 31, 2017

Mr. Jonathan R. Earle, Town Engineer Town of Windham Planning Department 8 School Road Windham, ME 04062

Comment Response: Highland Views Subdivision

Mr. Earle:

In response to your recent review of the Highland Views project, we would like to offer the following responses:

- 1. Your response to Comment 12 indicates that the 24 manufactured housing lots will be served by a private waste hauler that will provide curbside pick. I would suggest providing the Board with evidence of an agreement with a private hauler. The Town has experienced issues recently on with private roads bringing their trash to the nearest public road intersection, sometimes causing issues with sight distances, traffic, and safety.
 - The applicant intends upon providing for private curb side pickup and is currently soliciting waste haulers. We will provide you a copy of the agreement prior to final approval.
- 2. Reference the installation of roof dripline filter beds on sheet C8.1. The filter beds are called out on the signature/approval plan, but noting this on the post-development watershed plan would provide additional clarification.
 - We've added the entire Stormwater Restrictions note from the subdivision plan to Sheet C8.1.
- **3.** Similarly, the forested buffer is shaded on the C8.1, but is not called out with a note or referenced in the legend.
 - The forested buffers are now labeled on C8.1. I've also added the buffer hatching to the sheet legend.
- **4.** The level spreader on sheet C8.1 scales to 20' but is called out as 30' on the grading plan. Please clarify.
 - We have labeled the level spreaders on C8.1. Additionally, sheets C8.0 & C8.1 included incorrect graphical scales. We've corrected the scale.

5. Phosphorous budget calculations – Worksheet 1 indicates there are no wetlands in the Windham portion of the project. The plans are showing a small amount of wetland acreage in Windham, which would slightly decrease the phosphorous budget for the project.

MDEP methodology stipulates that only that NWI wetlands be deducted. The small forested wetlands are not shown on the NWI map. The NWI wetlands were used by MDEP in generating the per acre allocation. On one past occasion, I was told by the MDEP program coordinator to deduct an area of NWI wetlands from a project even though there were not actually wetlands on the ground. So, NWI wetlands are deducted whether or not they are accurately located on the map.

6. Predevelopment stormwater plan & calculations — On sheet C8.0, there is a time of concentration segment at the end of the flow path calling out 150' of shallow concentrated flow that's not show in the modelling. Please clarify.

We have removed the corrected in inconsistency & updated the plan with the correct Tc path & label.

We received a comment from MDEP about the development area and the lot impervious allowance has been slightly reduced & the corresponding amount of landscaping area has been added to the phosphorus calculations. The updated calculations area shown in their entirety on C8.2 (see attached). The changes resulted in a small decrease in phosphorus production.

We hope that these responses addresses your concerns. Please contact me directly with additional questions or concerns.

