# COOK ROAD RETIREMENT COMMUNITY GRAY ROAD, WINDHAM, MAINE SHEET INDEX **COVER SHEET & LOCATION MAP** C-0.0

## **PREPARED BY:**

**CIVIL ENGINEER:** TERRADYN CONSULTANTS, LLC 41 CAMPUS DR. SUITE 101 NEW GLOUCESTER, MAINE 04260 (207)926-5111

SURVEYOR: WAYNE T. WOOD & CO. 30 WOOD DRIVE GRAY, MAINE 04039 (207) 657-3330

SEPTIC EVALUATION: SUMMIT ENGINEERING SERVICES 145 LISBON STREET, SUITE 701 LEWISTON, MAINE 04240 (207)576-3313

## **APPLICANT / OWNER:**

JAMES CUMMINGS P.O. BOX 957 WINDHAM, MAINE 04062

# **PROJECT PARCEL SITE**

TOWN OF WINDHAM TAX ASSESSOR'S MAP & LOT NUMBERS <u>MAP</u> 9 LOT 5



# **PRELIMINARY - NOT FOR CONSTRUCTION**



11/18/2018

LRB

1841

C-0.0

DATE:

SCALE: DESIGNED:

JOB NO:

FILE:

SHEET

PROPOSED SETBACK LINE EXISTING SETBACK LINE EXISTING EASEMENT PROPOSED EASEMEN ROAD CENTERLINE **EXISTING MINOR CONTOUR** EXISTING MAJOR CONTOUR PROPOSED CONTOUR EXISTING STORMDRAIN PROPOSED STORMDRAIN **EXISTING SANITARY SEWER** PROPOSED SANITARY SEWEI EXISTING WATER LINE PROPOSED WATER LINE EXISTING UNDERDRAIN PROPOSED UNDERDRAIN EXISTING OVERHEAD ELECTRIC & TELEPHONE ------ OHE ------- PROPOSED OVERHEAD ELECTRIC & TELEPHONE ------UGE------ EXISTING UNDERGROUND ELECTRIC & TELEPHONE ----- UGE ----- PROPOSED UNDERGROUND **ELECTRIC & TELEPHONE** EXISTING EDGE OF PAVEMEN PROPOSED EDGE OF PAVEMENT EXISTING EDGE OF GRAVE — — — — — — PROPOSED EDGE OF GRAVE **EXISTING CURB** PROPOSED CURE EDGE OF WATER EXISTING TREE LINE uuuuu PROPOSED TREE LINE CHAIN LINK FENCE PROPOSED FENCE EXISTING GUARDRAIL PROPOSED GUARDRAI SILT FENCE EXISTING VALVE PROPOSED VALVE EXISTING HYDRANT PROPOSED HYDRANT EXISTING TRANSFORMER PROPOSED TRANSFORMER EXISTING LIGHT POLE PROPOSED LIGHT POLE EXISTING UTILITY POLE PROPOSED UTILITY POLE EXISTING CATCH BASIN PROPOSED CATCH BASIN EXISTING SEWER MANHOLE S PROPOSED SEWER MANHOLE EXISTING SPOT GRADE + 30.20 ×30.20 PROPOSED SPOT GRADE EXISTING SIGN PROPOSED SIGN EXISTING BUILDING PROPOSED BUILDING WETLAND AREA <u>Mk</u> PROPOSED PAVEMENT RIPRAP 

S-1.0

C-1.0

C-2.0

C-3.0 C-4.0

C-4.1

C-5.0

C-5.1

C-5.2

C-5.3

C-5.4

LEGEND

SURVEY PLAN OF LAND

UTILITY PLAN

DETAILS

EXISTING PROPERTY LINE

--- PROPOSED PROPERTY LINE

ROADWAY PROFILE

DRAINAGE DETAILS

POND DETAILS & NOTES

POND DETAILS & NOTES

**ROADWAY PROFILES** 

SITE LAYOUT AND LANDSCAPING PLAN

**GRADING & EROSION CONTROL PLAN** 

PROPOSED WETLAND ALTERATION AREA



k No



## HOUSEKEEPING NOTES:

- 1. SPILL PREVENTION. CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS ON SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER. AND APPROPRIATE SPILL PREVENTION. CONTAINMENT, AND RESPONSE PLANNING AND IMPLEMENTATION.
- OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE
- FUGITIVE SEDIMENT AND DUST. ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL.
- TO STORMWATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
- 5. TRENCH OR FOUNDATION DE-WATERING. TRENCH DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES, FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT AND SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER MUST BE REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, AND MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. EQUIVALENT MEASURES MAY BE TAKEN IF APPROVED BY THE DEPARTMENT.
- D. NON-STORMWATER DISCHARGES. IDENTIFY AND PREVENT CONTAMINATION BY
- 7. ADDITIONAL REQUIREMENTS. ADDITIONAL REQUIREMENTS MAY BE APPLIED ON A SITE-SPECIFIC BASIS.

### 4. SPACE AND BULK CRITERIA:

FARM ZONE WITH RET	IREME	ENT CO	омми	NITY AND CARE FACIL
MIN. LOT SIZE: .			-	200,000 SF
NET RESIDENTIAL DE	NSITY:		-	5,000 SF/UNIT
MIN. FRONTAGE: .			-	200'
MIN. FRONT SETBACK	:.		-	40'
MIN. FRONT SETBACK	(MULT	IFAMI	LY):	100' (BUILDING HEIGH
	•			150' (BUILDING HEIGH
MIN. SIDE SETBACK:			-	10'
MIN. REAR SETBACK:			-	10'
MAX. BUILDING HEIGH	IT:		-	35'
MAX. BUILDING COVEI	RAGE:		-	25%



# **PRELIMINARY - NOT FOR CONSTRUCTION**

## CONSTRUCTION NOTES

1. All work shall conform to the applicable codes and ordinances.

2. Contractor shall visit the site and familiarize him or herself with all conditions affecting the proposed work and shall make provisions as to the cost thereof. Contractor shall be responsible for familiarizing him or herself with all contract documents, field conditions and dimensions and confirming that the work may be accomplished as shown prior to proceeding with construction. Any discrepancies shall be brought to the attention of the engineer prior to the commencement of work.

3. Contractor shall notify engineer of all products or items noted as "existing" which are not found in the field.

4. Install all equipment and materials in accordance with manufacturer's recommendations and owner's requirements unless specifically otherwise indicated or where local codes or regulations take precedence.

5. Contractor shall verify all dimensions and conditions in the field prior to fabrication and erection of any material. Any unusual conditions shall be reported to the attention of the engineer.

6. Contractor shall clean and remove debris and sediment deposited on public streets, sidewalks, adjacent areas, or other public ways due to construction.

7. Contractor shall incorporate provisions as necessary in construction to protect existing structures, physical features, and maintain site stability during construction. Contractor shall restore all areas to original condition and as directed by design drawings.

8. Site contractor shall obtain all required permits prior to construction.

9. All erosion and sediment control measures shall be installed in accordance with "maine erosion and sedimentation control handbook for construction: best management practices" published by the cumberland county soil and water conservation district and maine department of environmental protection, march 2004 or latest edition. It shall be the responsibility of the contractor to possess a copy of the erosion control plan at all times

10. The contractor is hereby cautioned that all site features shown hereon are based on field observations by the surveyor and by information provided by utility companies. The information is not to be relied on as being exact or complete. The contractor shall contact dig safe (1-888-digsafe) at least three (3) but not more than thirty (30) days prior to commencement of excavation or demolition to verify horizontal and vertical location of all utilities.

11. Contractor shall be aware that dig safe only notifies its "member" utilities about the dig. When notified, dig safe will advise contractor of member utilities in the area. Contractor is responsible for identifying and contacting non-member utilities directly. Non-member utilities may include town or city water and sewer districts and small local utilities, as well as usg public works systems.

12. Contractors shall be responsible for compliance with the requirements of 23 mrsa 3360-a. It shall be the responsibility of the contractor to coordinate with the appropriate utilities to obtain authorization prior to relocation of any existing utilities which conflict with the proposed improvements shown on these plans. If a utility conflict arises, the contractor shall immediately notify the owner, the municipality and appropriate utility company prior to proceeding with any relocation.

13. All pavement markings and directional signage shown on the plan shall conform to the manual of uniform traffic control devices (mutcd) standards.

14. All pavement joints shall be sawcut prior to paving to provide a durable and uniform joint.

15. No holes, trenches or structures shall be left open overnight in any excavation accessible to the public or in public rights-of-way.

16. All work within the public right-of-way shall require a M.D.O.T. Permit as well as permits from the town as applicable.

17. The proposed limits of clearing shown hereon are approximate based upon the proposed limits of site grading. The applicant reserves the right to perform normal forest management activities outside of the clearing limit as shown. Tree removal outside of the limits of clearing may be necessary to remove dead or dying trees or tree limbs. This removal is due to potential safety hazards and to promote proper forest growth.

18. Immediately upon completion of cuts/fills, the contractor shall stabilize disturbed areas in accordance with erosion control notes and as specified on plans.

### POND DEWATERING NOTES

- DEWATERING OF THE FOREBAY AND FILTER AREA OF THE POND SHALL BE CONDUCTED SUCH THAT THE POND WILL NOT FILL WITH WATER UNTIL THE FOREBA & FILTER AREA FLOORS ARE COMPLETED
- DEWATERING PROCEDURES SHALL BE CONDUCTED USING MDEP APPROVED TECHNIQUES AND SHALL INCLUDE THE USE OF A DIRT BAG SYSTEM. THE DIRT BAG SHALL BE USED ACCORDING TO MANUFACTURER INSTRUCTIONS.

19. The contractor shall be fully and solely responsible for the removal, replacement and rectification of all damaged and defective material and workmanship in connection with the contract work. The contractor shall replace or repair as directed by the owner all such damaged or defective materials which appear within a period of one year from the date of substantial completion.

20. All work performed by the general contractor and/or trade subcontractor shall conform to the requirements of local, state or federal laws, as well as any other governing requirements, whether or not specified on the drawings.

21. Where the terms "approved equal", "other approved", "equal to", "acceptable" or other general qualifying terms are used in these notes, it shall be understood that reference is made to the ruling and judgment of terradyn consultants, llc.

22. The general contractor shall provide all necessary protection for the work until turned over to the

23. The general contractor shall maintain a current and complete set of construction drawings on site during all phases of construction for use of all trades.

24. The contractor shall take full responsibility for any changes and deviation of approved plans not authorized by the architect/engineer and/or client/owner.

25. Details are intended to show end result of design. Any modification to suit field dimension and condition shall be submitted to the engineer for review and approval prior to any work.

26. Before the final acceptance of the project, the contractor shall remove all equipment and materials, repair or replace private or public property which may have been damaged or destroyed during construction, clean the areas within and adjacent to the project which have been obstructed by his/her operations, and leave the project area neat and presentable.

-----

FILTER BASIN #1

(SEE C-5.3 FOR DETAIL

15"SD

L=20'

S'0.01

CB-6 •

STA:-3+84.00

RIM EL=378.72

INV OUT=375.47

SILT

FENCE

POLE

\_#106-

UNITS 1&2

GFE=281.30

FFE=281.30

INV OUT=375.07

**PRELIMINARY - NOT FOR CONSTRUCTION** 



![](_page_4_Picture_1.jpeg)

# PRELIMINARY - NOT FOR CONSTRUCTION

![](_page_5_Figure_1.jpeg)

SCALE: 1"=40' HORIZONTAL 1"=4" VERTICAL

# PROFILE OF HIGH GARDEN DR

JEFREY D. 1016 1016 NAL						
P.E.: JEFF	REY D. /	AMOS		PP'D BY		
				REVISIONS		
				DATE		
				ÖZ		
41 CAMPUS DRIVE 565 CONGRESS S	OFFICE: (207) 926-5111 FAX: (207) 221-1	NG   STORMWATER DESIGN   ENVIRONMENTAL PERM				
TERRADYN Consultants, LLC						
SHEET DESCRIPTION SHEET DESCRIPTION COOK ROAD RETIREMENT COMMUNITY SOG GRAY ROAD 306 GRAY ROAD 306 GRAY ROAD 306 GRAY ROAD 306 GRAY ROAD ROADWAY PROFILE PREPARED FOR DESIGNED: TLA PROFILE PREPARED FOR P.O. BOX 957 WINDHAM, MAINE 04062 P.O. BOX 957 WINDHAM, MAINE 04062						

![](_page_6_Figure_0.jpeg)

![](_page_6_Figure_1.jpeg)

![](_page_6_Figure_3.jpeg)

JEERREY D. HILLING						
DATE: 1	FREY D.	AMOS	PP'D BY			
			REVISIONS			
			DATE			
			ING NO.			
41 CAMPUS DRIVE 565 CONGRESS S	SUITE 101 NEW GLOUCESTER, ME 04260 PORTLAND, ME 02	<b>TERRADYN</b> OFFICE: (207) 926-5111 FAX: (207) 221-1: consultants, LLc www.terradynconsultants.com	CIVIL ENGINEERING   LAND PLANNING   STORMWATER DESIGN   ENVIRONMENTAL PERM			
COOK ROAD RETIREMENT COMMUNITY	306 GRAY ROAD ROADWAY PROFILE	PREPARED FOR MR. JAMES CUMMINGS	VINDHAM, MAINE 04062			

![](_page_7_Figure_0.jpeg)

![](_page_7_Figure_4.jpeg)

### SLIPFORM CURB TIPDOWN DETAIL NOT TO SCALE

![](_page_7_Figure_6.jpeg)

![](_page_7_Figure_7.jpeg)

![](_page_7_Figure_8.jpeg)

![](_page_7_Figure_9.jpeg)

![](_page_8_Figure_0.jpeg)

## EROSION AND SEDIMENT CONTROL PLAN

A PERSON WHO CONDUCTS, OR CAUSES TO BE CONDUCTED, AN ACTIVITY THAT INVOLVES FILLING, DISPLACING OR EXPOSING SOIL OR OTHER EARTHEN MATERIALS SHALL TAKE MEASURES TO PREVENT UNREASONABLE EROSION OF SOIL OR SEDIMENT BEYOND THE PROJECT SITE OR INTO A PROTECTED NATURAL RESOURCE AS DEFINED IN 38 MRSA § 480-B. EROSION CONTROL MEASURES MUST BE IN PLACE BEFORE THE ACTIVITY BEGINS. MEASURES MUST REMAIN IN PLACE AND FUNCTIONAL UNTIL THI SITE IS PERMANENTLY STABILIZED. ADEQUATE AND TIMELY TEMPORARY AND PERMANENT STABILIZATION MEASURES MUST BE TAKEN. THE SITE MUST BE MAINTAINED TO PREVENT UNREASONABLE EROSION AND SEDIMENTATION. MINIMIZE DISTURBED AREAS AND PROTECT NATURAL DOWNGRADIENT BUFFER AREAS TO THE EXTENT PRACTICABLE.

### GENERAL REQUIREMENTS

A. POLLUTION PREVENTION: MINIMIZE DISTURBED AREAS AND PROTECT NATURAL DOWNGRADIENT BUFFER AREAS TO THE EXTENT PRACTICABLE. CONTROL STORMWATER VOLUME AND VELOCITY WITHIN THE SITE TO MINIMIZE SOIL EROSION. MINIMIZE THE DISTURBANCE OF STEEP SLOPES, CONTROL STORMWATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND VOLUME TO MINIMIZE EROSION AT OUTLETS. THE DISCHARGE MAY NOT RESULT IN EROSION OF ANY OPEN DRAINAGE CHANNELS, SWALES, STREAM CHANNELS OR STREAM BANKS, UPLAND, OR COASTAL OR FRESHWATER WETLANDS OFF THE PROJECT SITE.

WHENEVER PRACTICABLE, NO DISTURBANCE ACTIVITIES SHOULD TAKE PLACE WITHIN 50 FEET OF ANY PROTECTED NATURAL RESOURCE. IF DISTURBANCE ACTIVITIES TAKE PLACE BETWEEN 30 FEET AND 50 FEET OF ANY PROTECTED NATURAL RESOURCE. AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED. IF DISTURBANCE ACTIVITIES TAKE PLACE LESS THAN 30 FEET FROM ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED AND DISTURBED AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED WITHIN 7 DAYS.

A. SEDIMENT BARRIERS. PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, PROPERLY INSTALL SEDIMENT BARRIERS AT THE EDGE OF ANY DOWNGRADIENT DISTURBED AREA AND ADJACENT TO ANY DRAINAGE CHANNELS WITHIN THE PROPOSED DISTURBED AREA. MAINTAIN THE SEDIMENT BARRIERS UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED.

B. CONSTRUCTION ENTRANCE: PRIOR TO ANY CLEARING OR GRUBBING, A CONSTRUCTION ENTRANCE SHALL BE CONSTRUCTED AT THE INTERSECTION WITH THE PROPOSED ACCESS DRIVE AND THE EXISTING ROADWAY TO AVOID TRACKING OF MUD, DUST AND DEBRIS FROM THE SITE.

C. INLET PROTECTION: PRIOR TO DISTURBANCE, INSTALL SILT SACK SEDIMENT BARRIERS OR OTHER INLET PROTECTION AT CATCH BASIN INLETS RECEIVING RUNOFF FROM DISTURBED AREAS. INLET PROTECTION SHALL BE INSPECTED WEEKLY AND SEDIMENT SHALL BE REMOVED AND LEGALLY DISPOSED OF WHEN IT REACHES 1/2 OF THE HEIGHT OR DEPTH OF THE BARRIER.

D. RIPRAP: SINCE RIPRAP IS USED WHERE EROSION POTENTIAL IS HIGH. CONSTRUCTION MUST BE SEQUENCED SO THAT THE RIPRAP IS PUT IN PLACE WITH THE MINIMUM DELAY. DISTURBANCE OF AREAS WHERE RIPRAP IS TO BE PLACED SHOULD BE LINDERTAKEN ONLY WHEN FINAL PREPARATION AND PLACEMENT OF THE RIPRAP CAN FOLLOW IMMEDIATELY BEHIND THE INITIAL DISTURBANCE. WHERE RIPRAP IS USED FOR OUTLET PROTECTION, THE RIPRAP SHOULD BE PLACED BEFORE OR IN CONJUNCTION WITH THE CONSTRUCTION OF THE PIPE OR CHANNEL SO THAT IT IS IN PLACE WHEN THE PIPE OR CHANNEL BEGINS TO OPERATE. MAINTAIN TEMPORARY RIPRAP, SUCH AS TEMPORARY CHECK DAMS UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED.

E. TEMPORARY STABILIZATION. STABILIZE WITH TEMPORARY SEEDING, MULCH, OR OTHER NON-ERODABLE COVER ANY EXPOSED SOILS THAT WILL REMAIN UNWORKED FOR MORE THAN 7 DAYS EXCEPT, STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OR PRIOR TO A PREDICTED STORM EVENT. WHICHEVER COMES FIRST, IE, HAY OR STRAW MULCH IS USED, THE APPLICATION RATE MUST BE 2 BALES (70-90 POUNDS) PER 1000 SF OR 1.5 TO 2 TONS (90-100 BALES) PER ACRE TO COVER 75 TO 90% OF THE GROUND SURFACE. HAY MULCH MUST BE KEPT MOIST OR ANCHORED TO PREVENT WIND BLOWING. AN EROSION CONTROL BLANKET OR MAT SHALL BE USED AT THE BASE OF GRASSED WATERWAYS, STEEP SLOPES (15% OR GREATER) AND ON ANY DISTURBED SOIL WITHIN 100 FEET OF LAKES, STREAMS AND WETLANDS. GRADING SHALL BE PLANNED SO AS TO MINIMIZE THE LENGTH OF TIME BETWEEN INITIAL SOIL EXPOSURE AND FINAL GRADING. ON LARGE PROJECTS THIS SHOULD BE ACCOMPLISHED BY PHASING THE OPERATION AND COMPLETING THE FIRST PHASE UP TO FINAL GRADING AND SEEDING BEFORE STARTING THE SECOND PHASE, AND SO ON.

F. TEMPORARY SEDIMENT SUMP: THE PROPOSED GRAVEL WETLAND SHALL BE EXCAVATED TO SUBGRADE DEPTH AND USED AS A SEDIMENT SUMP DURING CONSTRUCTION OF THE ROAD. THE RIPRAP SWALE, INTERNAL BERM AND SPILLWAY, EMBANKMENT, AND RIPRAP EMERGENCY SPILLWAY SHALL BE CONSTRUCTED PRIOR TO GRUBBING FOR THE ROADWAY CONSTRUCTION. WHEN THE ROADWAY AND ROADSIDE SWALES ARE STABILIZED, ACCUMULATED SEDIMENT SHALL BE REMOVED FROM THE BASIN, AND THE GRAVEL WETLAND SHALL BE COMPLETED IN ACCORDANCE WITH THE DETAILS LOCATED IN THE PLAN SET. IF THE BASIN MUST BE DEWATERED FOR CONSTRUCTION, SEDIMENT LADEN WATER SHALL BE PUMPED THROUGH A DIRTBAG SEDIMENT REMOVAL DEVICE.

### PERMANENT STABILIZATION

IF AN AREA WILL NOT BE WORKED FOR MORE THAN ONE YEAR OR HAS BEEN BROUGHT TO FINAL GRADE, THEN PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, SOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR ROAD SUB-BASE. PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SODDING, PLANTING, AND SEEDING SO TO AVOID DIE-OFF FROM SUMMER DROUGHT AND FALL FROSTS, NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL-ESTABLISHED WITH 90% COVER BY HEALTHY VEGETATION. IF NECESSARY, AREAS MUST BE REWORKED AND RESTABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPLY TO A PARTICULAR SITE.

A. SEEDED AREAS. FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS AN 90% COVER OF THE DISTURBED AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.

B. SODDED AREAS. FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD ROOTS INTO THE UNDERLYING SOIL WITH NO SLUMPING OF THE SOD OR DIE-OFF.

C. PERMANENT MULCH. FOR MULCHED AREAS. PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. EROSION CONTROL MIX MAY BE USED AS MULCH FOR PERMANENT STABILIZATION ACCORDING TO THE APPROVED APPLICATION RATES AND LIMITATIONS.

H RIPRAP, PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP RIPRAP. FOR AREAS STABILIZED WIT HAVE AN APPROPRIATE BACKING OF A WELL-GRADED GRAVEL OR APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP. DETAILS ARE PROVIDED IN THE PLAN SET.

E. PAVED AREAS. FOR PAVED AREAS, PERMANENT STABILIZATION MEANS THE PLACEMENT OF THE COMPACTED GRAVEL SUBBASE IS COMPLETED.

F. DITCHES, CHANNELS, AND SWALES. FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH A 90% COVER OF HEALTHY VEGETATION, WITH A WELL-GRADED RIPRAP LINING, TURF REINFORCEMENT MAT, OR WITH ANOTHER NON-EROSIVE LINING SUCH AS CONCRETE OR ASPHALT PAVEMENT. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE CHANNEL LINING, UNDERCUTTING OF THE CHANNEL BANKS, OR DOWN-CUTTING OF THE CHANNEL.

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE FOLLOWED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION OF THIS PROJECT

A. ALL TOPSOIL SHALL BE COLLECTED, STOCKPILED, SEEDED WITH RYE AT 3 POUNDS/1,000 SF AND MULCHED, AND REUSED AS REQUIRED. SILT FENCING SHALL BE PLACED DOWN GRADIENT FROM THE STOCKPILED LOAM. STOCKPILE TO BE LOCATED BY DESIGNATION OF THE OWNER AND INSPECTING ENGINEER.

B. THE INSPECTING ENGINEER AT HIS/HER DISCRETION, MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES AND/OR SUPPLEMENTAL VEGETATIVE PROVISIONS TO MAINTAIN STABILITY OF EARTHWORKS AND FINISH GRADED AREAS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND INSTALLING ANY SUPPLEMENTAL MEASURES AS DIRECTED BY THE INSPECTING ENGINEER. FAILURE TO COMPLY WITH THE ENGINEER'S DIRECTIONS WILL RESULT IN DISCONTINUATION OF CONSTRUCTION ACTIVITIES.

C. EROSION CONTROL MESH SHALL BE APPLIED IN ACCORDANCE WITH THE PLANS OVER ALL FINISH SEEDED AREAS AS SPECIFIED ON THE DESIGN PLANS.

D. ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN UNTIL THEY ARE ADEQUATELY STABILIZED.

E. ALL EROSION, AND SEDIMENT CONTROL PRACTICES AND MEASURES SHALL BE CONSTRUCTED, APPLIED AND MAINTAINED IN ACCORDANCE WITH THE DETAILS PROVIDED ON THE PLANS AND MANUFACTURER'S RECOMMENDATIONS. F. AREAS SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 INCHES PRIOR TO PLACEMENT OF TOPSOIL

G. REMOVE ANY TEMPORARY CONTROL MEASURES, SUCH AS SILT FENCE, WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED. REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE.

PERMANENT VEGETATIVE COVER SHOULD BE ESTABLISHED ON DISTURBED AREAS WHERE PERMANENT, LONG LIVED VEGETATIVE COVER IS NEEDED TO STABILIZE THE SOIL, TO REDUCE DAMAGES FROM SEDIMENT AND RUNOFF, AND TO ENHANCE

PERMANENT LAWN SEED MIXTURE SHALL CONTAIN THE FOLLOWING PERCENTAGES OF SEED TYPES:

### 50% BARON BLUEGRASS 35% PENNLAWN FESCUE

THE ENVIRONMENT

15% MANHATTAN II PERENNIAL RYE SEE THE PROJECT SPECIFICATIONS FOR ADDITIONAL SEED REQUIREMENTS.

A. GRADE AS FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION AND ANCHORING, AND MAINTENANCE.

B. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY THE UNIVERSITY OF MAINE SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 800 POUNDS PER ACRE OR 18.4 POUNDS PER 1,000 SQUARE FEET USING 10-20-20 (N-P2O5-K2O) OR EQUIVALENT. APPLY GROUND LIMESTONE (EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB. PER 1,000 SQ. FT).

C. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.D. REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE, CLODS, LUMPS OR OTHER UNSUITABLE MATERIAL.

D. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.

E. PERMANENT SEEDING SHOULD BE MADE 45 DAYS PRIOR TO THE FIRST KILLING FROST OR AS A DORMANT SEEDING WITH MULCH AFTER THE FIRST KILLING FROST AND BEFORE SNOWFALL. WHEN CROWN VETCH IS SEEDED IN LATER SUMMER, AT LEAST 35% OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED). IF SEEDING CANNOT BE DONE WITHIN THE SEEDING DATES, MULCH ACCORDING TO THE TEMPORARY MULCHING BMP AND OVERWINTER STABILIZATION AND CONSTRUCTION TO PROTECT THE SITE

THE AREA SHOULD BE SEEDED AT THE BEGINNING OF THE GROWING SEASON.

CONTROLLED BY ADDITIONAL MEASURES AND RESTRICTIONS.

B. DO NOT EXPOSE SLOPES OR LEAVE SLOPES EXPOSED OVER THE WINTER OR FOR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY PROTECTED WITH MULCH. C. APPLY HAY MULCH AT TWICE THE STANDARD RATE (150 LBS. PER 1,000 SF). THE MULCH MUST BE THICK ENOUGH SUCH THAT

THE GROUND SURFACE WILL NOT BE VISIBLE AND MUST BE ANCHORED D. USE MULCH AND MULCH NETTING OR AN EROSION CONTROL MULCH BLANKET OR ALL SLOPES GREATER THAN 8 % OR OTHER AREAS EXPOSED TO DIRECT WIND.

E. INSTALL AN EROSION CONTROL BLANKET IN ALL DRAINAGEWAYS (BOTTOM AND SIDES) WITH A SLOPE GREATER THAN 3 %. F. SEE THE VEGETATION MEASURES FOR MORE INFORMATION ON SEEDING DATES AND TYPES.

G. WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SO THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.

H. AN AREA WITHIN 100 FEET OF A PROTECTED NATURAL RESOURCE MUST BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIFR

I. TEMPORARY MULCH MUST BE APPLIED WITHIN 7 DAYS OF SOIL EXPOSURE OR PRIOR TO ANY STORM EVENT, BUT AFTER EVERY WORKDAY IN AREAS WITHIN 100 FEET FROM A PROTECTED NATURAL RESOURCE.

J. AREAS THAT HAVE BEEN BROUGHT TO FINAL GRADE MUST BE PERMANENTLY MULCHED THAT SAME DAY. K. IF SNOWFALL IS GREATER THAN 1 INCH (FRESH OR CUMULATIVE), THE SNOW SHALL BE REMOVED FROM THE AREAS DUE TO BE SEEDED AND MULCHED.

L. LOAM SHALL BE FREE OF FROZEN CLUMPS BEFORE IT IS APPLIED.

M. ALL VEGETATED DITCH LINES THAT HAVE NOT BEEN STABILIZED BY NOVEMBER 1. OR WILL BE WORKED DURING THE WINTER CONSTRUCTION PERIOD, MUST BE STABILIZED WITH AN APPROPRIATE STONE LINING BACKED BY AN APPROPRIATE GRAVEL BED OR GEOTEXTILE UNLESS SPECIFICALLY RELEASED FROM THIS STANDARD BY THE DEPARTMENT.

MAINTENANCE AND INSPEC A. MINIMUM EROSION CONTROL MEASURES WILL NEED TO BE IMPLEMENTED AND THE APPLICANT WILL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION MUST BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND NEED TO BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. A CONSTRUCTION LOG MUST BE MAINTAINED FOR THE EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE

B. INSPECT DISTURBED AND IMPERVIOUS AREAS, EROSION CONTROL MEASURES, MATERIALS STORAGE AREAS THAT ARE EXPOSED TO PRECIPITATION, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE. INSPECT THESE AREAS AT LEAST ONCE A WEEK AS WELL AS BEFORE AND WITHIN 24 HOURS AFTER A STORM EVENT (RAINFALL), AND PRIOR TO COMPLETING PERMANENT STABILIZATION MEASURES, A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING THE STANDARDS AND CONDITIONS IN THE PERMIT, SHALL CONDUCT THE INSPECTIONS.

C. A LOG (REPORT) MUST BE KEPT SUMMARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS OF THE PERSONNEL MAKING THE INSPECTION. THE DATE(S) OF THE INSPECTION. AND MAJOR OBSERVATIONS RELATING TO OPERATION OF EROSION AND SEDIMENTATION CONTROLS AND POLLUTION PREVENTION MEASURES. MAJOR OBSERVATIONS MUST INCLUDE: BMPS THAT NEED TO BE MAINTAINED; LOCATION(S) OF BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION: AND LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED THAT DID NOT EXIST AT THE TIME OF INSPECTION. FOLLOW-UP TO CORRECT DEFICIENCIES OR ENHANCE CONTROLS MUST ALSO BE INDICATED IN THE LOG AND DATED, INCLUDING WHAT ACTION WAS TAKEN AND WHEN.

THE LOG MUST BE MADE ACCESSIBLE TO DEPARTMENT STAFF AND A COPY MUST BE PROVIDED UPON REQUEST. THE PERMITTEE SHALL RETAIN A COPY OF THE LOG FOR A PERIOD OF AT LEAST THREE YEARS FROM THE COMPLETION OF PERMANENT STABILIZATION.

RESOURCE.

![](_page_9_Figure_55.jpeg)

![](_page_9_Picture_56.jpeg)

LENGTH

PLAN VIEW

DIRTBAG BY ACF ENVIRONMENTAL

- SEAMS MUST BE HIGH STRENGTH DOUBLE STITCHED "J" SEAMS.
- THROUGH A VEGETATED BUFFER AT LEAST 50' UPSTREAM OF WETLAND AREAS.
- BE SITED IN CRITICAL AREAS, SUCH AS WETLANDS.

# EAS AND BACK SLOPES SHALL BE SEEDED AT A RATE OF 3 F, 6% RED TOP, 24% KENTUCKY BLUEGRASS, 10% PERENNIAL FR.

![](_page_9_Figure_62.jpeg)

A. PERMANENT STABILIZATION CONSISTS OF AT LEAST 90% VEGETATION, PAVEMENT/GRAVEL BASE OR RIPRAP.

A DEWATERING PLAN IS NEEDED TO ADDRESS EXCAVATION DE-WATERING FOLLOWING HEAVY RAINFALL EVENTS OR WHERE THE EXCAVATION MAY INTERCEPT THE GROUNDWATER TABLE DURING CONSTRUCTION. THE COLLECTED WATER NEEDS TREATMENT AND A DISCHARGE POINT THAT WILL NOT CAUSE DOWNGRADIENT EROSION AND OFFSITE SEDIMENTATION OR WITHIN A

CRUSHED STONE

AGGREGATE

SEWN IN NECK

HOSE

- 4" PUMP DISCHARGE

![](_page_9_Figure_66.jpeg)

Inspection Notes for Lot Grading and Driveway location Inspections by a professional engineer shall consist of a visit to the site prior to construction to consult with the earthwork contractor and a post construction meeting to confirm grading on lots and for all driveways to ensure runoff is directed according to plans and to oversee the re-stabilization of the lot into a vegetated cover.

INSTALLATION)

**TYPICAL EROSION CONTROL MEASURES** FOR DWELLING UNITS

![](_page_9_Figure_69.jpeg)

1. BURY THE TOP END OF THE MESH MATERIAL IN A 6" TRENCH AND BACKFILL AND TAMP TRENCHING SECURE END WITH STAPLES AT 6" SPACING, 4" DOWN FROM EXPOSED END.

2. FLOW DIRECTION JOINTS TO HAVE UPPER END OF LOWER STRIP BURIED WITH UPPER LAYERS OVERLAPPED 4" AND STAPLED. OVERLAP B OVER A.

3. LATERAL JOINTS TO HAVE 4" OVERLAP OF STRIPS. STAPLE 18" ON CENTER.

4. STAPLE OUTSIDE LATERAL EDGE 2' ON CENTER.

5. WIRE STAPLES TO BE MIN. OF #11 WIRE, 6" LONG & 1-1/2" WIDE. 6. USE NORTH AMERICAN GREEN DS 150 (OR APPROVED EQUAL) ON SLOPES BETWEEN 4:1-2:1. USE NORTH AMERICAN GREEN VMAX SC250 PERMANENT TURF REINFORCEMENT MAT (OR APPROVED EQUAL) ON SLOPES 2:1 AND STEEPER..

> **EROSION CONTROL BLANKET** NOT TO SCALE

![](_page_9_Figure_76.jpeg)

**GRASSED SWALE** 

3. CONSTRUCTION DEWATERING OF TURBID WATER SHALL BE PUMPED THROUGH A DIRTBAG AND RELEASED 4. THE LOCATION OF THE DIRTBAG SHALL BE DETERMINED BY THE CONTRACTOR, BUT SHALL IT SHALL NOT

![](_page_9_Figure_79.jpeg)

![](_page_10_Figure_0.jpeg)

![](_page_10_Picture_23.jpeg)

		INTERNAL	EMERGENCY	2 YR
POND NAME	BOTTOM EL.	BERM EL	SPILLWAY	D
GW #1	274	275.5	275.5	27
GW #2	276	277.5	277.5	27

![](_page_10_Figure_25.jpeg)

![](_page_11_Picture_0.jpeg)

# **PRELIMINARY - NOT FOR CONSTRUCTION**

![](_page_11_Figure_2.jpeg)